

Interactive comment on “An EC-Earth coupled atmosphere-ocean single-column model (AOSCM) for studying coupled marine and polar processes”

by Kerstin Hartung et al.

Anonymous Referee #1

Received and published: 29 June 2018

We would like to thank the anonymous reviewer for the useful feedback.

We have restructured the section describing the model setups and data to better motivate the choice of experiments, their similarities and differences. A table now summarises all main experiments used in this study and also gives a brief overview of sensitivity experiments. We have furthermore corrected typos and adapted suggestions for textual changes. The changes may easily be followed in the attached document containing track changes.

For suggestions requiring more explanations, we provide answers below.

* General comments:

This manuscript describes a new coupled single-column model (SCM) based on one-dimensional (1D) configurations of NEMO ocean and sea-ice model, OpenIFS atmospheric model and OASIS3-MCT coupler. The technical implementation of the coupling between the models is well described and can be used as guidelines for further coupled models developments. It must be noted that SCM are extensively employed to develop and compare ocean and atmospheric models and vertical parameterizations, but independently most of the time. The originality of this work relies on the possibility to couple each component (ocean, sea-ice and atmosphere) in the same 1D framework, and consequently to revisit and to extend the classical SCM approach. The limitations of this approach (horizontal terms are not represented in the SCM equations) are also carefully discussed and different existing solutions (prescribing lateral/vertical advection, geostrophic wind and nudging) are proposed and tested. The authors also give some useful recommendations to carefully design numerical experiments and to check the validity of the SCM results. The originality of the manuscript also relies on the multiple applications created with the coupled SCM at three different latitudes: the tropics (Pirata mooring), midlatitudes (Papa station) and polar regions (ACSE campaign). The sensitivity of the simulations to the different relaxation methods, strength and frequency is also discussed. Hence, the manuscript gives a complete description of what can be expected from a coupled SCM in realistic conditions.

However, despite all these positive aspects, I found the manuscript quality uneven. This is especially true regarding the “Results” part which is poorly constructed and quite difficult to follow. I think this is mainly due to the authors intent to show a too much comprehensive study. The experimental setups and diagnostics are very different at the three locations, so no clear conclusion regarding the SCM behaviour and the relaxation methods can be easily drawn. Consequently, some work is needed to improve this disappointing part in order to get a more globally coherent and qualitative manuscript.

The main objective of our manuscript is to demonstrate the validity and the performance of the newly developed AOSCM.

To this end, we choose to run several sensitivity studies at the three locations presented. At each site, the default simulation is intended to showcase the usability of the model. This is achieved by checking that the model is not exhibiting drifts, by comparison to ocean mooring data and atmospheric reanalysis profiles.

All of the experiments are also intended to analyse potential sensitivity to forcing and model settings as well as to showcase the versatility of the tool. The latter is possible in a more natural way by presenting a broad range of experiments, even though their relationship is not immediately obvious. However, we tried to clarify similarities and differences of the simulations at the three locations.

In addition, we aim to demonstrate the usability of the model by applying it to investigate current scientific questions. This is for example done at the PIRATA location to study why global climate

models produce a warm bias in the tropical cold tongue region of the Atlantic, and at an Arctic location to study the lifecycle of mixed-phase clouds associated with the intrusion of warm and moist air masses. Even though our results can point to interesting scientific analysis it is not our goal here to comprehensively present scientific results but to highlight the application possibilities and potential.

Regarding the general form of the manuscripts, I suggest to merge the setup subsections 2.3.1 to 2.3.3 with the corresponding results subsections (3.1 to 3.3) to avoid any confusion between the three test cases.

By separating setup and results for the three locations, we can compare the motivation between the cases, highlight similarities and point to differences in the setups. The introduction to Section 2.3 is updated (now Section 4.1) to clarify similarities and differences, including the table suggested in one of the specific comments.

We now combine all experiment sections together to highlight their relation.

Most of the figures legends must be completed to get a better description. I also recommend a better usage of punctuation (especially commas) and a proofreading by a native English speaker to improve the manuscript readability.

We asked a native English speaker to check for punctuation, grammar and spelling.

*** Specific comments:**

The section 2.3 structure should be improved by merging specific experimental setup sections (2.3.x) with the corresponding results section (3.x). Some experiments are named (AOSCM-3h, : : :), others are not. An additional table summarising all the experiments can improve the readability of the results section. Please also address the comments and questions in the following section (especially from p.9 to p.16).

We prefer to provide the setup and results separately as this allows us to focus more on similarities and differences in the experiments. In addition, we can motivate all three locations and the experiments performed before going into the results.

We also added Table 1 to Section 2.3 (now Section 4.1) to provide a clearer overview of the experiments. This table also gives the basic model settings used in these simulations.

*** Specific and technical corrections:**

p.3 l.5: “GCSS” acronym is not defined

Yes, “GCSS” stands for GEWEX cloud system study and we now include the definition. In addition, we have added the definition for GEWEX, which was previously missing.

p.3 l.13: “SCM studies” -> please give some references

We have removed the ambiguous reference and restructured the text to clarify all references.

p.3 l.14: please explain why a stably stratified ABL should not be forced by surface fluxes

The paper of Basu et al (2008) describes the problem with using a prescribed sensible heat flux as a boundary conditions for a stably stratified boundary layer. Such a flux is extracting heat from the atmosphere and it can not be ensured that the atmospheric turbulence is able to keep up with the surface flux, which would lead to unrealistic development of the boundary layer. The details can be found in the referenced paper, it would be deviating too much from the subject to discuss it in detail in our manuscript.

p3. l.22: near-surface observations and reanalysis cannot be considered as idealized forcing, please clarify

This should be “using prescribed forcing”.

p.3 l.28-31: can you give more details about the main results achieved by these studies please?

We find it outside the scope of this model development paper to discuss results of these studies, they are referenced mainly to acknowledge previous work along these lines.

p.4 l.10: give reference and link for OASIS3-MCT please

We have included a reference to the official website of OASIS.

p.5 l.23: surface emissivity only concerns the longwave radiation emitted by the surface and not the net surface Lwflux. Please correct the equation.

We have corrected this mistake in the revised version.

p.5 l.26: is there a skin layer conductivity parameterization for the ocean ? If not it could be better to talk about diffusivity for the ocean instead of conductivity.

There is a skin layer parameterization for the ocean, details are provided in Beljaars (1997) and Zeng and Beljaars (2005). Thus, we judge it to be detailed enough in this description to give the surface energy budget equation in a general form, for details we refer to the IFS documentation.

p.5 l.27-28: I don't understand this sentence. Does it mean that the albedo is prognostic ?

The albedo is not a prognostic variable in ASCM, there it is provided as a boundary condition. In AOCSM, it is updated prognostic when sea-ice is present. It should indeed be upward coupling, so we changed the phrasing.

p.6. l.8-9: please add a reference about equation of state formulation

We have added the references Fofonoff and Millard (1983) for EOS-80 and IOC et al. (2010) for TEOS-10.

p.6 l.10: what is the interest to change the equation of state for the 1D ? numerical cost ?

To run the model based on TEOS-10, potential temperature and practical salinity need to be converted to conservative temperature and absolute salinity (which are conservative state variables). This approach does not notably increase the runtime. However, with EOS-80 less preparation of data is required and enhanced accuracy is not as important for the 1D model.

p.6 l.14: please give different time scale variable names for the different components (ocean, atmosphere, ice)

Thank you for this suggestion. We have renamed the timescales tau_a and tau_o.

p.6 l.20: please add Reffray et al. 2015 citation here.

The Reffray et al. (2015) reference is concerned with the PAPA mooring and other references exist in general about mixing parametrizations. We have included a more explicit reference to Reffray et al. (2015) at the beginning of Section 4.1.1.

p.8 l.34: can you give a practical example or reference about this statement please ?

We have added a reference for this statement.

p. 9 l.14: can you give more details or practical recommendations/exemples about the relationship between the horizontal resolution of the host model and the SCM please ?

We added a sentence explaining “The resolution of the forcing is the main scale information applied in the model, apart from potential time-scale settings dependent on the horizontal grid settings”.

p.9 l.24: the computation of the forcing data is not the same depending on the considered experiment and should consequently be moved in the corresponding experiment section.

The method applied to calculate the forcing information is the same for all experiments. Only the forcing frequency, vertical resolution and vertical extent (e.g. cut off above certain height for Arctic case) are specific to the three locations.

We have tried to highlight differences and similarities between simulations more clearly, also by introducing Table 1.

p.9 l.25: can you give explanations/practical reasons about the T511 resolution choice please? And the convective time step

The horizontal resolution is set to T511 to reduce instabilities, occurring due to a too long convective adjustment time scale, which can be found for example in the 2m temperature. The convective adjustment time scale is constant for grids finer than T511 and the choice of the horizontal resolution does not influence other parameters.

We have updated the sentence to read “to T511, mainly reducing the convective adjustment timescale and thereby alleviating instabilities.”

p.9 l.25: “ASCM” acronym is not defined

Now we have defined both “ASCM” and “OSCM” in the general introduction (Sec 4.1).

p.9 l.31: specify that ORAS4 is a reanalysis

We have added this information.

p.10 l.4: satellite chlorophyll climatology is used for Papa only or also in the 2 other locations ? If Papa only, this sentence can be moved in the 2.3.1 section.

Satellite chlorophyll data is used for all three locations. For increased clarity we have added in text “ [...] climatologies are used. For the PAPA location the data is the same as presented in Reffray et al. (2015).”

p.10 l.21: please give the start date of the long simulation

The long simulations are started on the first of the respective month at 18 UTC. This was added to the manuscript.

p.10 l.24-26: what about relative humidity?

Observations of relative humidity have not been used in our study.

p.11 l.5: if all simulations are done with 60 vertical levels, this information can be moved in the general setup section.

Simulations are done on 60 levels for the PAPA and PIRATA locations but in the Arctic the number of levels is increased to 137. This information is now included in Table 1, which is describing the performed experiments.

p.11 l.20: “loosely” ?

We have removed the phrase “loosely”, rewritten the sentence and also added the reference in which the complete setup is described at this point.

p.11 l.27: what is the LES boundary layer height ? is it constant ?

No, it is not constant. The vertical distribution of the forcing, and thus of the boundary layer, is shown in Figure 3 of Sotiropoulou et al. (2018).

p.11 l.28: why vertical advection from ERAI generates unrealistic results ? which kind of results ? please give more details about this point.

The vertical velocity is a difficult parameter to estimate from observations or models, as discussed in Section 2.2. In this particular case, we have observations that indicate that the cloud top height is decreasing in the beginning of the period and then remain constant at about 250 m. The vertical velocity from ERA-Interim is upward for some periods and results in a deeper cloud that is rising to about 1.5 km.

We think that this information does not fit the technical description paper of our model and can further be explained in a later paper.

p.12 l.6: what about the wind conditions associated with the cold advection event ?

Figure 7 shows that the period of weak advection is also associated with relatively weak winds. During the first four days of the considered period the winds at 10 m do not exceed 6 m/s and mostly stay slower than 4 m/s.

p.12 l.15: what can you conclude from the fact that results are similar between AOSCM3h and 6h? Please add a few comments.

We have added the following sentence: “During a period of weak atmospheric advection the frequency with which forcing information is updated is thus not influencing the evolution of the coupled column.”

p.12 l.18-19: can you add in the text the local inertial period at Papa station to compare it with the simulation oscillations please ?

Yes, this is a good idea. We have extended the text by: “At the location of the PAPA mooring the frequency of inertial oscillations is about 16 h.”

p.12 l.27: can you add the reanalysis in Figure 7 please to facilitate the comparison ?

See comment on Figure 7.

p.12 l.30-31: you should add a figure showing this result.

In our study the focus is not on analysing physical phenomena but on demonstrating the model. Therefore, we choose to not present more detail on this result here, so we have added “(not shown)” at the end of this description.

p.12 l.31-32: the fact that nudging improves cloud and LW but deteriorate temperature and LH suggest there is errors compensation in your simulation. This should be stated in the text.

Not necessarily, a mismatch of observations and reanalysis (when the model is strongly nudged) can also indicate that local processes make it difficult to compare gridded and point information. We now mention both potential error sources in the text.

p.13 l.1: what about the skin SST parameterization in ERAI ?

ERA-Interim, as IFS in general, does include both a cool skin and a warm layer parametrizations. The same parametrisations are acting in OIFS cycle 40r1.

p.13 l.10: “sixteen” -> “five” ?!

The results shown in Tables 2 and 3 (new numbers) are mean and standard deviation of the RMSE from 16 29-day experiments which are done for 5 different setups (see new Table 1). The captions for tables 2-3 now include this information more clearly.

p.13 l.14: I think you have inverted “warm” and “cold” in this sentence.

Thank you for pointing out this mismatch. The reference to the months has been switched. Warm periods have a shallow mixed-layer and occur during June-September.

p.13 l.15: “daily-mean” -> “observed daily-mean”

SST data used for ERA-Interim is not just based on observations but also including some post-processing, even data assimilation for some periods (Dee et al., 2011). These SST fields are also used here.

p.14 l.18-19: You cannot conclude that just by looking at the surface total heat flux in Fig. 8. A surface heat budget is needed for that.

We calculated the total surface energy budget (see equation (5) in the manuscript), which consists of the turbulent and radiative fluxes. We added the reference to the equation in the revision.

p.14 l.22-23: a timeseries with observed and simulated precipitations would be more convincing than Fig. 8b.

Accumulated precipitation reduces the noise compared to resolving the time series temporally. In addition, we are not interested if the timing and strength of each precipitation event is correctly modelled but just if the overall mass flux to the ocean is comparable.

p.15 l.34 – p.16 l.1: can you explain why the cloud formation is different from the LES ? Is it because the subsidence is not represented in the model ? If yes, why not force the model with a negative vertical velocity ?

The subsidence in the atmospheric component of the AOSCM is implemented in the same way as it is applied in the LES. The grid is coarser in the SCM, which gives a slightly different representation of the vertical distribution of heat and moisture, which gives a cloud with slightly more water in the AOSCM. Another difference is that whenever a cloud is formed in the LES, the region becomes turbulent due to radiative cooling. That process is not represented the same way in the IFS and may lead to subtle differences which then gives a different evolution. These detailed discussions are outside the scope of the present manuscript. They will be discussed in subsequent papers when the tool is used to answer questions on how the parameterisations interact and are able – or not – to capture observed evolutions.

p.16 l.10: the liquid water path is integrated over the entire atmosphere height ?

Yes, the integrated LWP is calculated over the depth of the atmosphere, however, during the period only low-level clouds are contributing.

p.16 l.22-23: is there any observations for the surface albedo ? if yes, can you validate your model albedo ? or directly use the observed albedo in your simulations ?

During ACSE, no albedo observations were made since that is not possible to do from a ship. Other sources of albedo for the location and time are discussed in Sotriopoulou et al. (2018). A longer discussion on this topic will be part of a later paper.

p.17 l.12: “infrequent”: not sure if this the correct word to describe low-frequency forcing or the problems related to inertial frequency forcing

We changed the phrasing to be “temporally coarser data”.

p.18 (should be page 17) l.26: you recommend pressure gradient forcing without testing it directly. It would be better to present it as a promising possibility that need to be tested.

We motivate pressure gradient forcing from a physical point of view on page 8 ll 15 (location in previous manuscript). However, it is correct that we do not present results from sensitivity experiments without pressure gradient forcing. We extend this sentence as “Based on the fluid dynamical theory and our results [...]”.

* Figures comments:

Figure 1: please detail the acronyms such as “GWD”, : : :

Yes, this is a good suggestion. We have removed all acronyms in figures 1-3.

Figure 4: This schematic is confusing because LIM3 is a part of NEMO. Perhaps A big “NEMO” box with inside 2 small boxes such as “OPA” and “LIM3” would be easier to understand.

We have updated the figure as suggested.

Table 2: a “Table 3” with oceanic RMSE would be interesting

Oceanic RMSE are very similar and not differing more than one standard deviation (calculated from 16 cases) between setups (5 different experiments). Therefore, we do not show this table. However, we now include a brief comment on this in Section 4.2.2.

Figure 6:

- Should be moved before Tables 1-2

Yes, we moved two of the PAPA result figures ahead of the tables. Note that at this stage figures might not be in the correct order because latex is optimising page space.

- A third panel showing data from ERAi and Papa mooring would greatly improve this figure.

Information from ERA-Interim is included in the difference maps on the top row. The bottom row includes ocean profiling information in the difference. Surface information from the PAPA mooring does not fit into this figure and is instead shown in Figure 7.

- Color bars are missing

This figure presents the values on the contour lines instead of through a colour bar, which would add more components to this complex figure.

- The initial mooring data appears to be missing in the figure, how do you initialize the ocean model if so ?

- Why are mooring oceanic observations missing between the surface and -10m ?

We cannot explain why ocean data is missing for some periods or height levels. However, some information is not missing but just appears to do (like initial profiles or surface values of salinity and temperature) because the contour plot does not resolve data if it is only available for one time step or one height level.

- Why did you chose this period if there are a lot of missing oceanic data ?

We choose this period because it is characterised by weak atmospheric advection. We do not want to investigate the origin of ocean biases further and therefore decided it is okay if data are not complete.

- BLH is computed from the AOSCM or ERAI ? Please clarify it.

- MDL is computed from observations or the AOSCM ? Please clarify it.

The BLH and MDL are computed in the AOSCM. We have added a clarification in the caption.

- (c) and (d) panels description are missing

Panel descriptions for (c) and (d) are included at the top of (a) and (b). We have added a note on this in the caption.

Figure 7: - please add Q2m and precipitation timeseries - please add ERAI to check how ERAI compare with observations and the model (it will also clarify your discussion).

This is a good idea in principal but most surface parameters are only available in the forecast fields and not in the 6-hourly ERA-Interim fields, from which the forcing was derived. The turbulent heat fluxes and radiation are model products and thus not suitable for evaluation of the AOSCM.

Figure 8: - please separate panels descriptions for (a) and (b) - legend is missing for grey squares - panel (b): wrong x axis: “fluxes” -> rain I would remove panel (b) and replace it by precipitation timeseries in Figure 6.

We have added separate labels for precipitation and now call it “Precipitation measured” and “Precipitation modelled”. What seems to be grey squares are violet squares but with a brighter boundary instead of a dark blue boundary to indicate warm and cold points. Keeping the accumulated precipitation here simplifies the analysis compared to a noisy time series.

Figure 10 l.5: the red dots (cloud base) are not visible.

The figure caption was incorrect and we do not mention the red dots anymore.

Figure 12: the empty blue circle is not described in the legend.

Yes, it is described as “ASCM open blue symbol”.

References:

- Basu, S., Holtslag, A. A.M., Van DeWiel, B. J. H., Moene, A. F., and Steeneveld, G.-J.: An inconvenient “truth” about using sensible heat flux as a surface boundary condition in models under stably stratified regimes, *Acta Geophysica*, **56**, 88–99, <http://dx.doi.org/10.2478/s11600-007-0038-y>, 2008.
- Beljaars, A. C. M. (1997). Air-sea interaction in the ECMWF model. In *Proc. of ECMWF Seminar on Atmosphere Surface Interaction*, pp. 33–52, Reading, 8–12 September 1997
- Dee et al.,: The ERA-Interim reanalysis: configuration and performance of the data assimilation system, *Quart. J. Roy. Meteor. Soc.*, **137**, 553–597, <https://doi.org/10.1002/qj.828>, 2011.
- Fofonoff, N. and Millard, R. C.: Algorithms for Computation of Fundamental Properties of Seawater, *Unesco Technical Papers in Marine Science*, 1983.
- IOC, S. and IAPSO: The international thermodynamic equation of seawater - 2010: Calculation and use of thermodynamic properties, *Tech. rep., Intergovernmental Oceanographic Commission*, http://www.teos-10.org/pubs/TEOS-10_Manual.pdf, 2010.
- Reffray, G., Bourdalle-Badie, R., and Calone, C.: Modelling turbulent vertical mixing sensitivity using a 1-D version of NEMO, *Geoscientific Model Development*, **8**, 69–86, <https://doi.org/10.5194/gmd-8-69-2015>, 2015.
- Sotiropoulou, G., Tjernström, M., Savre, J., Ekman, A. M. L., Hartung, K., and Sedlar, J.: Large Eddy Simulation of warm-air advection and air-mass transformation in the summer Arctic, *Quart. J. Roy. Meteor. Soc. Accepted Author Manuscript*, 2018
- Zeng, X. and Beljaars, A. C.M. (2005). A prognostic scheme of sea surface skin temperature for modelling and data assimilation. *Geophys. Res. Lett.*, **32**, L14605.

Interactive comment on “An EC-Earth coupled atmosphere-ocean single-column model (AOSCM) for studying coupled marine and polar processes”

by Kerstin Hartung et al.

Anonymous Referee #2

Received and published: 14 July 2018

The manuscript provides a detailed description of a coupled atmosphere – sea ice – ocean column model and examples of its applications. The model components and the coupling methods are basically well presented. Particularly good in the manuscript is the discussion on how to design experiments applying the coupled column model. Also the Introduction is very good and motivates a reader. The manuscript has potential to become a good paper, and particularly useful for those who carry out column model experiments or plan to start such activities. The manuscript has, however, also weaknesses, and substantial revisions are needed before I can recommend it for publication.

We would like to thank the anonymous reviewer for the useful feedback. We have corrected typos and adapted suggestions for textual changes. The changes may easily be followed in the attached document containing track changes.

For suggestions requiring more explanations, we provide answers below.

Major comments

1. In several parts of the manuscript, the text is too technical, including acronyms never explained, e.g. on page 6, lines 8, 10, and 17; page 7, lines 12, 14, and 15, and many other places. This holds also for Figures 1 to 3, which are more like computer codes than illustrations that one would expect to see in a peer-reviewed journal.

Yes, it is indeed true that some abbreviations and technical terms were not sufficiently explained in the first version of the manuscript. We wanted to include technical terms as our article should also be useful to those who will be working with the model code and its development. We now tried to give generally understandable explanations but also refer to the technical terms.

P 6: We no longer include the technical terms of the equations of state in the text (l. 6 and 8) and have also added the name of the time stepping routine in brackets.

P 7: The special technical terms concerning the OASIS routines are now also included in brackets.

Figures 1-3: When we started documenting the model, we came across the GMD publication <https://www.geosci-model-dev.net/10/1549/2017/> which uses code illustrations to highlight the work done. We think this visualisation is useful but we have tried to clarify and reduce the content of the tree schematics.

2. The description of sea ice component is very brief, and leaves many open questions. How many model levels there are in sea ice and snow? How the grid is affected when ice and snow thicknesses change, i.e., is the number of levels changed or is the vertical resolution changed? Is penetration of solar radiation into snow and ice taken into account (as in case of the open ocean)? Is snow-to-ice transformation (via refreezing of melt water, rain, or sea water flooded on top of ice) taken into account? Are melt ponds taken into account? These are important questions in atmosphere – ocean coupling in Polar regions. Figure 3 does not provide any help on these issues.

We now give a bit more information about the setup of the sea-ice and snow component (2 vertical layers, thickness categories which are constant in time and only the distribution of fractions is changing).

However, we decided to not go into too much detail in our paper but refer to the respective modelling site. This is partly due to the fact that modelling details change all the time and we want to keep our paper from being outdated soon. We now explain briefly in the model overview section (2.1) why the model descriptions are not very detailed.

3. I am concerned about conclusions made on the basis of comparisons of the model results and ERA-Interim reanalyses in the open-ocean experiments. Are the vertical profiles in ERA-Interim over remote ocean areas accurate enough to make robust conclusions on the performance of the column model? Some references or other evidence on the accuracy of the ERA-Interim profiles should be provided. Further, on page 11, line 3, it is stated that observational data are complemented by ERA-Interim for the atmosphere. It should be more clearly explained what atmospheric variables were observed.

This is a very relevant comment. ERA-Interim is, in the first place, used to initialise and force the atmospheric column. We decided to also use the reanalysis profiles as a test for model drift. Although updated by data assimilation, ERA-Interim is based on the same atmospheric model as the AOSCM. Thus, the AOSCM should follow the forcing profiles approximately. We have added a brief discussion of this topic in Section 4.1.

Comparison with observations is necessary for a strict evaluation of the AOSCM. These data were available near the surface, where the newly coupled model should produce the most benefits. It is definitely desirable to extend the assessment of model performance, however, this should be content of following publications.

Observations used for analysis at the PIRATA mooring were presented on page 11, line 3 (old location). Namely, SST, radiative fluxes as well as profiles of ocean temperature and salinity. We have kept this information.

4. The presentation of the results of the three cases studies should be clarified. It is presently hard to understand the basis of the conclusions made.

The main goal of the results section is to demonstrate the versatility of the AOSCM, while at the same time discussing different types of experimental setups as well as testing the model's stability and sensitivities to some of the model parameters.

We have restructured the text to make it clearer that the experiments section belong together. Conclusions are presented in an overview section on model results (Section 4.3). Additional results to scientific questions are not the main part of our study and therefore not explained in detail.

5. On page 11, line 24, it is told that 0.06 m was used for sea ice roughness. This value is much larger than observations indicate (see papers by Andreas, Lupkes and others). If the key parameter for dynamical coupling between the atmosphere and sea ice is so strongly tuned, what is the relevance of the column model experiments?

Roughness length was here set to achieve an agreement of the friction velocity with LES simulations and observations, to be able to compare with the LES.

In models, the relationship between surface roughness and the strength of the turbulence (i.e. the friction velocity) usually depends on the vertical stability. The momentum coupling is known to be difficult and it is generally not possible to reproduce all aspects of the atmospheric state associated to this coupling, e.g. the boundary layer wind-turning, the jet speed and frequency of boundary layer decoupling from the surface. See for example Sandu et al. (2013).

This might explain why a different roughness length is necessary in the model in comparison to observations and the LES.

6. Advective tendencies were not applied in the ocean, but could be obtained from ocean reanalyses, analogously to obtaining them from ERA-Interim.

Yes, this is correct. Currently the ocean model does not allow forcing with advective tendencies. It is planned to include this in later versions of the AOSCM. However, although it is technically possible to calculate the ocean advection, ocean reanalyses fields are often only available as monthly means or as running averages over a few days. It would probably be necessary to obtain ocean advection from global climate model results.

7. In Summary and Outlook the authors should better evaluate which processes can be simulated applying AOSCM and which cannot. Considering processes acting in the vertical dimension in the Arctic Ocean, there are major challenges in understanding and modelling at least the following processes: gravity drainage of salt in sea ice, brine formation, turbulent exchange of momentum, heat and salt at the ice base during ice growth, double-diffusive convection, and those mentioned in comment 2 above. After reading the manuscript, it remains unclear if AOSCM takes these processes into account.

Our paper focuses on presenting the coupled atmosphere-ocean single column model and its general way of use. All thermodynamic processes described by vertical parametrizations can be studied with the AOSCM. Details on physical parametrizations of the different sub-components cannot all be included, but we refer to the respective model development literature. Please also see answer to comment 2.

Minor comments

Page 3, line 7: Do you mean 44% of meteorological modelling centres or modelling centres in general?

It is modelling centres which develop coupled atmosphere and ocean models. We have clarified this in the text.

Page 5, line 18: Clarify what is meant by a reference state.

We now explain the term “reference state” both in Section 2.1.1 and Section 2.2.

Equations (5) and (8): If part of the solar radiation penetrates below the surface, as in Eq. (8), it should not contribute to surface energy balance, but this is not reflected in Eq. (5).

We forgot to include one parameter, which describes the fraction of solar radiation penetrating below the skin layer. Now the surface energy budget is consistent with penetration of solar radiation into the ocean and sea-ice.

Page 7, line 21: does “fraction” mean areal coverage of sea ice?

This is correct, we have included a comment in the revision.

Page 9, line 12: Briefly explain what is asynchronous coupling.

Thanks for this suggestion. We now briefly explain an alternative coupling option. Also, there was a mistake before and the more advanced coupling is synchronous coupling.

“An example of a more advanced coupling method is synchronous coupling (Lemarie et al., 2015) in which coupling fields are sent and received at the same time.”

Page 10, line 24: Does “near-surface temperature” mean 2-m air temperature?

Yes, this is correct. We changed the phrasing in the text.

Page 10, line 28: Was the tide only due to M2 component? Is the diurnal tide had large contribution, 12 h running means do not help. Note that tidal currents may also affect vertical mixing in the ocean (although not necessarily much in the case presented, as it is in the deep ocean) and, if the model does not include tides, temporal averaging does not help.

The vertical displacement of density surfaces due to tides is not captured in the model. However, mixing resulting due to internal tide breaking is parametrized. Before we applied the running mean over the observations of salinity and temperature we checked for the main frequency peak in the oscillations. The data exhibit a maximum at around 12 h and no peak is visible at around 24 h. We have added this information to the manuscript.

Page 12, lines 29-31: Why did the results improve?

We did not follow up what physical processes lead to reduced biases. This could be the content of a follow up paper and does not fit the model description paper.

Page 14, line 31: Why not simply write RMSE instead of confusing “integrated bias”.

Yes, this is a good suggestion.

Page 17, line 2: Why do you call EC-Earth as “the next version climate model”? It sounds very strange, particularly when referring to a paper eight years old.

Yes, this is a good comment. The paper refers to EC-Earth version 2. Our AOSCM is similar to version 3, apart from using OIFS instead of IFS. The plan is that for EC-Earth version 4 OIFS will be used as the atmospheric model so that similarities between the 3D and 1D models increase. We removed the reference to the version 2 paper at this point.

References:

- Lemarié, F., Blayo, E., and Debreu, L.: Analysis of Ocean-atmosphere Coupling Algorithms: Consistency and Stability, *Procedia Computer Science*, **51**, 2066 – 2075, <https://doi.org/https://doi.org/10.1016/j.procs.2015.05.473>, international Conference On Computational Science, ICCS 2015, 2015.
- Sandu, I., A. Beljaars, P. Bechtold, T. Mauritsen, and G. Balsamo (2013), Why is it so difficult to represent stably stratified conditions in numerical weather prediction (NWP) models?, *J. Adv. Model. Earth Syst.*, **5**, 117–133, doi:10.1002/jame.20013.

An EC-Earth coupled atmosphere-ocean single-column model (AOSCM.v1 EC-Earth3) for studying coupled marine and polar processes

Kerstin Hartung^{1,2,3}, Gunilla Svensson^{1,2,3}, Hamish Struthers^{4,5}, Anna-Lena Deppenmeier⁶, and Wilco Hazeleger^{6,7}

¹Department of Meteorology, Stockholm University, Sweden

²Bolin Centre for Climate Research, Stockholm University, Sweden

³Swedish e-Science Research Centre, Sweden

⁴NSC, Linköping, Sweden

⁵Linköping University, Sweden

⁶Wageningen University, The Netherlands

⁷Netherlands eScience Center, The Netherlands

Correspondence: Kerstin Hartung (kerstin.hartung@misu.su.se)

Abstract. Single-column models (SCM) have been used as ~~a tool to~~ tools to help develop numerical weather prediction and global climate models for several decades. SCMs decouple small-scale processes from large-scale forcing ~~and thus allow to test physical parameterizations~~, which allows the testing of physical parametrizations in a controlled environment with reduced computational cost. Typically, either the ocean, sea-ice or atmosphere is fully modelled and assumptions have to be made ~~on~~ regarding the boundary conditions from other subsystems, adding a potential source of ~~errors~~. error. Here, we present a fully coupled atmosphere-ocean SCM (AOSCM), ~~including sea-ice, which is related to~~ which is based on the global climate model ~~EC-Earth, consisting of EC-Earth3. The initial configuration of the AOSCM consists of:~~ NEMO3.6 (ocean), LIM3 (sea ice), OpenIFS cycle 40r1 (atmosphere), and OASIS3-MCT (coupler).

~~The AOSCM is tested~~ Results from the AOSCM are presented at three locations: the tropical Atlantic, the midlatitude Pacific, and the Arctic. At all three locations, in-situ observations are available for comparison. ~~Evaluating model performance with buoy data, soundings and ship-based observations, we~~ We find that the coupled AOSCM can capture the observed atmospheric and oceanic evolution ~~Model based on comparisons with buoy data, soundings, and ship based observations. The model evolution is sensitive to the initial conditions and forcing data imposed on the column. Coupling several model components while alongside using them individually~~ Comparing coupled and uncoupled configurations of the model can help disentangle

model feedbacks. ~~Although the model can be extended, we demonstrate that already~~ We demonstrate that the AOSCM in the current setup ~~it~~ is a valuable tool to advance our understanding in marine and polar boundary layer processes and the interactions ~~of their coupled components~~ between the individual components of the system (atmosphere, sea-ice and ocean).

1 Introduction

5 Single-column models (SCM) have ~~already~~ been used for several decades to advance our understanding of physical processes and their parametrizations in numerical models. SCMs originated from bulk ~~(mixed-layer)~~ models (Kraus and Turner, 1967; Niiler and Kraus, 1977). The first vertically resolved SCMs were developed in the late 1980s. For example, Betts and Miller (1986) demonstrated added value of an atmospheric SCM framework for the development and evaluation of a convective adjustment scheme in atmospheric models, and Price et al. (1986) used an ocean SCM to study the diurnal cycle of the mixed
10 layer in the subtropical Pacific. Research with SCMs is a valuable addition to studies with three-dimensional numerical weather prediction (NWP) models and global climate models (GCM). By zooming into a single grid column of a host model, either in the atmosphere, the ocean, or the sea-ice, one achieves a separation between resolved large-scale processes and processes parametrized in the vertical column. This means that physical processes, and the ability of their associated parametrization schemes to produce the correct physical tendencies, can be studied in a controlled framework (Randall et al., 1996). Similar
15 to the setup of a three-dimensional model, initial conditions are provided, typically from a sounding, mooring or a reanalysis profile. ~~Though~~ Although the column is decoupled from the large-scale flow, forcing mimicking the influence of the large-scale circulation on the column of interest can be applied. In practice, this is done by applying pressure gradient forcing via the geostrophic wind, horizontal advection and vertical velocity forcing to the atmospheric component of the SCM. Relaxation (nudging) is an alternative way to include forcing by the large-scale environment. ~~All forcing types can be used individually and~~
20 ~~complementary~~ Forcing types can also be applied in combination, depending on the type of model experiment being performed. In the controlled environment of an SCM, the evolution of idealized or realistic initial profiles exposed to forcing of varying complexity can be studied in an Eulerian or Lagrangian setting. The choice of experimental setup ~~will affect the possibility to study the performance of~~ determines how and to what extent, different physical parametrizations within the model can be studied. Thus, an experiment needs to be designed carefully, depending on the underlying scientific question. ~~Furthermore, by~~
25 By only evolving a single grid column, the computational cost is reduced considerably compared to experiments with a three-dimensional model. This allows for comprehensive parameter testing as more sensitivity experiments can be carried out ~~at much reduced time cost.~~ In summary, an SCM can be a powerful tool if its limitations are handled with care.

For these reasons, SCMs have regularly been employed to investigate ~~physical processes~~ modelling of physical processes in the ocean, sea-ice and atmosphere. In the ocean, single-column models, sometimes just called column models, started off as
30 bulk mixed-layer models (Kraus and Turner, 1967; Price et al., 1986). From the start they were used to study the impact of air-sea exchange and vertical mixing on the temporal evolution of the oceanic mixed-layer. In Gaspar et al. (1990) and Large et al. (1994), these bulk models are extended to 1D turbulence models which can be applied in the whole column and are thus

suitable for GCMs. More recent examples of oceanic SCM models being used for model development are Ling et al. (2015) and Reffray et al. (2015).

In addition to research with individual atmospheric SCMs (e.g. Betts and Miller, 1986; Randall et al., 1996), SCM inter-comparison studies have focused on e.g. convection (e.g. Betts and Miller, 1986; Ghan et al., 2000; Bechtold et al., 2000; Lenderink et al., 2004), stratocumulus (e.g. Bretherton et al., 1999; de Roode et al., 2016) and mixed-phase clouds (e.g. Klein et al., 2009; Klein et al., 2009; Pithan et al., 2016), and the representation of the boundary layer (e.g. Cuxart et al., 2006; Baas et al., 2010; Svensson et al., 2011, as part of GABLS (GEWEX Atmospheric Boundary Layer Study, Holtslag, 2006); GEWEX: Global Energy and Water EXchanges). These studies also present a wide range of numerical approaches to set up, initialize (e.g. idealized or based on measurements), and force the model (e.g. whether Eulerian or Lagrangian forcing is prescribed). Idealized model setups are commonly complemented by large eddy simulations (LES) or cloud-resolving models (CRM), capturing the atmospheric evolution in more detail. LES and CRM are used to compile forcing data or as benchmarks when evaluating the performance of parametrization parametrizations in SCMs (e.g. Bechtold et al., 2000; Guichard et al., 2004; Beare et al., 2006). The cases developed within GCSS (GEWEX Cloud System Study) and GABLS, which merged into GASS (GEWEX Global Atmospheric System Study) at the end of 2010, have been successfully used to identify and improve parametrized processes (e.g. Lenderink et al., 2004) and serve as testbeds for model development. 44% of modelling centres, which develop coupled atmosphere and ocean models, polled by Hourdin et al. (2017) reported the use of SCMs for model development and tuning. This coordinated way of working has not been, to our knowledge, as extensively utilized in the ocean or sea-ice communities.

In contrast to global climate models, SCMs have mostly been implemented uncoupled. Thus, for the majority of atmospheric studies mentioned, the surface is prescribed by boundary conditions. Sensitivity to the formulation of the surface boundary conditions and surface forcing (e.g. surface temperature, surface fluxes or surface energy budget equation) was found in several of the atmospheric SCM studies. Firstly, there are theoretical limitations: while an atmospheric convective boundary layer may be forced by surface fluxes, a stably stratified one should not (Basu et al., 2008). Furthermore, a using surface temperature or fluxes. The choice of boundary condition may influence the results. Using prescribed surface temperature has proven to lead to very different energy content in the boundary layer (Svensson et al., 2011), while using different land models also introduces spread (Bosveld et al., 2014 Bosveld et al., 2014 and GABLS4), a subject that is currently further studied in DICE (<http://apponconv.metoffice.com/dice/dice.html>). There are also theoretical limitations to consider, such as problems that arise when a stably stratified boundary layer is forced with surface fluxes (Basu et al., 2008). Over sea-ice, the presence of snow modulates the surface energy budget and thus results vary depending on the description of snow in the surface model (Pithan et al., 2016). In the ocean, the depth of the mixed layer is sensitive to the coupling, especially in the tropics and during summer, when the mixed layer is shallow and quickly responding to forcing. The fast response can give rise to positive feedbacks between model biases in the atmospheric and oceanic mixed layers (Breugem et al., 2008; Toniazzo and Woolnough, 2014). It is common to develop model components using idealized prescribed forcing, i.e., ocean and land models use near-surface observed or reanalysis mean state variables to provide atmospheric fluxes. However, this can lead to surprises when model components are interactively coupled. Atmospheric models are forced with observed SSTs over the ocean and often

developed in a framework with an interactive land model over land, although the land model is taken as is and i.e. thus not developed in the interactive framework. To avoid ambiguities arising from specifications of surface boundary conditions, it is desirable to combine several SCMs ~~to~~into one coupled model, especially when studying boundary layer processes or processes that depend on interfacial coupling.

5 In the last two decades a few coupled single-column models have been developed. Clayson and Chen (2002) coupled an atmosphere and an ocean SCM to study tropical atmosphere-ocean feedbacks and Goyette and Perroud (2012) combined a 1D lake model with an atmospheric column model. More recently, West et al. (2016) coupled a one-dimensional sea-ice and an atmospheric column model to investigate the optimal interface at which to calculate the surface energy budget.

Following this line of work, we present a coupled atmosphere-ocean sea-ice SCM (AOSCM) following the global climate
10 host model EC-Earth (Hazeleger et al., 2010, 2012). The AOSCM provides a platform to study ~~coupling processes,~~ both physical and numerical ~~at the marine and polar~~coupling processes at the surface interface. First, we present and discuss ways to set up and force the model. This encompasses idealized and realistic initial conditions and forcing, Eulerian and Lagrangian setups, short-term case based or long-term statistical analysis. Application of the AOSCM is demonstrated at three locations, namely mid-latitudes, tropics and the Arctic. Varying experimental designs display the versatility of the tool.

15 2 Model description, model ~~setups~~setup and data

2.1 Model components

In this study, the AOSCM is ~~realized by combining~~build from the atmospheric model OpenIFS (Open Integrated Forecasting System, <https://software.ecmwf.int/wiki/display/OIFS/Single+column+model+40r1+release+notes>), including the land model H-Tessel (Balsamo et al., 2009), and the ocean model NEMO (Nucleus for European Modelling of the Ocean, <https://www.nemo-ocean.eu/>)
20 ~~including with~~ the sea-ice model LIM (Louvain-la-Neuve Sea Ice Model, <http://www.elic.ucl.ac.be/repomdx/lim/>). All coupling actions between the column versions of the sub-components NEMO and OpenIFS are performed by the coupling software OASIS3-MCT (<https://portal.enes.org/oasis>). For model development purposes, the column model should follow the specifications of a GCM host model. In an iterative process, findings from the SCM, and specifically their impact on the large-scale circulation, can then be directly tested and evaluated in the GCM. In this way the computational
25 cost for coupled model development is reduced. Here, the AOSCM is set up to closely match the development version of the EC-Earth model. Presently, this means that the default setup is a column version of EC-Earth v3, except that instead of using IFS cycle 36r4 the AOSCM uses OpenIFS cycle 40r1. Future versions of EC-Earth will be based on OpenIFS. The other components, namely NEMO3.6, LIM3 and OASIS3-MCT, are used with the same version in both EC-Earth v3 and the AOSCM.

30 The different model components are presented with a focus on formulations and settings specific to the one-dimensional versions of the codes. Still, the description does not encompass all details on the model subcomponents. This is mainly motivated by the fact the AOSCM, as well as all its components, are continuously under development. For current settings and recent updates we refer to the AOSCM code branch and the respective model platforms.

2.1.1 OpenIFS

OpenIFS (hereafter OIFS) is developed by the European Centre for Medium-Range Weather Forecasts (ECMWF) as a version of IFS intended for research and education (Day et al., 2017). The main difference of OIFS40r1 to IFS 40r1 is the exclusion of the data assimilation component of IFS. Extensive documentation is available for IFS at: <https://www.ecmwf.int/en/forecasts/>

5 documentation-and-support/changes-ecmwf-model/cycle-40r1/cycle-40r1.

The atmospheric part of the AOSCM solves the one-dimensional version of the primitive equations:

$$at5 - \dot{\eta} \frac{\partial u}{\partial \eta} + F_u + f(v - v_g) + P_u + \frac{u_r - u}{\tau} \frac{u_r - u}{\tau_a} = \frac{\partial u}{\partial t} \quad (1)$$

$$- \dot{\eta} \frac{\partial v}{\partial \eta} + F_v - f(u - u_g) + P_v + \frac{v_r - v}{\tau} \frac{v_r - v}{\tau_a} = \frac{\partial v}{\partial t} \quad (2)$$

$$- \dot{\eta} \frac{\partial T}{\partial \eta} + F_T + \frac{RT\omega}{c_p p} + P_T + \frac{T_r - T}{\tau} \frac{T_r - T}{\tau_a} = \frac{\partial T}{\partial t} \quad (3)$$

$$10 - \dot{\eta} \frac{\partial q}{\partial \eta} + F_q + P_q + \frac{q_r - q}{\tau} \frac{q_r - q}{\tau_a} = \frac{\partial q}{\partial t} \quad (4)$$

A As in the full model system, a two-time level semi-Lagrangian scheme is used (~~as in the full model system,~~ an Eulerian scheme is ~~optional~~also available) to integrate the momentum with horizontal wind components u and v (Eq. (1) and (2)), thermodynamics T (Eq. (3)), moisture q (Eq. (4)) as well as the continuity equation. The vertical coordinate is based on η levels, which merge orography following σ coordinates near the surface with pressure coordinates in the free atmosphere.

15 Here, $\dot{\eta}$ and ω are vertical velocities, in η and pressure coordinates, respectively. F_i is the horizontal advection, P_i summarizes physical parametrizations and u_r, v_r, T_r, q_r denote the reference profiles used for nudging with a time scale τ, τ_a . Furthermore, f is the Coriolis parameter, u_g and v_g the horizontal components of the geostrophic wind, R the moist air gas constant, c_p the heat capacity of moist air at constant pressure and p the pressure. In addition to the atmospheric state variables (Eq. (1) - (4)), the model prognostically calculates cloud liquid, ice, rain, snow and cloud cover.

20 The total tendency (right-hand sides of Eq. (1) - Eq. (4)) to each prognostic variable is calculated as the sum of dynamical (first three terms on the left-hand side) and physical parametrization tendencies P_i (fourth term), possibly updated by relaxation (i.e. nudging, fifth term). The order of the left-hand side of the equation is, in a simplified way, equivalent to the sequence in which the tendencies are calculated in the model (Fig. 1). In the time-stepping loop, the dynamical tendencies are determined, mainly aggregating available prescribed forcing. The pressure gradient forcing is represented by the geostrophic wind. The

25 third term of the heat equation captures adiabatic heating through vertical motion. Calculations of tendencies from physical parametrizations are done in the same way as in the three-dimensional OIFS. Detailed discussion of the parametrizations used for these processes, namely, the radiation, turbulence, cloud and convection parametrization schemes as well as the non-orographic gravity wave drag, orographic gravity wave drag and surface drag, can be found in the IFS documentation for cycle 40r1 (https://www.ecmwf.int/sites/default/files/IFS_CY40R1_Part4.pdf). Relaxation tendencies are calculated weighing

the difference between the new state, as determined by physical and dynamical tendencies, and a reference state, with the relaxation timescale τ . All forcing is τ_o . References states can, for example, be observed or modelled profiles of atmospheric variables. All forcing fields are read in at forcing time steps and linearly interpolated at intermediate model steps.

Besides visualising the sequence of main routines called during an OIFS SCM run, Fig. 1 also highlights in red communications with other AOSCM components through the coupler, and use of coupling variables in red. Coupling variables are also schematically shown in Figure 4. They enter the primitive equation system (Eq. (1) - (4)) via the surface energy balance budget (Eq. (5)).

$$(1 - \alpha_i)(1 - f_{Rs,i})R_s + \epsilon(R_T - \epsilon\sigma T_{sk,i}^4) + H_i + LH_i = Q_T = \Lambda_{sk,i}(T_{sk,i} - T_1) \quad (5)$$

The energy budget is solved individually for each surface tile i , which in the coupled system are the ocean and/or sea-ice. The downward short-wave and long-wave radiations are R_s and R_T , with the tiled albedo α_i , the surface tiled fraction of short-wave radiation absorbed at the surface $f_{Rs,i}$, the surface emissivity ϵ , the Stefan-Boltzmann constant σ , the skin temperature $T_{sk,i}$, and the skin layer conductivity $\Lambda_{sk,i}$. H_i is the tiled sensible heat flux and LH_i the tiled latent heat flux. Downward-Upward coupling is implemented through the surface albedo and the temperature of the upper snow, sea-ice or ocean layer T_1 .

2.1.2 NEMO

NEMO is based on the thermodynamics and dynamics OPA model (Océan PARallélisé) and includes the LIM3 sea-ice component. More details of NEMO can be found in Madec (2016), and Rousset et al. (2015) describes the recent version of LIM.

The ocean component NEMO3.6 is a primitive equation model based on the one-dimensional version of the Navier-Stokes equations (Eq. (6) and (7)), the hydrostatic equation, the incompressibility equation, heat and salt conservation equations (Eq. (8) and (9)), and the equation of state.

$$at5 - \frac{\partial}{\partial z} \nu_t \frac{\partial u}{\partial z} + f v + P_u + \frac{u_r - u}{\tau} \frac{u_r - u}{\tau_o} = \frac{\partial u}{\partial t} \quad (6)$$

$$- \frac{\partial}{\partial z} \nu_t \frac{\partial v}{\partial z} - f u + P_v + \frac{v_r - v}{\tau} \frac{v_r - v}{\tau_o} = \frac{\partial v}{\partial t} \quad (7)$$

$$- \frac{\partial}{\partial z} K_t \frac{\partial T}{\partial z} + \frac{1}{\rho_o c_p} \frac{\partial I(F_{sol}, z)}{\partial z} + P_T + \frac{T_r - T}{\tau} \frac{T_r - T}{\tau_o} = \frac{\partial T}{\partial t} \quad (8)$$

$$- \frac{\partial}{\partial z} K_t \frac{\partial S}{\partial z} + E - P + P_S + \frac{S_r - S}{\tau} \frac{S_r - S}{\tau_o} = \frac{\partial S}{\partial t} \quad (9)$$

EC-Earth v3 uses the polyTEOS10-bsq formulation, i.e. it is an equation of state which is based on conservative state variables and provides better conservation constraints than other representations of the equation of state (polyTEOS10-bsq, IOC and IAPSO, 2010). That is of less importance in the 1D version, which is therefore here based on the polyEOS80-bsq based on a simpler equation of state (polyEOS80-bsq, Fofonoff and Millard, 1983). The prognostic variables of the EOS used in the 1D version are the

tracers potential temperature T , practical salinity S , and the horizontal velocity components u and v as described in Eq. (6)-(9). Here, ν_t and K_t are the vertical turbulent viscosity and diffusivity, respectively. $I(F_{sol}, z)$ denotes the penetrative part of the solar surface heat flux, and E and P are the evaporation and precipitation fluxes. P_i summarize physical parametrizations and u_r, v_r, T_r, S_r again describe reference profiles to which the modelled profiles can be relaxed with a time scale τ_{T_0} . The terms on the left hand sides of the equation system capture the column forcing.

The general structure and work-flow in the NEMO and LIM models are summarized in Fig. 2 and 3. The main ocean integration is organized from the time stepping routine (*stp_cld*), with tracer and momentum tendencies evaluated separately. The AOSCM setting includes physical parametrizations P_i , for example describing the turbulence closure. In the standard setting, the vertical mixing scheme is based on a TKE dependent eddy coefficient and a 1.5 turbulent closure for convection but other turbulence schemes are implemented in the code and can easily be selected. A Langmuir circulation parametrization is also turned on and the effect of chlorophyll ~~for-on~~ heating due to solar penetration is taken into account. Advection of tracers is not possible in the one-dimensional framework but can, in a ~~way-similar~~ similar way to that applied in the atmospheric model, be approximated by relaxing profiles of both tracer and momentum fields towards reference profiles. However, this procedure is not utilized in the examples presented here.

~~Again-communications~~ Communications with other components during the work-flow are highlighted in red (Fig. 2). Coupling actions are performed at the beginning of the time stepping, namely receiving fields as part of the boundary condition routines, and at the end of the time stepping, when the updated SST and ice parameters are ~~send~~ sent to the atmospheric part of the AOSCM. The ~~boundary-conditions-at-the-surface~~ surface boundary conditions for the momentum and tracer variables are given in Eq. (10) - (13). There, $\tau_{u,v}$ are the surface wind stress components, ρ_0 is the in situ density, and S_t the rate of change of the sea-ice thickness budget. Only the non-penetrative part of the net surface heat flux (see Eq. (5)) influences the temperature boundary condition.

$$\nu_t \frac{\partial u}{\partial z} = \frac{\tau_u}{\rho_0} \quad (10)$$

$$\nu_t \frac{\partial v}{\partial z} = \frac{\tau_v}{\rho_0} \quad (11)$$

$$K_t \frac{\partial T}{\partial z} = \frac{Q_T}{\rho_0 C_p} \quad (12)$$

$$K_t \frac{\partial S}{\partial z} = \frac{(E - P - S_t) \cdot S(z=0)}{\rho_0} \quad (13)$$

LIM3, the sea-ice model embedded in the oceanic component of the AOSCM, contains a thermodynamic and a dynamic component. In its 1D version, only the thermodynamic model is currently used, including the representation of subgrid-scale distributions of ice thickness, enthalpy, salinity and age. The model includes multiple sea-ice categories of different ice thickness, set to five categories as a default. The distribution of sea-ice thickness categories is determined based on the mean ice thickness and is constant in time. The sea-ice concentration in each category varies due to source and sink processes of

sea-ice. The halo-thermodynamics parametrized in the model are solved for each ice category, which consist of one snow layer and potentially several ice layers. A brief description of the model sub-components is given in Fig. 3.

2.1.3 OASIS3-MCT

The OASIS3-MCT coupler (Valcke, 2006) takes care of ~~communication~~ communications between the atmosphere and the ocean/sea ice components, and carries out transfers and temporal transformations of variables. Regridding is not necessary since two SCMs are coupled. Coupling between the atmospheric and oceanic models is performed by ~~the~~ OASIS writing (*oasis_put* and *oasis_get* actions in the atmospheric and oceanic models) actions (see Fig. 1 and 2). At every coupling step (a multiple of each model's time step), coupling variables are exchanged between the components. It is recommended to use a temporal lag between ~~put and get~~ OASIS writing and reading actions to avoid long-waiting times of components or possible deadlocks, even in a single-column setup. In this framework, the variables are ~~put~~ written a given time before the coupling timestep, usually determined by the model timestep, but only read by the receiving model (~~get~~) at the coupling timestep. Thus, initialization files of the coupling variables are needed at the start of the simulation.

Variable transfer between NEMO and OIFS is implemented in both directions (Fig. 4). NEMO receives from OIFS surface stress, solar radiation, longwave radiation, sensible and latent heat fluxes, the temperature sensitivity of the non-solar heat fluxes (long-wave radiation, sensible and latent heat flux), precipitation, and evaporation. In the reverse direction, only the sea surface temperature is passed in ice-free conditions. In presence of sea-ice, sea-ice albedo, thickness, fraction, temperature, and snow thickness are also transferred from LIM to OIFS. Sea-ice parameters are available for the different sea-ice thickness categories but the aggregated mean is transferred to the atmosphere. If sea-ice is present, some ice parameters are also coupled to the ocean model. The ocean receives, in addition to the atmospheric parameters, sea-ice fraction (areal coverage), thickness, temperature, and albedo. The rate of change in ice thickness is added to the mass flux received from the atmosphere, evaporation, and precipitation. OASIS3-MCT allows to pass either instantaneous values of the coupling fields at the time of coupling, or transform the field by ~~means of~~ calculating an average, maximum, minimum or sum over the period since the last coupling. As in EC-Earth v3, coupling parameters are averaged over the coupling ~~time-step~~ timestep.

2.2 ~~How to design an (AO)SCM experiment~~

25 3 How to design an (AO)SCM experiment

As mentioned in Sec 1, the freedom in setting up the model initial conditions and forcing is both an advantage and a challenge when using the AOSCM. One needs to find a balance of forcing settings, based on the research question to be studied. Here, we briefly present some possibilities of using the (AO)SCM.

Figure 5 shows the main options to consider when designing an SCM experiment. Firstly, the ~~questions~~ question is if the model should be used in an idealized setting or following measurements, reanalysis, or model data. In idealized simulations, the vertical structure of initial conditions and forcing, as well as the vertical extent of the forcing can be simplified. If no forcing is prescribed, the model column evolves in a Lagrangian way. In an SCM it would usually be assumed that the whole column is

migrating simultaneously, ~~although this is likely not~~ this is unlikely to be true in reality. The Lagrangian approach of following an air parcel needs to be adapted in an AOSCM, as disregarding relative horizontal velocities of the components is unrealistic, especially for longer simulations.

More complex experiments can be designed in a variety of ways, as for example described in Randall and Cripe (1999).

- 5 They are presented here in order of increasing control on the model evolution and complexity of the setup. It is often advisable to combine several of these forcing options.

Pressure-gradient forcing is one of the most basic large-scale forcings. It ensures that energy is supplied from the non-resolved large-scale pressure field to counteract energy loss through frictional dissipation near the surface. As the wind is forced to be close to the geostrophic wind, modulated by the timescale prescribed by the Coriolis parameter, it can be understood as a physically motivated relaxation. Unless nudging of the wind is applied, this forcing is necessary and it is in general advisable for longer simulations. Forcing with geostrophic winds is known to introduce inertial-type oscillations into the column (e.g. Egger and Schmid, 1988). Advective tendencies of prognostic variables and vertical velocity also emulate the influence of neighbouring columns on the column of interest. As the vertical structure in the AOSCM might differ from the host model column or from measurements, one needs to ensure that the tendencies are physically reasonable and, if possible, prevent the model from drifting away. Thus, it might be necessary to apply advective tendencies only ~~, or not,~~ over a specific height interval or to add relaxation forcing. It should be noted that the vertical velocity is often corrected from large-scale forcing (Sigg and Svensson, 2004), since it is a parameter not easily diagnosed in large-scale models. For example, in ERA-Interim (Dee et al., 2011) the vertical velocity is a combination of the diagnosed vertical velocity and residuals from the calculation of physical ~~parameterizations~~ parametrizations (Nils Wedi (ECMWF), ECMWF, personal communication). Finally, the model column can be forced by relaxation (also called nudging). This is the forcing option which is the most dependent on the actual model state at the time the forcing is applied, and the only one which is not mimicking a process resolved in a three-dimensional model. Weighted with the characteristic time scale of relaxation, the AOSCM column mean profile is forced towards a reference profile, for example a sounding or mooring profile, or reanalysis fields. Thus, nudging can alleviate or prevent model drift, depending on the time scale chosen. ~~However, nudging~~ Nudging best reduces biases of state variables ~~and~~ but has been reported to lead to problems for variables describing rates, extensively documented for precipitation (e.g. Randall and Cripe, 1999; Hack and Pedretti, 2000; Ghan et al., 2000). ~~Another restriction is that some physical parametrizations can only be tested if the momentum balance is not artificially altered. While the cloud micro-physics description could be evaluated in a AOSCM applying relaxation, a~~ Nudging momentum can be very helpful when evaluating cloud microphysics (e.g. Lohmann et al., 1999) but not in a study of the boundary-layer turbulence evolution ~~is not recommended.~~ Nudging changes the equilibrium of dynamic forcing and physical parametrizations, and might mask model biases. On the other hand, nudging tendencies can be evaluated and used to diagnose model drift and imbalances. Nudging is also useful as it allows handling of inaccurate or missing information, like inertial oscillations of wind or vertical velocity forcing.

30

After designing initial and forcing data, the number and length of simulations needs to be decided. Measurement campaigns are usually limited in time and thus motivate shorter simulation lengths. Even if relaxation of the profile is used to prevent

model drift, the impact of initial condition and forcing sensitivity might limit the model run length to which parametrizations can be evaluated.

The physical processes of interest, and the need to appropriately resolve them, determine settings of time steps, vertical grid and coupling frequency. Even though not ~~feasible-practicable~~ for the host model, for which settings are usually tested, it is desirable to run the SCM with highest temporal and spatial resolution. Similarly, the model can be used to develop and understand different coupling options, ~~like asynchronous coupling (Lemarié et al., 2015)~~, which are less feasible in a three-dimensional model. An example of a more advanced coupling method is synchronous coupling (Lemarié et al., 2015), in which coupling fields are sent and received at the same time step.

Both pressure gradient forcing and horizontal advective tendencies are calculated based on horizontal gradients. Thus, it should be noted that when using forcing based on model data, they depend on the horizontal resolution of the host model. The resolution of the forcing is the main scale information applied in the model, apart from potential time-scale settings, which depend on the horizontal grid settings. In addition, the temporal resolution of the forcing steers how closely the observed temporal evolution can be captured.

3.1 ~~Experimental setup and evaluation~~

4 Examples of experimental setup and evaluation

~~In this section, the setup of the AOSCM~~

4.1 Experimental setup

To illustrate the versatility of the new tool, the AOSCM is applied at three different locations, namely the Pacific midlatitudes, the tropical Atlantic and the North Polar region,~~is presented. We start by detailing the data used and settings common to all or most.~~ The locations are chosen to demonstrate the model in three different climatic regions. Result from the coupled SCM (AOSCM) are compared with atmosphere-only (ASCM) or ocean-only (OSCM) simulations.

Special focus is placed on analysing the stability of the simulations, i.e. we test for model drift, compared to gridded reanalysis data (for the Pacific midlatitudes and tropical Atlantic locations). It should be noted that evaluation against reanalysis does not assume that reanalyses present the truth. However, it allows to detect potential model drift against the forcing dataset. Simulations in the North Polar region are based on reanalysis data in a semi-idealized way, which also considers a reference LES simulation. At all locations, model simulations are evaluated against point-based observations. In addition to testing for model stability, sets of experiments at the three locations analyse the sensitivity to forcing and model settings while highlighting the versatility of the AOSCM. Furthermore, current scientific questions and avenues to study them are touched upon for two of the locations ~~(tropical Atlantic and North Polar region). However, our aim is not to conclusively answer these science problems but to motivate other users to consider the AOSCM for such tasks.~~

~~For all locations atmospheric~~

An overview of the experiments at the three locations is given in Table 1.

Atmospheric initial conditions and forcing are obtained from ERA-Interim (Dee et al., 2011), ~~though with different temporal and spatial resolution.~~ Both analysis steps, which are provided every six hours, and intermediate 3-hourly forecast are used. The OIFS SCM is initialized with profiles of the non-cloud atmospheric prognostic variables. In case of atmosphere-only simulations, the sea surface temperature is initialized and updated daily. Restart files of surface parameters required for coupled
 5 simulations are obtained from short ASCM simulations. All forcing data, horizontal advective tendencies of the prognostic variables, geostrophic wind and vertical velocities, are calculated from the three-dimensional fields of ERA-Interim for each output timestep. ~~To ensure best performance, the equivalent resolution of the ASCM is set to T511, mainly influencing the convective adjustment timescale. In contrast to EC-Earth v3, the radiation time step is equal to the dynamics time step of 900 s.~~

10 The ocean is initialized from observed daily-mean profiles of temperature and salinity, measured to a depth of ~~between~~ 120-500 m at the ~~marine~~ Pacific and Atlantic locations. As these depths are well below the typical mixed layers, we assume that temporally coarser data in the deeper ocean does not significantly influence the model evolution near the surface ~~significantly~~. Therefore, the observed initial profiles are extended below by monthly-mean potential temperature and salinity ORAS4 reanalysis fields (Balmaseda et al., 2013). At the Arctic location, the initial ocean ~~profiles are fully profile~~
 15 is taken from ORAS4 data. The vertical grid is based on 75 levels, though at the Arctic location the shallow bathymetry means that only 17 levels are used. The ocean is only forced by coupling information from the atmosphere.

To ensure best performance, the equivalent resolution of the A(O)SCM is set to T511, mainly reducing the convective adjustment timescale and thereby alleviating instabilities. In contrast to EC-Earth v3, the radiation time step is equal to the dynamics time step (see Table 1). The NEMO configuration differs from the standard EC-Earth GCM settings, since it is uses
 20 NEMO-C1D options (Reffray et al., 2015). Namely, the equation of state formulation and the temporal chlorophyll structure are adapted. Instead of a constant value, SeaWIFS based chlorophyll climatologies are used (NASA Goddard Space Flight Center, 2014), ~~based on Reffray et al. (2015) for.~~ For the PAPA location, the data is the same as presented in Reffray et al. (2015). No bottom geothermal heating is parametrized and the enhanced vertical mixing schemes of EC-Earth is turned off. The
 25 timeseries of observed ocean profiles are influenced by tidal oscillations. As the model does not resolve these, the oscillations in measurements are removed by applying a running mean of 12 h (the frequency of the peak in the energy spectrum, not shown) for the comparison (Figure 6).

4.1.1 Midlatitudes: PAPA station, east Pacific

For the first experiment, we place the AOSCM at the PAPA mooring in the midlatitudinal ~~east~~ north-east Pacific (nominally at ~~50.1° N, 144.8°~~ 50° N, 145° W, <https://www.pmel.noaa.gov/ocs/Papa>). Observations at this location have been extensively
 30 used to develop physical ~~parameterization~~ parametrization in the ocean (e.g. Gaspar et al., 1990; Reffray et al., 2015), because the buoy is situated in a region of weak horizontal advection. Reffray et al. (2015) present a reference configuration of the NEMO column model at the PAPA mooring and test various mixing parametrizations available within NEMO.

The main experiment at the PAPA location consists of a 5-day coupled atmosphere-ocean simulation, initialized on 11 July 2014 at 18 UTC (11am local time) ~~. The atmospheric model uses 60 levels and which~~ is forced with 6-hourly data

(AOSCM-6h). ~~The ocean column is resolved with 75 layers that are initialized from daily-mean profiles of temperature and salinity measured to a depth of 200 m. The coupling time step and coupling lag are chosen equal to the time step of the individual model components to be 900 s. Restart files of surface parameters required for coupled simulations are obtained from a short ASCM simulation.~~ An uncoupled atmosphere-only simulations with 6-hourly atmospheric forcing (ASCM-6h) and a coupled simulation with 3-hourly atmospheric forcing (AOSCM-3h) act as sensitivity runs to the main setup. One further set of simulations highlights how model drift in the free troposphere can be minimized. Here, nudging of temperature, moisture, and horizontal wind with a timescale of $\tau=6\tau_a=6$ h above a height of 3 km is applied (AOSCM-N3km6h). In addition, the model was run with the standard setting extended by relaxing the horizontal wind with a timescale of $\tau=1\text{h}\tau_a=1\text{h}$ (AOSCM-Nuv0km1h). With each of the experiment settings described above, a further sixteen 29-day long simulations started at 18 UTC on the first of the respective months (Oct 2010; Apr, Jun-Jul, Nov 2011; Mar, Aug, Nov 2012; Jun-Jul 2013; Jan, Apr, Jul-Sep, Nov 2014) are run for statistical assessment.

~~The atmospheric column of the model is first compared with ERA-Interim to ensure that the mean large-scale state is not drifting.~~ Surface variables are evaluated using hourly averaged PAPA mooring surface measurements. The variables used here are, with measurement error estimates in parentheses: ~~near-surface~~ 2 m air temperature ($\pm 0.2^\circ\text{C}$), SST ($\pm 0.003^\circ\text{C}$), 10 m wind speed ($\pm 2\%$), wind-speed corrected precipitation ($\pm 4\text{ mm h}^{-1}$ on 10 min filtered data with measurement threshold of 0.2 mm h^{-1}), long- and short-wave radiation (downwelling component with $\pm 1\%$ error), and turbulent fluxes of heat. ~~Thus, the model evaluation includes both a model-model comparison and an evaluation of grid-box mean results with point-measurements. The timeseries of ocean profiles at the PAPA location are influenced by tidal oscillations. As the model does not resolve these, the oscillations in measurements are removed by applying a running mean of 12h for the comparison.~~

4.1.2 Tropical Atlantic

The second ~~marine~~ location at which the SCM is tested, lies in the tropical Atlantic, situated at the 6°S , 8°E buoy of the PIRATA mooring array (Servain et al., 1998; Bourlès et al., 2008, <https://www.pmel.noaa.gov/tao/drupal/disdel/>). We choose a boreal summer month to demonstrate the AOSCM's ability to follow the SST cooling connected to the annual cold tongue development in the ~~topical~~ tropical Atlantic (Lübbecke et al., 2010; Xie and Carton, 2004). During the period of 1-30 June 2014, mooring observations of SST, radiative fluxes, and ocean temperature and salinity are available for SCM evaluation. ~~For evaluation of the experiments the observational data, which~~ are complemented by ERA-Interim for the atmosphere. ~~The ocean is initialised with daily mean temperature and salinity at the 1st of June from 0-500 m and 0-120 m respectively.~~ We perform experiments in-using several settings of the AOSCM and one OSCM simulation. The ~~atmosphere is run with 60 levels and atmospheric column is~~ either forced by advective tendencies and vertical velocity only (F01, F12, F15 AOSCM-Jun1/12/15), or additionally, profiles of temperature, moisture, and horizontal wind are nudged above 1 km with a timescale of 6 hours (N1km6h). ~~For comparison~~ AOSCM-N1km6h. ~~For comparison,~~ we also perform an ocean-only simulations (OSCM), which is forced by hourly precipitation, near-surface wind, temperature and moisture from ERA-Interim, and shortwave- and longwave radiation measured at the PIRATA buoy (OSCM). ~~The oceanic, atmospheric, and coupling time steps are 900 s each.~~

4.1.3 North Polar region

To explore the AOSCM in an experimental setting with idealized forcing, and to show the additional interaction with sea ice, we choose an Arctic summer case. For this location (76° N, 160° E), we have observations from the ACSE (Arctic Clouds in Summer Experiment) campaign during a warm-air advection episode in early August 2014 causing rapid ice melt (Tjernström et al., 2015). Sotiropoulou et al. (2018) ~~apply idealized forcing to a LES case~~ use an LES to study the importance of advection for cloud evolution during this period. Here, we present results from the LES (Savre et al., 2014), in comparison with results from the ASCM, using the same experimental setup as in Sotiropoulou et al. (2018). Furthermore, we explore the importance of coupling to the ocean/sea ice, as well as the sensitivity to atmospheric model time step and coupling frequency, in ASCM and AOSCM experiments. With the aim to separate the influence of local and remote processes, as in Sotiropoulou et al. (2018), we turn off large-scale advection of heat and moisture.

The idealized experiment, ~~loosely based on observations~~ based on simplified information from observations and reanalysis (Sotiropoulou et al., 2018), assumes an initial ice concentration (100 %), surface albedo (0.65), and temperature (273.15 K, i.e. melting point of ice). The LES is applying a surface friction velocity of ~~$0.2 u_* = 0.2$~~ 0.2 m s^{-1} as lower boundary condition, while it is modelled in the ASCM and AOSCM using a surface roughness, updated from its default value (0.001 m) to 0.06 m to achieve approximately the same averaged u_* . The LES and the atmospheric component of AOSCM are initialized with the same vertical mean profiles, smoothed versions of soundings at 1 August 06 UTC, the starting time of the simulation. The atmospheric forcing consists of a constant geostrophic wind of 5.4 m s^{-1} and advective tendencies of temperature and humidity, all derived from 6-hourly ERA-Interim data interpolated to a vertical L137 grid, but restricted vertically to the LES boundary layer height. ~~All forcing is 6-hourly in accordance with the LES setup.~~ The synoptic scale divergence (i.e. vertical advection), is not directly taken from the ERA-Interim as it generates unrealistic results. Thus, a prescribed divergence of $2.3 \cdot 10^{-5} \text{ s}^{-1}$ is applied over the first 18 simulated hours and then decreased by ~~50 %~~ 50 %, in both the LES and the SCM experiments.

5 Results

4.1 Results from experiments

25 4.2 PAPA mooring

~~As a first marine test location we choose the PAPA mooring in the east Pacific. Results are presented from one short summer case study and from 16 month-long simulations distributed throughout the year.~~

4.1.1 Case study

4.1.1 PAPA mooring – Case study

During 11-15 July 2014, the PAPA mooring briefly experienced an atmospheric cold advection event, followed by a period of weak advection, which was finally ended by warm advection (not shown). A cloud, which initially caps the boundary layer, rises and dissipates after about two days. Only during the last day does a cloud form again, associated with the warm advection.

AOSCM-6h reproduces the general temporal evolution as given by the forcing, but shows a mismatch in cloud height of up to 500 m, associated with temperature and moisture biases (Fig. 6 a and b). Modelled temperatures are overestimated at and below the reanalysis cloud height and are underestimated above, with cold biases peaking at the height of the modelled cloud. In addition, the AOSCM produces too much water vapour mixing ratio relative to ERA-Interim. In the reanalysis, the cloud dissipates during 13 July, whereas at least a thin cloud is persisting for most of the simulation time in the three model experiments. The atmospheric boundary layer height varies around a depth of 500 m and the marine-oceanic turbocline stays shallow, reaching at most 20 m (Fig. 6c). Atmospheric evolution and biases are similar in AOSCM-3h and ASCM-6h. During a period of weak atmospheric advection, the frequency with which forcing information is updated is thus not influencing the evolution of the coupled column.

Figure 7 summarizes the comparison between the modelled surface parameters and the PAPA measurements. If the model forcing is updated less frequently (A(O)SCM-6h), oscillations in the wind arise with larger amplitude than in AOSCM-3h (Fig. 7f). Oscillations occur mainly during periods of weak wind forcing and their amplitude increases with height (not shown). They are a sign of the column not being in geostrophic equilibrium and are enhanced if applying pressure gradient forcing, as this adds momentum to the column. At the location of the PAPA mooring, the frequency of inertial oscillations is about 16 h. A footprint of the artificial inertial oscillations is visible in the boundary layer height (Fig. 6a) and the turbulent surface fluxes (Fig. 7d, e). The flux oscillations arise from the oscillating near-surface shear, which generates turbulence. In the coupled simulations, temperature biases peak around 1° C (Fig. 7a, b). In ASCM-6h, a larger 2m-temperature bias can be reduced to similar values if forced with observed hourly SST instead of daily mean SST from ERA-Interim (not shown).

Comparing AOSCM-6h results to reanalysis data and PAPA measurements reveals disagreements in terms of bias signs. On the one hand, the reanalysis, and thus the forcing state, indicates that the AOSCM is too warm and moist near the surface. On the other hand, comparison to PAPA measurements points to an underestimation of atmospheric moisture (too large upward latent heat flux) and too cold near-surface temperatures. These differences might partly be explained by deviations in the SST between reality and ERA-Interim reanalysis, which steer boundary layer dynamics via stability differently in different ways. It is interesting to note that when the atmospheric evolution is nudged to tightly follow tightly nudged to the reanalysis, the cloud structure, as well as short- and long-wave radiation improve compared to measurements, improve (not shown). Near-surface temperature and latent heat flux, however, deviate even further from observations. These differences might partly be due to compensating biases, but could also be due to non-representativeness of the buoy measurements for the model grid box. During the studied period, the AOSCM captures the local observations even with the likely erroneous large-scale forcing. Comparison with the large-scale forcing fields can be used to reveal potential atmospheric model drifts. However, in ERA-Interim the

coupling to the ocean is not interactive and SSTs are only prescribed with daily resolution. One way to overcome this is to use measurements for the analysis since they reflect the observed coupling and are dependent on the true near-surface stability.

The evolution of the atmosphere is also sensitive to the initial conditions. Initializing the model only six hours later increases the biases during the final warm air advection period (not shown). In this simulation the cloud cover is underestimated, thus giving increased biases in the radiative fluxes at the surface. Furthermore, in this setup, a strong sensitivity to forcing frequency can be diagnosed, as these biases do not occur in AOSCM-3h results. Again, nudging the wind down to the surface removes the cloud biases. Initializing 18 hours earlier, on the other hand, ~~does~~ only weakly influence the results.

4.1.2 PAPA mooring – Statistical assessment

~~A set of root~~ Root mean square error (RMSE) statistics ~~summarizing results of,~~ relative to ERA-Interim and observations,
10 summarize results from sixteen simulations for the main three setups AOSCM-6h, ASCM-6h and AOSCM-3h ~~is presented in~~
(Tables 2 and 3- ~~Statistical significance is assessed by testing-~~). Statistical significant differences are assessed by comparing
the two mean values and their range of one standard deviation ~~to be disjoint-~~ . If the values do not overlap considering only the
range of variability from one variable we call this one-sided statistically significant. Results are separately compiled for warm
and cold periods (not shown in the tables, only in Fig. 8), with eight of the sixteen simulations falling into each category. Here,
15 warm cases are characterised by a mean ocean mixed-layer depth of less than 10 m ~~(November-April~~ June-September) and cold
cases by more than 30 m ~~(June-September)-November-April)~~ . Results based on oceanic profiles are not included because the
variability produced by experiment setups is less than the variability among the sixteen different periods.

AOSCM-6h and ASCM-6h exhibit similar monthly mean biases in the considered parameters. Daily-mean SSTs used to
force ASCM-6h simulations are one-sided statistically significantly superior to SSTs modelled by the AOSCM-6h. Reduced
20 variability is due to a coarser temporal resolution of the forcing. The signal is largest in summer months and can be explained
by SST cold biases in AOSCM runs, in some cases also present during winter. This SST bias in the AOSCM is part of a
temperature bias dipole in the ocean column which intensifies with runtime. Refray et al. (2015) discuss a sensitivity of the
mixing depth to a TKE length parameter, describing the deepening of the mixed layer by near-inertial waves and ocean swell
or waves. In the standard TKE setup used in EC-Earth v3, the parameter is either a function of latitude and set ~~as to~~ 30 m at
25 the PAPA station (standalone ocean model) or set to 0 m so that no additional mixing is supplied (coupled model). Setting the
parameter to 0 m, thus not considering additional mixing by waves, produces very similar results to the ones presented here
(Tables 2 and 3), but cold biases during summer months are now replaced by warm biases of roughly equal strength and too
shallow mixed layers (not shown). Reducing the value of the parameter to 10 m, as suggested by Refray et al. (2015), and thus
limiting an increase of mixing depth by internal mixing, alleviates the observed summer cold biases (not shown).

30 In general, the AOSCM can successfully reproduce atmosphere-only results. The added benefit of a coupled simulation is
that the interactions between the marine and atmospheric boundary layer are resolved and can be studied directly. AOSCM-3h,
forced with atmospheric data of higher temporal frequency, is better able to represent measurements and model reference data
than AOSCM-6h, with largest impact on momentum. Again the annual mean signal originates mainly from one subperiod, in
this case the cold months, when AOSCM-3h performance exceeds that of AOSCM-6h in several aspects. Firstly, wind biases

are statistically significantly reduced in the whole atmospheric column. Secondly, the mean column state bias is reduced, although not ~~statistically significantly to an extent that is statistically significant~~. In addition to improvements in the mean state, an increase in the depth of the mixed layer is found in both atmosphere and ocean (not shown), related to reduced coupling biases, though ~~again the change is~~ not statistically significant.

5 Higher frequency forcing is, in many cases, linked to pronounced improvements in wind representation through reduction of oscillations in wind speed. One way of emulating this effect is to relax horizontal wind profiles in the model towards those provided by reanalyses. Results from simulations ~~applying wind relaxation over the whole column with a timescale of 1 h with AOSCM-Nuv0km1h settings~~ are summarized in the 4th ~~columns of the tables~~ column of Tables 2 and 3. Atmospheric column and surface wind biases can be reduced by nudging the wind, ~~as well as SST biases~~. SST biases are also alleviated during cold months (not shown). ~~Atmospheric but atmospheric~~ temperature and humidity biases are not sensitive to wind nudging. However, the ocean is affected through momentum transport during cold months. The ocean responds similarly as in AOSCM-3h simulations, though only one-sided statistically significant. The ocean mixed layer is ~~deepening~~ deeper whereas the annual mean atmospheric boundary layer is shallower than in all other configurations. Thus, nudging of the wind components can be used to reduce model biases. However, it has to be noted that wind nudging perturbs the momentum balance. Especially when studying boundary layer turbulence parametrization, nudging interferes with the performance of the parametrization.

In some simulations, the free troposphere drifts away from the reanalysis state. A weak atmospheric nudging of the four main prognostic variables temperature, moisture and horizontal wind above 3 km (i.e. well above the boundary layer, ~~AOSCM-N3km6h~~) reduces biases in the troposphere even below 3 km (Table 3). At the same time, the ocean state is only weakly influenced by deepening the ocean mixed layer. This way of nudging can be used even when the momentum balance at the surface is required to be unperturbed in the boundary layer.

Accumulated energy fluxes (~~see Equ. (5)~~) and accumulated precipitation from the main three sensitivity runs are visualized in Fig. 8, resolving individual cases. Modelled fluxes are sampled every hour to match the measurement frequency. In summary, the ~~mode~~ surface receives too little energy ~~in the model~~ during summer and loses too much energy during winter. Considering all seasons, AOSCM-3h/6h perform best compared to ASCM-6h, but the main signal appears in different seasons. AOSCM-3h gives the best net surface energy balance during summer, and during winter AOSCM-6h exceeds the other setups. However, the overall variability is large and individual cases may show different results. Precipitation is larger during winter and the model produces generally more rain than observed.

4.2 Tropical Atlantic

30 4.1.1 Tropical Atlantic

Our second marine test location is the tropical Atlantic. During the time of the case study, June 2014, SSTs in this area cool by 4 °C. This trend is part of the cooling of the eastern tropical Atlantic due to its annual cycle (Lübbecke et al., 2010; Xie and Carton, 2004). To estimate AOSCM performance in this region, we perform a base simulation using only advective tendencies

(~~F01-AOSCM-Jun1~~ in Fig. 9). Within ten days, two main biases develop, one atmospheric and one oceanic. Firstly, atmospheric temperatures between 0.5 km and 1.5 km are overestimated, while moisture is underestimated over the same height interval (not shown). The patterns of these atmospheric biases are closely correlated and peak between June 14 and 17. Both biases are flow-dependent, i.e. they are not connected to a model drift but reduce again after the June 17. The ~~integrated-bias (RMSE~~
5 ~~)RMSE~~ in the lower 1.5 km develops similarly for temperature (Fig. 9a) and moisture (not shown). Secondly, although the cooling of the ocean surface layer is partly captured, its amplitude is underestimated, leading to a warm bias of around 2°C at the end of the simulation (Fig. 9b). It is worth noting that the ocean column follows the observations well until five days into the simulation, when the observed ocean cooling can no longer be matched by the model. The SST bias grows, and after a short period of recovery around day 7 to 10, it increases during the course of two days and does not reduce significantly afterwards.
10 Emergence of a model warm bias during the build up of SST cooling is a common model bias in the tropical Atlantic (Breugem et al., 2008; Toniazzo and Woolnough, 2014; Voldoire et al., 2018).

We demonstrate how the origins of the two biases can be traced in-back using several sensitivity experiments. Nudging above 3 km, as done in the PAPA case, also reduces the near surface bias in moisture and temperature, but in a weaker form (not shown). The atmospheric bias can largely be alleviated by nudging prognostic variables above 1 km with a time-scale
15 of ~~$\tau = \tau_a = 6\text{h}$~~ ($\tau = \tau_a = 6\text{h}$ (AOSCM-N1km6h)). However, the SST evolution is not influenced by atmospheric relaxation to a height of 1 km. Inspired by the indication of a flow dependent bias in the standard setup, ~~F12 and F15 show simulations with the same setup as F01 but initialized at days 12 and 15, respectively~~ AOSCM-Jun12 and AOSCM-Jun15 are initialized further into the period. Initializing the ocean between ~~June 10-15~~ 12-15 June, when the largest SST bias develops, strongly improves the SST representation in the AOSCM. The atmospheric biases develop again, stronger ~~in F12 than in F15~~ when initialising on
20 12 June than 15 June.

Finally, the SST bias can be studied by decoupling the ocean from the atmosphere. This can either be done by nudging the atmospheric column strongly (e.g. ~~$\tau = 0.25$~~ $\tau_a = 0.25$ h) down to the surface (not shown) or by performing an ocean-only simulation (OSCM, Fig. 9b). Both simulations produce very similar evolutions of the SST bias (not shown). The similarities point to an oceanic origin of the SST bias, while differences to ~~F01~~ the simulation indicated 1 June indicate the impact of
25 additional feedbacks on the bias development. Observations of the ocean current vector (available at 10 m depth during this period) indicate two maxima of about 50 cm s⁻¹ at ~~June 5 and June~~ June and 10 June (not shown), coinciding with periods of maximum SST bias in all simulations initialized at ~~June 1-1~~ 1 June. The ocean model currently does not capture horizontal temperature advection. Temperature changes related to advection hence cannot be reproduced by the ~~SCM~~ OSCM. Heat budget analyses shows these terms to be small in the region of the experiment (Giordani et al., 2013; Deppenmeier et al., 2018).
30 However, short time scale events are likely to be missed and can impact the budget on shorter times. Another possible oceanic origin of the bias is insufficient ocean vertical mixing of near-surface warming into the ocean. The importance of and sensitivity to vertical ocean mixing has been observed and demonstrated by Hazeleger and Haarsma (2005) and Hummels et al. (2013), among others. Too little mixing of cold water masses into the well-mixed layer as well as too little heat transport from the upper layer into the deep ocean leads to artificially warm SSTs, similar to those observed towards the end of the simulation.
35 In the current setup, upper ocean vertical mixing only penetrates the first upper meters of the ocean column, and then stops

abruptly. Replacing the relatively strongly stratified observed profile with the more gradual profile from ORAS4 deepens the mixed-layer and improves the results slightly, but still only down to 20 m (not shown). This feature and its impact on the SST evolution are currently under investigation.

4.2 North Polar region

5 4.1.1 North Polar region

Finally, the AOSCM is used to simulate a moist~~intrusion~~, warm air advection event in the Arctic summer. Figure 10 shows the evolution of the liquid-water content for the reference LES simulation (a) together with observational estimates of cloud top and different versions of the ASCM and AOSCM (b-f). The ~~atmosphere-only~~ atmosphere-only run (b) is the most similar to the LES as it keeps a cloud with a top at about 200 m during the whole simulation. The formation of the cloud in the beginning
10 of the simulations (not shown) is quite different. The LES initially forms a cloud with a top at about 800 m that is slowly descending under the influence of the subsidence. In all the AOSCM simulations, a cloud also forms at that height, dissipates,
and after a few hours a new cloud appears with a top at around 200 m. The evolution of the simulated cloud between hour 12 and 48 is diverging from a similar state at around hour 12, with sensitivity to coupling and time-step. In a simulation with short timesteps in all model components and coupling at every time step (~~$\tau = 450$~~ $\Delta t = 450$ s, Fig. 10.c),
15 into a double-layered cloud at about hour 32. Using a longer time-step, 2700 s as is used in EC-Earth (Fig. 10.d), results in a descending and thinning cloud, which at the end of the period is only present close to the surface. Returning to a shorter time-step of 900 s in the atmosphere, but keeping the ocean, ice, and coupling at 2700 s, results in a cloud that keeps its top at 200 m for a longer time (Fig. 10.e). Two simulations are run where first the temperature and then the moisture advection is turned off, the resulting cloud for the first simulation is not that different (compare Fig. 10.e and f). When the moisture
20 advection is removed, the cloud disappears before hour 12 (not shown).

The integrated liquid-water content between hour 12 and 48 is presented in Fig. 11. The LES liquid water path (red) varies between 50 and 150 g m⁻² during the simulation, while the observations show a wider range. Only the ASCM (blue dashed line) reaches observed values, the coupled simulations (thick lines in blue, magenta, and cyan) produce smaller liquid water paths and little variability in sensitivity tests. In this figure, the importance of advection of moisture is clearly seen (dash-dotted
25 cyan line, near the bottom of the figure). Without temperature advection (cyan dashed line), the cloud stays cooler and can thus hold more liquid water.

For this Arctic case, the cloud both shields the surface from the sun and increases the long-wave radiation. For the short-wave cloud effect, the surface albedo plays an important role. As discussed in Tjernström et al. (2015), the surface is changing characteristics rapidly as energy is absorbed and melting occurs. Figure 12 shows the initial albedo in the simulation (averaged
30 over hour 1) for the various simulations, calculated using the model's incoming and reflected shortwave radiation. The albedo during the first hour is a result of both the initialization (same for all coupled simulations) and processes changing the albedo. The albedo in the AOSCM is calculated in LIM based on the sea-ice state, and is quite different from the default albedo climatology provided to the ASCM. In the coupled simulations, the albedo spans from about 63 to 74 %, while the ASCM's

albedo is at 58 %. The LES value is 65 % and constant in time. Some of these differences can be explained by how the cloud affects the diffuse radiation and thereby the amount of reflected light at the surface. The albedo decreases over the 48 hours in all simulations, the most (≥ 15 %) in the simulation where the cloud disappears. This illustrates the complexity of the coupling and ~~all these~~ how these different processes influence the net energy received by the surface.

In Fig. 13, the net mean energy at the surface, with and without the sensible and latent heat flux contribution, is shown. The deviation from the dashed 1-to-1 line gives the magnitude of the turbulent fluxes. In all simulations, the turbulent fluxes present a net source of energy for the surface i.e. stably stratified conditions dominate. However, the observational estimate (black dot) shows a small net upward flux and the overall available energy at the surface is about 40 W m^{-2} less. This analysis points to differences in the vertical structure of the atmosphere.

5 Summary and outlook

4.1 Evaluation of experiments

~~We demonstrate a coupled atmosphere-ocean single-column model (AOSCM) following the setup of the next version climate model EC-Earth (Hazeleger et al., 2010). The AOSCM is designed for studying the physical interaction of oceanic and atmospheric boundary layer processes as well as technical aspects of the coupling. Here, we demonstrate the functionalities of the model by applying it at three locations and present analysis showing the versatility of the tool. Furthermore, we highlight avenues of how to design process studies using the AOSCM.~~

~~The AOSCM reproduces the evolution of the Earth system column and can simulate it reliably during short and month-long experiments. We demonstrate the model at three different locations, with varying degree of forcing complexity, in a framework with coupled and individual model component simulations.~~ Based on results from the PAPA station and considering atmosphere-only setups as a benchmark, the AOSCM is performing well and is in some cases even superior to the ASCM (~~atmosphere single-column model~~). Extending an ASCM to an AOSCM allows us to resolve coupled processes. A sensitivity to the forcing frequency is apparent, which is largely related to deteriorated winds in simulations forced with ~~infrequent~~ temporally coarser data. Both the horizontal advection and the vertical wind forcing are captured more realistically with increased forcing frequency. It should be noted that a linear interpolation will result in deteriorated results even for perfect forcing data. A linear functionality is likely not a good assumption for the temporal evolution of the forcing fields. Wind components can be nudged to alleviate oscillations in wind speed, while this process does not influence temperature and moisture evolution. Nudging wind down to the surface ensures that atmospheric momentum biases do not deteriorate ocean performance, but the nudging interferes with parametrizations connected to momentum, e.g. turbulence. Nudging all fields above the boundary layer with weak nudging time scale remedies biases in the free troposphere while allowing to focus on the freely evolving surface interactions. At the PIRATA buoy, nudging above 3 km also reduces time-dependent atmospheric biases considerably. Biases are almost completely removed when reducing the lowest nudged height to 1 km. At the sea surface, a temperature bias remains even in an ocean-only setting or with a strongly nudged atmosphere. Both biases are sensitive to initialization time of the simulation. The sensitivity tests performed for the Arctic case, compared with both observations and an idealized LES simulation, show

the complexity of how the coupling between the lower atmospheric structure, surface properties and clouds affect the energy budget at the surface. Further analysis of this case is ongoing.

Based on ~~our results~~ fluid dynamical theory and our results, we recommend to force the AOSCM with advective tendencies and pressure gradient forcing in the atmosphere. The forcing frequency should be kept as ~~short~~ high as possible, ideally based on information from the host model at every time step, e.g. for model development. If model drifts or other persistent biases are identified, nudging profiles down to the surface, or above the processes of interest ~~can be added to enhance~~, can enhance the stability of the simulation and keep close analogies with observations. Running several sensitivity experiments based on different forcing and coupling settings, periods for further parameter sensitivity experiment can be identified and then studied inexpensively in the AOSCM.

5 Summary and outlook

We demonstrate a coupled atmosphere-ocean single-column model (AOSCM) following the setup of a future version of the climate model EC-Earth (v4, currently v3). The AOSCM is designed to study the physical interaction of oceanic and atmospheric boundary layer processes as well as technical aspects of the coupling. Here, we demonstrate the functionalities of the model by applying it at three locations and present analysis showing the versatility of the tool. Furthermore, we discuss possibilities of how to design process studies using the AOSCM.

As the AOSCM consists of individually compiled components, it is relatively straightforward to update and exchange routines, e.g. when newer cycles become available. At this stage, the capabilities of the EC-Earth AOSCM can be extended along several avenues. Even though the hydrometeorological variables cloud liquid, ice, rain, snow, and cloud cover are treated prognostically in ~~OIFS~~ OpenIFS, their profiles can currently not be forced by advective tendencies or nudging. The missing advection terms can be partially included by adding the advective tendencies of cloud liquid and ice mixing ratios to the advective tendency of water vapour mixing ratio. Similarly, advective tendency forcing could be added to both the sea-ice and ocean equation systems. Apart from the necessary model infrastructure, this requires observations or model data to compile the relevant forcing. ~~With~~ Based on the current model without advective forcing, one option is to limit the run time of the model. In that case the relative stationarity of ocean and sea-ice ~~relative~~ with respect to atmospheric movement can be assumed. ~~The other~~ Another option is to relax the ocean profile towards a reference profile, either across the whole column or only below the mixed layer. A similar feature, namely an adaptive relaxation height, is currently not available in the atmospheric part of the AOSCM. It is ~~however~~, however, possible to nudge only above a constant level, as we demonstrate. If this height is chosen well above the boundary layer, ~~this still ensures~~ it is still ensured that the boundary layer is not affected by nudging, while biases in the free troposphere are limited.

Even though the model can be extended in numerous ways, it is a useful tool to explore several open science questions already ~~at the current stage~~ in its current form. A non-extensive list of problems that can be tackled includes:

In the marine environment simulations similar to ASTEX (Bretherton et al., 1999; de Roode et al., 2016), describing stratocumulus to cumulus transition, can be performed with coupled models. Independent of the location where it is placed, a coupled atmosphere-ocean SCM allows to study the concept of stochastic air-sea fluxes decoupled from large-scale motions (Williams, 2012). An AOSCM, including sea-ice, presents the opportunity to study physical processes in the polar regions.

5 The atmosphere-ice-ocean system is strongly coupled and sensitive to even small energy imbalances at the interfaces, and thus to the correct representation of sea-ice fluxes (Bourassa et al., 2013; Spengler et al., 2016). Understanding of the processes relevant for sea-ice melting and freeze-up in the changing polar regions is crucial. Work can be done along the lines of previous studies, like [Pithan et al. \(2016\)](#), investigating Arctic air mass transformations, and the local interactions with the snow surface (Sterk et al., 2013; Lecomte et al., 2015).

10 The AOSCM is a tool for investigating [local, vertical](#) interactions at the air-ice-ocean interface. ~~It can~~ [All physical parametrizations implemented in the individual model components \(see respective references\), and their interactions, can be tested in the current setup. The AOSCM can furthermore](#) yield insights into the physical processes responsible for model shortcomings in areas where the coupling at the interface plays ~~a considerable~~ [an important](#) role. With its low computational cost ~~it can~~, [it can furthermore](#) help understand how choices of coupling parameters and numerical setup influence the evolution of the whole

15 column.

6 Acknowledgements

We would like to thank for support from (O)IFS, OASIS, NEMO, and LIM communities. In addition we would like [to](#) thank ECMWF for providing ERA-Interim data and support compiling forcing information, especially Nils Wedi, Filip Vana, Glenn Carver, Irina Sandu, and Maike Ahlgrim. In addition, we would like to thank the OCS and GTMBA Project Office of

20 NOAA/PMEL for providing measurements at the PAPA and PIRATA buoys, the ACAS team under the lead of Michael Tjernström for the observational data and Georgia Sotiropoulou for providing the LES data. [The project received support from the European Union's Horizon 2020 project APPLICATE under grant agreement No 727862 and from the EU FP7/2007-2013 under grant agreement no. 603521, project PREFACE.](#)

7 Code and data availability

25 [Usage of and access to the EC-Earth source code are licensed to affiliates of institutions which are members of the EC-Earth consortium. More information on EC-Earth is available at <http://www.ec-earth.org>. As the AOSCM includes the ECMWF OpenIFS single-column model, use of the AOSCM model also requires an OpenIFS license agreement, which can be obtained from ECMWF for free \(<https://software.ecmwf.int/wiki/display/OIFS/OpenIFS+Home>\).](#)

The model source code is available from the EC-Earth development portal:

30 *svn checkout <https://svn.ec-earth.org/ecearth3/branches/development/2016/r2740-coupled-SCM> r2740-coupled-SCM.*

~~More information~~ [A tagged version on which results presented here are based can be found at *https://svn.ec-earth.org/ecearth3/tags/AOSCM*](https://svn.ec-earth.org/ecearth3/tags/AOSCM)
[More information on the AOSCM](https://dev.ec-earth.org/projects/ecearth3/wiki/Single_Column_Coupled_EC-Earth) and example data can be found on the EC-Earth AOSCM wiki page: https://dev.ec-earth.org/projects/ecearth3/wiki/Single_Column_Coupled_EC-Earth.

References

- Baas, P., Bosveld, F., Lenderink, G., van Meijgaard, E., and Holtslag, A. A. M.: How to design single-column model experiments for comparison with observed nocturnal low-level jets, *Quarterly Journal of the Royal Meteorological Society*, 136, 671–684, <https://doi.org/10.1002/qj.592>, <http://dx.doi.org/10.1002/qj.592>, 2010.
- 5 Balmaseda, M. A., Mogensen, K., and Weaver, A. T.: Evaluation of the ECMWF ocean reanalysis system ORAS4, *Quarterly Journal of the Royal Meteorological Society*, 139, 1132–1161, <https://doi.org/10.1002/qj.2063>, <http://dx.doi.org/10.1002/qj.2063>, 2013.
- Balsamo, G., Beljaars, A., Scipal, K., Viterbo, P., van den Hurk, B., Hirschi, M., and Betts, A. K.: A Revised Hydrology for the ECMWF Model: Verification from Field Site to Terrestrial Water Storage and Impact in the Integrated Forecast System, *Journal of Hydrometeorology*, 10, 623–643, <https://doi.org/10.1175/2008JHM1068.1>, <http://dx.doi.org/10.1175/2008JHM1068.1>, 2009.
- 10 Basu, S., Holtslag, A. A. M., Van De Wiel, B. J. H., Moene, A. F., and Steeneveld, G.-J.: An inconvenient “truth” about using sensible heat flux as a surface boundary condition in models under stably stratified regimes, *Acta Geophysica*, 56, 88–99, <https://doi.org/10.2478/s11600-007-0038-y>, <http://dx.doi.org/10.2478/s11600-007-0038-y>, 2008.
- Beare, R. J., Macvean, M. K., Holtslag, A. A. M., Cuxart, J., Esau, I., Golaz, J.-C., Jimenez, M. A., Khairoutdinov, M., Kosovic, B., Lewellen, D., Lund, T. S., Lundquist, J. K., McCabe, A., Moene, A. F., Noh, Y., Raasch, S., and Sullivan, P.: An Intercomparison of Large-Eddy Simulations of the Stable Boundary Layer, *Boundary-Layer Meteorology*, 118, 247–272, <https://doi.org/10.1007/s10546-004-2820-6>, <https://doi.org/10.1007/s10546-004-2820-6>, 2006.
- 15 Bechtold, P., Redelsperger, J.-L., Beau, I., Blackburn, M., Brinkop, S., Grandper, J.-Y., Grant, A., Gregory, D., Guichard, F., How, C., and Ioannidou, E.: A GCSS model intercomparison for a tropical squall line observed during toga-coare. II: Intercomparison of single-column models and a cloud-resolving model, *Quarterly Journal of the Royal Meteorological Society*, 126, 865–888, <https://doi.org/10.1002/qj.49712656405>, <http://dx.doi.org/10.1002/qj.49712656405>, 2000.
- 20 Betts, A. K. and Miller, M. J.: A new convective adjustment scheme. Part II: Single column tests using GATE wave, BOMEX, ATEX and arctic air-mass data sets, *Quarterly Journal of the Royal Meteorological Society*, 112, 693–709, <https://doi.org/10.1002/qj.49711247308>, <http://dx.doi.org/10.1002/qj.49711247308>, 1986.
- Bosveld, F. C., Baas, P., Steeneveld, G.-J., Holtslag, A. A. M., Angevine, W. M., Bazile, E., de Bruijn, E. I. F., Deacu, D., Edwards, J. M., Ek, M., Larson, V. E., Pleim, J. E., Raschendorfer, M., and Svensson, G.: The Third GABLS Intercomparison Case for Evaluation Studies of Boundary-Layer Models. Part B: Results and Process Understanding, *Boundary-Layer Meteorology*, 152, 157–187, <https://doi.org/10.1007/s10546-014-9919-1>, <https://doi.org/10.1007/s10546-014-9919-1>, 2014.
- 25 Bourassa, M. A., Gille, S. T., Bitz, C., Carlson, D., Cerveck, I., Clayson, C. A., Cronin, M. F., Drennan, W. M., Fairall, C. W., Hoffman, R. N., Magnusdottir, G., Pinker, R. T., Renfrew, I. A., Serreze, M., Speer, K., Talley, L. D., and Wick, G. A.: High-Latitude Ocean and Sea Ice Surface Fluxes: Challenges for Climate Research, *Bulletin of the American Meteorological Society*, 94, 403–423, <https://doi.org/10.1175/BAMS-D-11-00244.1>, <http://dx.doi.org/10.1175/BAMS-D-11-00244.1>, 2013.
- 30 Bourlès, B., Lumpkin, R., McPhaden, M. J., Hernandez, F., Nobre, P., Campos, E., Yu, L., Planton, S., Busalacchi, A., Moura, A. D., Servain, J., and Trotte, J.: THE PIRATA PROGRAM, *Bulletin of the American Meteorological Society*, 89, 1111–1126, <https://doi.org/10.1175/2008BAMS2462.1>, 2008.
- 35 Bretherton, C. S., Krueger, S. K., Wyant, M. C., Bechtold, P., Van Meijgaard, E., Stevens, B., and Teixeira, J.: A GCSS Boundary-Layer Cloud Model Intercomparison Study Of The First Astex Lagrangian Experiment, *Boundary-Layer Meteorology*, 93, 341–380, <https://doi.org/10.1023/A:1002005429969>, <https://doi.org/10.1023/A:1002005429969>, 1999.

- Breugem, W.-P., Chang, P., Jang, C., Mignot, J., and Hazeleger, W.: Barrier layers and tropical Atlantic SST biases in coupled GCMs, *Tellus A: Dynamic Meteorology and Oceanography*, 60, 885–897, <https://doi.org/10.1111/j.1600-0870.2008.00343.x>, <https://doi.org/10.1111/j.1600-0870.2008.00343.x>, 2008.
- Clayson, C. A. and Chen, A.: Sensitivity of a Coupled Single-Column Model in the Tropics to Treatment of the Interfacial Parameterizations, *Journal of Climate*, 15, 1805–1831, [https://doi.org/10.1175/1520-0442\(2002\)015<1805:SOACSC>2.0.CO;2](https://doi.org/10.1175/1520-0442(2002)015<1805:SOACSC>2.0.CO;2), [http://dx.doi.org/10.1175/1520-0442\(2002\)015<1805:SOACSC>2.0.CO;2](http://dx.doi.org/10.1175/1520-0442(2002)015<1805:SOACSC>2.0.CO;2), 2002.
- Cuxart, J., Holtslag, A. A. M., Beare, R. J., Bazile, E., Beljaars, A., Cheng, A., Conangla, L., Ek, M., Freedman, F., Hamdi, R., Kerstein, A., Kitagawa, H., Lenderink, G., Lewellen, D., Mailhot, J., Mauritsen, T., Perov, V., Schayes, G., Steeneveld, G.-J., Svensson, G., Taylor, P., Weng, W., Wunsch, S., and Xu, K.-M.: Single-Column Model Intercomparison for a Stably Stratified Atmospheric Boundary Layer, *Boundary-Layer Meteorology*, 118, 273–303, <https://doi.org/10.1007/s10546-005-3780-1>, <https://doi.org/10.1007/s10546-005-3780-1>, 2006.
- Day, J. J., Svensson, G., Brooks, I. M., Bitz, C., Broman, L., Carver, G., Chevallier, M., Goessling, H., Hartung, K., Jung, T., Kay, J. E., Kolstad, E. W., Perovich, D., Screen, J., Siemen, S., and Váña, F.: The Abisko Polar Prediction School, *Bulletin of the American Meteorological Society*, 98, 445–447, <https://doi.org/10.1175/BAMS-D-16-0119.1>, <https://doi.org/10.1175/BAMS-D-16-0119.1>, 2017.
- de Roode, S. R., Sandu, I., van der Dussen, J. J., Ackerman, A. S., Blossey, P., Jarecka, D., Lock, A., Siebesma, A. P., and Stevens, B.: Large-Eddy Simulations of EUCLIPSE–GASS Lagrangian Stratocumulus-to-Cumulus Transitions: Mean State, Turbulence, and Decoupling, *Journal of the Atmospheric Sciences*, 73, 2485–2508, <https://doi.org/10.1175/JAS-D-15-0215.1>, <https://doi.org/10.1175/JAS-D-15-0215.1>, 2016.
- Dee, D. P., Uppala, S. M., Simmons, A. J., Berrisford, P., Poli, P., Kobayashi, S., Andrae, U., Balmaseda, M. A., Balsamo, G., Bauer, P., Bechtold, P., Beljaars, A. C. M., van de Berg, L., Bidlot, J., Bormann, N., Delsol, C., Dragani, R., Fuentes, M., Geer, A. J., Haimberger, L., Healy, S. B., Hersbach, H., Hólm, E. V., Isaksen, I., Kållberg, P., Köhler, M., Matricardi, M., McNally, A. P., Monge-Sanz, B. M., Morcrette, J.-J., Park, B.-K., Peubey, C., de Rosnay, P., Tavolato, C., Thépaut, J.-N., and Vitart, F.: The ERA-Interim reanalysis: configuration and performance of the data assimilation system, *Quart. J. Roy. Meteor. Soc.*, 137, 553–597, <https://doi.org/10.1002/qj.828>, <http://dx.doi.org/10.1002/qj.828>, 2011.
- Deppenmeier, A.-L., Haarsma, R. J., and Hazeleger, W.: Ocean mixing and cloud feedbacks linked to tropical Atlantic SST Variability, in preparation, 2018.
- Egger, J. and Schmid, S.: Elimination of spurious inertial oscillations in boundary-layer models with time-dependent geostrophic winds, *Boundary-Layer Meteorology*, 43, 393–402, <https://doi.org/10.1007/BF00121715>, <http://dx.doi.org/10.1007/BF00121715>, 1988.
- Fofonoff, N. and Millard, R. C.: Algorithms for Computation of Fundamental Properties of Seawater, *Unesco Technical Papers in Marine Science*, 1983.
- Gaspar, P., Grégoris, Y., and Lefevre, J.-M.: A simple eddy kinetic energy model for simulations of the oceanic vertical mixing: Tests at station Papa and long-term upper ocean study site, *Journal of Geophysical Research: Oceans*, 95, 16 179–16 193, <https://doi.org/10.1029/JC095iC09p16179>, <http://dx.doi.org/10.1029/JC095iC09p16179>, 1990.
- Ghan, S., Randall, D., Xu, K.-M., Cederwall, R., Cripe, D., Hack, J., Iacobellis, S., Klein, S., Krueger, S., Lohmann, U., Pedretti, J., Robock, A., Rotstain, L., Somerville, R., Stenchikov, G., Sud, Y., Walker, G., Xie, S., Yio, J., and Zhang, M.: A comparison of single column model simulations of summertime midlatitude continental convection, *Journal of Geophysical Research: Atmospheres*, 105, 2091–2124, <https://doi.org/10.1029/1999JD900971>, <http://dx.doi.org/10.1029/1999JD900971>, 2000.

- Giordani, H., Caniaux, G., and Voldoire, A.: Intraseasonal mixed-layer heat budget in the equatorial Atlantic during the cold tongue development in 2006, *Journal of Geophysical Research: Oceans*, 118, 650–671, 2013.
- Goyette, S. and Perroud, M.: Interfacing a one-dimensional lake model with a single-column atmospheric model: Application to the deep Lake Geneva, Switzerland, *Water Resources Research*, 48, n/a–n/a, <https://doi.org/10.1029/2011WR011223>, <http://dx.doi.org/10.1029/2011WR011223>, 2012.
- Guichard, F., Petch, J. C., Redelsperger, J.-L., Bechtold, P., Chaboureaud, J.-P., Cheinet, S., Grabowski, W., Grenier, H., Jones, C. G., Köhler, M., Piriou, J.-M., Tailleux, R., and Tomasini, M.: Modelling the diurnal cycle of deep precipitating convection over land with cloud-resolving models and single-column models, *Quarterly Journal of the Royal Meteorological Society*, 130, 3139–3172, <https://doi.org/10.1256/qj.03.145>, <http://dx.doi.org/10.1256/qj.03.145>, 2004.
- 10 Hack, J. J. and Pedretti, J. A.: Assessment of Solution Uncertainties in Single-Column Modeling Frameworks, *Journal of Climate*, 13, 352–365, [https://doi.org/10.1175/1520-0442\(2000\)013<0352:AOSUIS>2.0.CO;2](https://doi.org/10.1175/1520-0442(2000)013<0352:AOSUIS>2.0.CO;2), [http://dx.doi.org/10.1175/1520-0442\(2000\)013<0352:AOSUIS>2.0.CO;2](http://dx.doi.org/10.1175/1520-0442(2000)013<0352:AOSUIS>2.0.CO;2), 2000.
- Hazeleger, W. and Haarsma, R. J.: Sensitivity of tropical Atlantic climate to mixing in a coupled ocean–atmosphere model, *Climate dynamics*, 25, 387–399, 2005.
- 15 Hazeleger, W., Severijns, C., Semmler, T., Ștefănescu, S., Yang, S., Wang, X., Wyser, K., Dutra, E., Baldasano, J. M., Bintanja, R., Bougeault, P., Caballero, R., Ekman, A. M. L., Christensen, J. H., van den Hurk, B., Jimenez, P., Jones, C., Kållberg, P., Koenigk, T., McGrath, R., Miranda, P., Noije, T. V., Palmer, T., Parodi, J. A., Schmith, T., Selten, F., Storelvmo, T., Sterl, A., Tapamo, H., Vancoppenolle, M., Viterbo, P., and Willén, U.: EC-Earth: A Seamless Earth-System Prediction Approach in Action, *Bull. Am. Meteorol. Soc.*, 91, 1357–1363, <https://doi.org/10.1175/2010BAMS2877.1>, <http://dx.doi.org/10.1175/2010BAMS2877.1>, 2010.
- 20 Hazeleger, W., Wang, X., Severijns, C., Ștefănescu, S., Bintanja, R., Sterl, A., Wyser, K., Semmler, T., Yang, S., van den Hurk, B., van Noije, T., van der Linden, E., and van der Wiel, K.: EC-Earth V2.2: description and validation of a new seamless earth system prediction model, *Clim. Dyn.*, 39, 2611–2629, <https://doi.org/10.1007/s00382-011-1228-5>, <http://dx.doi.org/10.1007/s00382-011-1228-5>, 2012.
- Holtlag, B.: Preface: GEWEX atmospheric boundary-layer study (GABLS) on stable boundary layers, *Boundary-Layer Meteorology*, 118, 243–246, 2006.
- 25 Hourdin, F., Mauritsen, T., Gettelman, A., Golaz, J.-C., Balaji, V., Duan, Q., Folini, D., Ji, D., Klocke, D., Qian, Y., Rauser, F., Rio, C., Tomassini, L., Watanabe, M., and Williamson, D.: The Art and Science of Climate Model Tuning, *Bulletin of the American Meteorological Society*, 98, 589–602, <https://doi.org/10.1175/BAMS-D-15-00135.1>, <https://doi.org/10.1175/BAMS-D-15-00135.1>, 2017.
- Hummels, R., Dengler, M., and Bourlès, B.: Seasonal and regional variability of upper ocean diapycnal heat flux in the Atlantic cold tongue, *Progress in Oceanography*, 111, 52 – 74, <https://doi.org/https://doi.org/10.1016/j.pocean.2012.11.001>, <http://www.sciencedirect.com/science/article/pii/S0079661112001607>, 2013.
- 30 IOC, S. and IAPSO: The international thermodynamic equation of seawater - 2010: Calculation and use of thermodynamic properties, Tech. rep., Intergovernmental Oceanographic Commission, http://www.teos-10.org/pubs/TEOS-10_Manual.pdf, 2010.
- Klein, S. A., McCoy, R. B., Morrison, H., Ackerman, A. S., Avramov, A., Boer, G. d., Chen, M., Cole, J. N. S., Del Genio, A. D., Falk, M., Foster, M. J., Fridlind, A., Golaz, J.-C., Hashino, T., Harrington, J. Y., Hoose, C., Khairoutdinov, M. F., Larson, V. E., Liu, X., Luo, Y., McFarquhar, G. M., Menon, S., Neggers, R. A. J., Park, S., Poellot, M. R., Schmidt, J. M., Sednev, I., Shipway, B. J., Shupe, M. D., Spangenberg, D. A., Sud, Y. C., Turner, D. D., Veron, D. E., Salzen, K. v., Walker, G. K., Wang, Z., Wolf, A. B., Xie, S., Xu, K.-M., Yang, F., and Zhang, G.: Intercomparison of model simulations of mixed-phase clouds observed during the ARM Mixed-Phase Arctic Cloud

- Experiment. I: single-layer cloud, *Quarterly Journal of the Royal Meteorological Society*, 135, 979–1002, <https://doi.org/10.1002/qj.416>, <http://dx.doi.org/10.1002/qj.416>, 2009.
- Kraus, E. B. and Turner, J. S.: A one-dimensional model of the seasonal thermocline II. The general theory and its consequences, *Tellus*, 19, 98–106, <https://doi.org/10.3402/tellusa.v19i1.9753>, <https://doi.org/10.3402/tellusa.v19i1.9753>, 1967.
- 5 Large, W. G., McWilliams, J. C., and Doney, S. C.: Oceanic vertical mixing: A review and a model with a nonlocal boundary layer parameterization, *Reviews of Geophysics*, 32, 363–403, <https://doi.org/10.1029/94RG01872>, <http://dx.doi.org/10.1029/94RG01872>, 1994.
- Lecomte, O., Fichet, T., Massonnet, F., and Vancoppenolle, M.: Benefits from representing snow properties and related processes in coupled ocean–sea ice models, *Ocean Modelling*, 87, 81 – 85, <https://doi.org/http://doi.org/10.1016/j.ocemod.2014.11.005>, <http://www.sciencedirect.com/science/article/pii/S1463500314001723>, 2015.
- 10 Lemarié, F., Blayo, E., and Debreu, L.: Analysis of Ocean-atmosphere Coupling Algorithms: Consistency and Stability, *Procedia Computer Science*, 51, 2066 – 2075, <https://doi.org/https://doi.org/10.1016/j.procs.2015.05.473>, <http://www.sciencedirect.com/science/article/pii/S1877050915012818>, international Conference On Computational Science, ICCS 2015, 2015.
- Lenderink, G., Siebesma, A. P., Cheinet, S., Irons, S., Jones, C. G., Marquet, P., üLLER, F. M., Olmeda, D., Calvo, J., Sánchez, E., and Soares, P. M. M.: The diurnal cycle of shallow cumulus clouds over land: A single-column model intercomparison study, *Quarterly Journal of the*
- 15 *Royal Meteorological Society*, 130, 3339–3364, <https://doi.org/10.1256/qj.03.122>, <http://dx.doi.org/10.1256/qj.03.122>, 2004.
- Ling, T., Xu, M., Liang, X.-Z., Wang, J. X. L., and Noh, Y.: A multilevel ocean mixed layer model resolving the diurnal cycle: Development and validation, *Journal of Advances in Modeling Earth Systems*, 7, 1680–1692, <https://doi.org/10.1002/2015MS000476>, <http://dx.doi.org/10.1002/2015MS000476>, 2015.
- Lohmann, U., McFarlane, N., Levkov, L., Abdella, K., and Albers, F.: Comparing Different Cloud Schemes of a Single Column Model by Using Mesoscale Forcing and Nudging Technique, *Journal of Climate*, 12, 438–461, [https://doi.org/10.1175/1520-0442\(1999\)012<0438:CDCSOA>2.0.CO;2](https://doi.org/10.1175/1520-0442(1999)012<0438:CDCSOA>2.0.CO;2), [https://doi.org/10.1175/1520-0442\(1999\)012<0438:CDCSOA>2.0.CO;2](https://doi.org/10.1175/1520-0442(1999)012<0438:CDCSOA>2.0.CO;2), 1999.
- 20 Lübbecke, J. F., Böning, C. W., Keenlyside, N. S., and Xie, S.-P.: On the connection between Benguela and equatorial Atlantic Niños and the role of the South Atlantic Anticyclone, *Journal of Geophysical Research: Oceans*, 115, 2010.
- Madec, G.: NEMO ocean engine. Note du Pole de modélisation, Version 3.6 27 ISSN No 1288-1619, Institut Pierre-Simon Laplace (IPSL),
- 25 France, 2016.
- NASA Goddard Space Flight Center, Ocean Ecology Laboratory, O. B. P. G.: Sea-viewing Wide Field-of-view Sensor (SeaWiFS) Ocean Color Data, NASA OB.DAAC, Greenbelt, MD, USA, 2014.
- Niiler, P. and Kraus, E. B.: One-dimensional models of the upper ocean, in: *Modelling and Prediction of the Upper Layers of the Ocean*, edited by Kraus, E. B., pp. 143–172, Pergamon, Tarrytown, N.Y., 1977.
- 30 Pithan, F., Ackerman, A., Angevine, W. M., Hartung, K., Ickes, L., Kelley, M., Medeiros, B., Sandu, I., Steeneveld, G.-J., Sterk, H. A. M., Svensson, G., Vaillancourt, P. A., and Zadra, A.: Select strengths and biases of models in representing the Arctic winter boundary layer over sea ice: the Larcform 1 single column model intercomparison, *Journal of Advances in Modeling Earth Systems*, 8, 1345–1357, <https://doi.org/10.1002/2016MS000630>, <http://dx.doi.org/10.1002/2016MS000630>, 2016.
- Price, J. F., Weller, R. A., and Pinkel, R.: Diurnal cycling: Observations and models of the upper ocean response to diurnal heating, cooling, and wind mixing, *Journal of Geophysical Research: Oceans*, 91, 8411–8427, <https://doi.org/10.1029/JC091iC07p08411>, <http://dx.doi.org/10.1029/JC091iC07p08411>, 1986.
- 35

- Randall, D. A. and Cripe, D. G.: Alternative methods for specification of observed forcing in single-column models and cloud system models, *Journal of Geophysical Research: Atmospheres*, 104, 24 527–24 545, <https://doi.org/10.1029/1999JD900765>, <http://dx.doi.org/10.1029/1999JD900765>, 1999.
- Randall, D. A., Xu, K.-m., Somerville, R. J. C., and Iacobellis, S.: Single-Column Models and Cloud Ensemble Models as Links between Observations and Climate Models, *Journal of Climate*, 9, 1683–1697, [https://doi.org/10.1175/1520-0442\(1996\)009<1683:SCMACE>2.0.CO;2](https://doi.org/10.1175/1520-0442(1996)009<1683:SCMACE>2.0.CO;2), [http://dx.doi.org/10.1175/1520-0442\(1996\)009<1683:SCMACE>2.0.CO;2](http://dx.doi.org/10.1175/1520-0442(1996)009<1683:SCMACE>2.0.CO;2), 1996.
- Reffray, G., Bourdalle-Badie, R., and Calone, C.: Modelling turbulent vertical mixing sensitivity using a 1-D version of NEMO, *Geoscientific Model Development*, 8, 69–86, <https://doi.org/10.5194/gmd-8-69-2015>, <http://www.geosci-model-dev.net/8/69/2015/>, 2015.
- Rousset, C., Vancoppenolle, M., Madec, G., Fichefet, T., Flavoni, S., Barthélemy, A., Benshila, R., Chanut, J., Levy, C., Masson, S., and Vivier, F.: The Louvain-La-Neuve sea ice model LIM3.6: global and regional capabilities, *Geoscientific Model Development*, 8, 2991–3005, <https://doi.org/10.5194/gmd-8-2991-2015>, <https://www.geosci-model-dev.net/8/2991/2015/>, 2015.
- Savre, J., Ekman, A. M. L., and Svensson, G.: Technical note: Introduction to MIMICA, a large-eddy simulation solver for cloudy planetary boundary layers, *Journal of Advances in Modeling Earth Systems*, 6, 630–649, <https://doi.org/10.1002/2013MS000292>, <https://agupubs.onlinelibrary.wiley.com/doi/abs/10.1002/2013MS000292>, 2014.
- Servain, J., Busalacchi, A. J., McPhaden, M. J., Moura, A. D., Reverdin, G., Vianna, M., and Zebiak, S. E.: A pilot research moored array in the tropical Atlantic (PIRATA), *Bulletin of the American Meteorological Society*, 79, 2019–2031, 1998.
- Sigg, R. and Svensson, G.: Three-dimensional simulation of the ASTEX Lagrangian 1 field experiment with a regional numerical weather prediction model, *Quarterly Journal of the Royal Meteorological Society*, 130, 707–724, <https://doi.org/10.1256/qj.02.209>, <http://dx.doi.org/10.1256/qj.02.209>, 2004.
- Sotiropoulou, G., Tjernström, M., Savre, J., Ekman, A. M. L., Hartung, K., and Sedlar, J.: Large Eddy Simulation of warm-air advection and air-mass transformation in the summer Arctic, *Quart. J. Roy. Meteor. Soc.* Accepted Author Manuscript, 2018.
- Spengler, T., Renfrew, I. A., Terpstra, A., Tjernström, M., Screen, J., Brooks, I. M., Carleton, A., Chechin, D., Chen, L., Doyle, J., Esau, I., Hezel, P. J., Jung, T., Kohyama, T., Lüpkes, C., McCusker, K. E., Nygård, T., Sergeev, D., Shupe, M. D., Sodemann, H., and Vihma, T.: High-Latitude Dynamics of Atmosphere–Ice–Ocean Interactions, *Bulletin of the American Meteorological Society*, 97, ES179–ES182, <https://doi.org/10.1175/BAMS-D-15-00302.1>, <http://dx.doi.org/10.1175/BAMS-D-15-00302.1>, 2016.
- Sterk, H. A. M., Steeneveld, G. J., and Holtslag, A. A. M.: The role of snow-surface coupling, radiation, and turbulent mixing in modeling a stable boundary layer over Arctic sea ice, *Journal of Geophysical Research: Atmospheres*, 118, 1199–1217, <https://doi.org/10.1002/jgrd.50158>, <http://dx.doi.org/10.1002/jgrd.50158>, 2013.
- Svensson, G., Holtslag, A. A. M., Kumar, V., Mauritsen, T., Steeneveld, G. J., Angevine, W. M., Bazile, E., Beljaars, A., de Bruijn, E. I. F., Cheng, A., Conangla, L., Cuxart, J., Ek, M., Falk, M. J., Freedman, F., Kitagawa, H., Larson, V. E., Lock, A., Mailhot, J., Masson, V., Park, S., Pleim, J., Söderberg, S., Weng, W., and Zampieri, M.: Evaluation of the Diurnal Cycle in the Atmospheric Boundary Layer Over Land as Represented by a Variety of Single-Column Models: The Second GABLS Experiment, *Boundary-Layer Meteorology*, 140, 177–206, <https://doi.org/10.1007/s10546-011-9611-7>, <https://doi.org/10.1007/s10546-011-9611-7>, 2011.
- Tjernström, M., Shupe, M. D., Brooks, I. M., Persson, P. O. G., Prytherch, J., Salisbury, D. J., Sedlar, J., Achtert, P., Brooks, B. J., Johnston, P. E., Sotiropoulou, G., and Wolfe, D.: Warm-air advection, air mass transformation and fog causes rapid ice melt, *Geophysical Research Letters*, 42, 5594–5602, <https://doi.org/10.1002/2015GL064373>, <http://dx.doi.org/10.1002/2015GL064373>, 2015GL064373, 2015.
- Toniazzo, T. and Woolnough, S.: Development of warm SST errors in the southern tropical Atlantic in CMIP5 decadal hindcasts, *Climate dynamics*, 43, 2889–2913, 2014.

- Valcke, S.: OASIS3 User Guide, Tech. rep., CERFACS, Toulouse, France, 2006.
- Voldoire, A., Demissie, T., Deppenmeier, A.-L., Exarchou, E., Frauen, C., Goubanova, K., Keenlyside, N., Koseki, S., Prodhomme, C., Sanchez-Gomez, E., Shen, M.-L., Shonk, J., Toniazzo, T., and Taore, A.-K.: Development of warm SST errors in the southern tropical Atlantic in CMIP5 decadal hindcasts, in preparation, 2018.
- 5 West, A. E., McLaren, A. J., Hewitt, H. T., and Best, M. J.: The location of the thermodynamic atmosphere–ice interface in fully coupled models – a case study using JULES and CICE, *Geoscientific Model Development*, 9, 1125–1141, <https://doi.org/10.5194/gmd-9-1125-2016>, <http://www.geosci-model-dev.net/9/1125/2016/>, 2016.
- Williams, P. D.: Climatic impacts of stochastic fluctuations in air–sea fluxes, *Geophysical Research Letters*, 39, n/a–n/a, <https://doi.org/10.1029/2012GL051813>, <http://dx.doi.org/10.1029/2012GL051813>, 110705, 2012.
- 10 Xie, S.-P. and Carton, J. A.: Tropical Atlantic Variability: Patterns, Mechanisms, and Impacts, in: *Earth’s Climate*, pp. 121–142, American Geophysical Union, <https://doi.org/10.1029/147GM07>, 2004.



Figure 1. Flow-Simplified flow chart of the OIFS model. Routines dedicated to coupling via OASIS are coloured red.

NEMO, NEMOGCM



Figure 2. Simplified flow chart of the NEMO model. Routines dedicated to coupling via OASIS are coloured red.




Figure 3. Flow-Simplified flow chart of the LIM model, part of the NEMO model if (nn_ice=3:LIM) in sbeice_lim (stp_cld) sea-ice is present. Routines dedicated to coupling via OASIS are coloured red.




Figure 4. Schematic of coupling variables exchanged between the model components. In the polar environment all red lines represent the coupling (dashed and full) and without sea-ice coupling reduces to the dashed line. From the atmosphere the horizontal wind stress $\tau_{u,v}$, the solar flux Q_s , the non-solar fluxes Q_{ns} and precipitation minus evaporation $P - E$ are passed to the ocean. In the presence of ice, the temperature sensitivity of the non-solar fluxes $dQ_{ns}dT$ is coupled as well. The ocean model sends the sea-surface temperature SST and in the presence of sea-ice the aggregated sea-ice concentration SIC, sea-ice thickness SIT, surface temperature T_s , surface albedo α and the snow thickness h_s . In a coupled simulation with sea-ice the ocean also receives the ice parameters SIC, SIT, T_s and α and in addition the rate of change of the sea-ice thickness S_t .




Figure 5. How Guideline on how to set up an SCM experiment. Each row represents a setup decision necessary (grey phrase on the far left) and potential approaches. IC is short for initial conditions.

Coupled-model biases of AOSCM-6h relative to ERA-Interim and PAPA-buoy measurements for July 11-15 2014. Note that the colour contours match different values for atmosphere and ocean. White areas indicate missing buoy data. Measured temperature and salinity evolution is smoothed with a 12-h running mean to remove tidal influences not included in the model. The liquid water content, i.e. the cloud, in the model (reanalysis) is given in panel (a) ((b)) in black contours showing 0.1, 0.2 and 0.3 g kg⁻¹.

Model evolution at the PAPA-buoy during Jul 11-15 2014 for AOSCM-6h, ASCM-6h and AOSCM-3h. Radiative fluxes are smoothed in time with a running-mean timescale of one hour. Measurements from PAPA-buoy in grey. All fluxes are defined positive downward.

Table 1. ~~Surface RMSE after 28 days evaluated~~ Model settings at the three test locations with respect to PAPA mooring measurements ~~a~~ selection of model parameters. ~~Suffix -Here, Δt is the time step and #lev_a the number of simulation-based-on-atmospheric forcing frequency~~model levels. ~~Extra nudging information in parenthesis~~ Simulations are either coupled (AOSCM), atmosphere-only (ASCM) or ocean-only (OSCM). Standard forcing includes horizontal advective tendencies, vertical velocity and geostrophic wind.

Experiment location	Experiment type	Δt [s]	#lev _a	Forcing	Sensitivity experiments
PAPA	AOSCM	900	60	6h ERA-Interim	(i) ASCM, (ii) 3h ERA-Interim, (iii) nudging of uv with $\tau_a = 1$ h nudging above 3km, (iv) uvTq with $\tau_a = 6$ h
PIRATA	AOSCM	900	60	3h ERA-Interim	(i-ii) initialised 12th and 15th of June instead of 1st, (iii) nudging above 1km, uvTq with $\tau_a = 6$ h, (iv) OSCM
Arctic	ASCM	450	137	6h idealized (ERA-Interim and observations)	(i) AOSCM, (ii-iii) $\Delta t \in \{900, 2700\}$ s, (iv-v) no T and q advection

Table 2. Surface RMSE after 28 days evaluated with respect to PAPA mooring measurements. Statistics calculated over 16 realizations of the five main experiments at the PAPA location. Table 1 describes experiments.

	AOSCM-6h	ASCM-6h	AOSCM-3h	AOSCM-6h (uvrel, $\tau = 1$h) AOSCM-Nuv0km1h	AOSCM-6h (uvTqrel, $\tau = 6$h) AOSCM-Nuv0km1h
T_{2m} [°C]	0.9 ± 0.2	0.8 ± 0.2	0.8 ± 0.2	0.9 ± 0.2	0.8 ± 0.2
SST [°C]	0.6 ± 0.3	0.4 ± 0.1	0.4 ± 0.3	0.4 ± 0.3	0.4 ± 0.2
SW rad [Wm^{-2}]	84 ± 27	82 ± 37	77 ± 34	78 ± 35	77 ± 34
LW rad [Wm^{-2}]	24 ± 5	24 ± 5	23 ± 5	23 ± 5	24 ± 4
SH flux [Wm^{-2}]	13 ± 7	13 ± 8	11 ± 5	12 ± 6	12 ± 7
LH flux [Wm^{-2}]	26 ± 13	28 ± 13	22 ± 10	24 ± 10	27 ± 13
u_{10m} [ms^{-1}]	2.0 ± 0.8	2.1 ± 0.8	1.5 ± 0.3	1.3 ± 0.3	1.9 ± 0.7




Figure 6. Coupled model biases of AOSCM-6h relative to ERA-Interim in the atmosphere (a and b) and PAPA buoy measurements in the ocean (c and d) for July 11-15 2014. Note that the colour contours match different values for atmosphere and ocean. White areas indicate missing buoy data. Measured temperature and salinity evolution is smoothed with a 12 h running mean to remove tidal influences which are not explicitly modelled by the AOSCM. The liquid water content, i.e. the cloud, in the model (reanalysis) is given in panel (a) ((b)) in black contours showing 0.1, 0.2 and 0.3 g kg^{-1} . The boundary layer height (BLH) and the turbocline depth are calculated by the AOSCM.

Table 3. Atmospheric As Table 2 but for RMSE after 28 days of atmospheric profiles evaluated with respect to ERA-Interim fields.

	AOSCM-6h	ASCM-6h	AOSCM-3h	AOSCM-6h (uvrel, $\tau=1\text{h}$)	AOSCM-Nuv0km1h	AOSCM-6h (uvTqrel, $\tau=6\text{h}$)
T [$^{\circ}\text{C}$], to 1km	1.7 ± 0.7	1.6 ± 0.6	1.3 ± 0.7	1.6 ± 0.5		1.3 ± 0.4
T [$^{\circ}\text{C}$], to 3km	2.5 ± 1.4	2.5 ± 1.4	1.6 ± 0.7	2.4 ± 1.3		1.3 ± 0.2
q [g kg^{-1}], to 1km	7 ± 3	7 ± 2	5 ± 3	7 ± 3		6 ± 2
q [g kg^{-1}], to 3km	9 ± 4	10 ± 5	6 ± 3	9 ± 4		7 ± 2
wind [ms^{-1}], to 1km	3.2 ± 1.4	3.2 ± 1.4	1.8 ± 0.5	0.5 ± 0.2		2.7 ± 1.2
wind [ms^{-1}], to 3km	5.3 ± 1.7	5.3 ± 1.7	2.7 ± 0.9	0.5 ± 0.2		2.6 ± 1.0




Figure 7. Model evolution at the PAPA buoy during Jul 11-15 2014 for AOSCM-6h, ASCM-6h and AOSCM-3h. Radiative fluxes are smoothed in time with a running-mean timescale of one hour. Measurements from PAPA buoy in grey. All fluxes are defined positive downward.




Figure 8. Accumulated fluxes, total surface energy and precipitation calculated over 29-day simulations at the PAPA mooring, compared for three main sensitivity runs AOSCM-6h, ASCM-6h and AOSCM-3h across all sixteen simulations. Symbols with a light (dark) border represent results from warm (cold) months. Modelled precipitation is filtered with the measurement hourly rain threshold of 0.2 mm h^{-1}




Figure 9. Atmospheric [temperature](#) root-mean square error integrated in lower 1.5 km of the atmosphere compared to ERA-Interim and SST biases relative to PIRATA measurements for several coupled and one ocean-only simulation. ~~Fxx show results from simulations forced with advective tendencies and initialized~~ [More details](#) on day $xx \in \{01, 12, 15\}$ of June 2014. N1km6h uses the same forcing as F01 but additionally nudging is added to horizontal wind, temperature and moisture above 1 km with $\tau = 6$ h [presented experiments can be found in Table 1](#). OSM is an ocean-only simulation.




Figure 10. Time-height evolution of the simulated cloud liquid water content (g kg^{-1}) in the Arctic setup for hours 12 to 48 with a color scale that maximize at about $0.8 (\text{g kg}^{-1})$ for a) LES results from Sotiropoulou et al. (2018), b) ASCM simulation with a time step of 450 s and 132-137 layers, c) AOSCM with time step 450 s in all components and coupling, d) AOSCM with conditions similar to EC-Earth i.e. 2700 s for all time steps and coupling, e) as in d) but with 900 s time step for the atmospheric component, and f) as in e) but with no temperature advection. Observational estimates of cloud base (red dots) and top (black dots) from ACSE are also included in a).




Figure 11. Liquid-water path in (g m^{-2}) for all Arctic simulations presented in Fig. 10, LES - red line, ASCM blue dashed line, AOSCM with various time steps - blue (all 450 s), magenta (all 2700 s) and cyan (IFS 900 s, other 2700 s). Also included are the results from simulations without advection of temperature (dashed cyan line) and without humidity (dash-dotted cyan thin line). Observations are shown as running averages over approximately 10 min (black dots).




Figure 12. Mean albedo (%) change over the simulated 40 hours plotted against the mean albedo for the first simulated hour for the experiments in Fig. 10, same colors as in Fig. 11, ASCM open blue symbol, AOSCM simulations with no advection of temperature (cyan star) and no humidity advection (cyan diamond) are also included.




Figure 13. Average radiative energy as function of average energy received at the surface for hour 12 to 48 for the simulations (same symbols as in Fig. 12) and observations (black dot). The thin dotted lines around the 1-to-1 line represents ± 10 and ± 20 W m⁻².