

Reply to

Anonymous Referee

*Russo, E., Kirchner, I., Pfahl, S., Schaap, M., and Cubasch, U.:
Sensitivity studies with the Regional Climate Model COSMO-CLM 5.0
over the CORDEX Central Asia Domain, Geosci. Model Dev.
Discuss., <https://doi.org/10.5194/gmd-2019-22>.*

Dear reviewer,

Thank you again for your effort in reviewing our paper.

Below we go point by point through your technical corrections, presented in *italic*, detailing how we dealt with your concerns reported in **bold**.

Thank you.

General Comments

- *I found that the authors have addressed the comments I made in my previous review. I acknowledge the big effort made, especially in order to clarify the origin of the large biases, with even additional simulations. However I cannot recommend yet the publication, being still some issues that need to be addressed. The most serious shortcoming is that the manuscript is messy and mixed up. There are many trivial errors revealing that the manuscript has not double checked carefully. The authors should check the manuscript before submission, in order not to worsen the work of the reviewer. More specifically, the figure numbering seems to be wrong when they are referenced. At page 7, line 32 you mention Fig.2, but Fig.2 shows the maps of the spread and not the subdomains. And so on... for almost all the cross-references. At page 11, line 13 you mention Fig.8 about SS analysis for subregions, but this figure seems missing so I cannot analyze the results described in Sec. 3.1.2.*

Following the referee comment, we realized that we mixed up the numbering of the figures in the text of the previous version of the manuscript. We will correct all the figures numbering in the new version of the manuscript. Concerning Fig. 8 of the previous manuscript version, we were actually referring to fig. 9, that will now correctly referenced in section 3.1.2. Additionally, we reviewed the text more thoroughly, as suggested by the referee, correcting all the possible errors that we encountered.

Other Comments

- *Pag 5, Lines 12: latitudes ?*

Corrected.

- *Pag 7, Lines 2-3: The authors decided not to address my previous comment about CDO, but I insist that this information is not relevant... otherwise you should mention also the software you have used for plotting the figures, for making calculations... However I leave the Editor the final decision about this comment.*

We finally agree with the referee and decided to exclude the citation to CDO from the final version of the manuscript.

- *Pag 10, line 6: observations ?*

Corrected.

- *Pag.11, lines 7-9 : Additionally, the ranges... for the area. You claim that the range of improvements are similar, but sincerely the values reported in Table 4 seem to me quite different, keeping in mind that in a sensitivity context even a difference of +1 is a large value. More specifically 7.5 is different from 4.9, 11.1 is rather different from 7.4.*

We agree with the referee on the fact that some differences in the magnitude of the changes in SS are present. Nevertheless, this does not exclude the fact that the behavior of the model in the two cases is quite similar. This confirms the fact that in the two different cases the model will produce an important improvement. Following the referee comment, we tried now to be more careful in the final version of the manuscript, saying that the results are similar in the two cases, even though some changes are present.

- *Sec. 3.1.4: probably in this case the cross reference of Fig. 8 is correct, but the figure and the text are not clear. What do these maps represent? You claim that SNOW configuration leads to warmer conditions, but I see a wide blue area on the right... probably I do not understand well the meaning of the figures.*

The previous figure 8 of the former manuscript version was actually misleading. This figure represented the bias of winter temperature between the reference simulations *a* and the SOIL and SNOW simulations. We now propose a new figure

where the bias is calculated as SOIL (SNOW)-REF and where it is possible to see now that the SNOW simulation produces even warmer winter temperatures over Western Siberia. We have modified the figure caption accordingly. Additionally, realizing that the description of the figure in sec. 3.1.4, we tried to improve it in the new version of the manuscript.

- *Pag 12, line 30: WSH? Probably it is WSC*

Corrected.

- *Pag 12, line 31: The largest underestimation... CSA. I guess that this analysis is related to Fig.10, but I do not understand the meaning of this figure. Probably the quality of the colors is low.*

Fig. 10 of the former manuscript version shows the variance ratio calculated between the different experiments and the observations. We actually think that the figure was already pretty well described in the text and in the figure caption. Concerning the colorbar we think that the choice we have made was an optimal compromise to show the different changes in variance ratio among the different variables and regions characterized by completely different climate conditions. We think that the used colorbar allows to perfectly see the fact that different experiments do not really perform significantly different in terms of simulated variance; it also allows to easily distinguish for which variables and regions the model has good or bad performances in the simulation of variability. For the given reasons, also considering the fact that we did not receive any other comment about the figure from the 2nd reviewer, we think that the selected colorbar should not be changed. Nonetheless, acknowledging the referee comment, we revised the text and the figure caption to make its description a bit clearer.

- *Pag. 13, line 28: conclusion?*

Corrected.

- *Pag 14, line 5: initiative ?*

Corrected.

- *Pag 14, lines 20-23: Following these... snow model. You say that no significant changes are evident. If so, what is the relationship with what you have written before (lines 11-20)?*

Following the reviewer comment, we reformulated the previous period emphasizing the fact that the results of these two additional simulations do not allow to improve model results. Considering also the model pretty low sensitivity in winter to the different changes in configuration, we can affirm that the model has some structural error that does not allow to properly simulate winter temperatures over Western Siberia and that new parameterizations for the simulation of processes related to snow cover and permafrost are required in COSMO-CLM.

- *Pag 14, line 24: I am not sure, but I guess that GUO can be written as Guo.*

Corrected.

- *Figure 1 (caption). You claim that these are rotated coordinates, but they seem to me geographical coordinates.*

Corrected.

- *Table 2: Why is there a question mark next to Tegen?*

Following the referee comment we realized that we forgot to reference the TEGEN aerosol data set in Table 2 of the previous manuscript version. We will include the proper reference in the new manuscript.

Sensitivity studies with the Regional Climate Model COSMO-CLM 5.0 over the CORDEX Central Asia Domain

Emmanuele Russo^{1,2,3}, Ingo Kirchner¹, Stephan Pfahl¹, Martijn Schaap^{4,1}, and Ulrich Cubasch¹

¹Institute for Meteorology, Freie Universität Berlin, Carl-Heinrich-Becker-Weg 6-10, 12165, Berlin, Germany

²Climate and Environmental Physics, Physics Institute, University of Bern, Sidlerstrasse 5, 3012, Bern, Switzerland

³Oeschger Centre for Climate Change Research, University of Bern, Hochschulstrasse 4, 3012, Bern, Switzerland

⁴TNO Built Environment and Geosciences, Department of Air Quality and Climate, Princetonlaan 6, 3584, CB, Utrecht, The Netherlands

Correspondence: emmanuele.russo@met.fu-berlin.de

Abstract. Due to its extension, geography and the presence of several under-developed or developing economies, the Central Asia domain of the Coordinated Regional climate Downscaling Experiment (CORDEX) is one of the most vulnerable regions on Earth to the effects of climate changes. Reliable information on potential future changes with high spatial resolution acquire significant importance for the development of effective adaptation and mitigation strategies for the region. In this context, Regional Climate Models (RCMs) play a fundamental role.

In this paper, the results of a set of sensitivity experiments with the regional climate model COSMO-CLM version 5.0, for the Central Asia CORDEX domain, are presented. Starting from a reference model setup, general model performance is evaluated for present-days, testing the effects of ~~a set of singular physical parameterizations~~ singular changes in the model physical configuration and their mutual interaction on the simulation of monthly and seasonal values of three variables that are important for impact studies: 2-meter near surface temperature, precipitation and diurnal temperature range. The final goal of this study is two-fold: having a general overview of model performance and its uncertainties for the considered region and determining at the same time an optimal model configuration.

Results show that the model presents remarkable deficiencies over different areas of the domain. The combined change of the albedo taking into consideration the ratio of forest fractions and the soil conductivity taking into account the ratio of liquid water and ice in the soil, allows to achieve the best improvements in model ~~performance~~ performances in terms of climatological means. Importantly, the model seems to be particularly sensitive to those parameterizations that deal with soil and surface features, and that could positively affect the repartition of incoming radiation. The analyses also show that improvements in model ~~performance~~ performances are not achievable for all domain sub-regions and variables, and they are the result of some compensation effect in the different cases. The proposed better performing configuration in terms of mean climate, leads to similar positive improvements when considering different observational datasets and boundary data employed to force the simulations. On the other hand, due to the large uncertainties in the variability estimates from observations, the use of different boundaries and the model internal variability, it has not been possible to rank the different simulations according to their representation of the monthly variability.

This work is the first ever sensitivity study of an RCM for the CORDEX Central Asia domain and its results are of fundamental importance for further model development and for future climate projections over the area.

Copyright statement.

1 Introduction

5 Regional Climate Models (RCMs) are a fundamental tool for the study of climate change, allowing to reproduce the climate system with a high quality of details and to provide information at a regional scale. Their use for future climate projections, constitutes indeed a vital resource for policy makers in their decision making under the threat of future global warming (Kim et al., 2014).

10 The Coordinated Regional climate Downscaling Experiment (CORDEX) (Giorgi et al., 2009) is an initiative sponsored by the World Climate Research Programme, aiming to coordinate international regional climate downscaling experiments. CORDEX sets a number of directives, including predefined resolution, regions, output variables and formats, to facilitate analysis of possible future climate changes (Nikulin et al., 2012).

15 Among the different CORDEX regions, Central Asia represents one of the largest domains, covering parts of Europe, Africa and almost the entire Asian continent. The domain extends from eastern Europe to the eastern part of China and from the northern part of India and the Arabian Peninsula in the South, to Siberia and the Arctic ocean (Barents sea and Kara sea) in the North. It includes, almost entirely, two of the most important and populated countries of the World: China and Russia. The region, despite being mainly characterized by arid and semi-arid climatic conditions, presents a wide and differing variety of climatic zones, going from the desertic zones of Gobi and the Arabian peninsula, to the cold and dry areas of Siberia and the wet Northern Indian monsoon [area-region](#) (Ozturk et al., 2017). Therefore, it offers the unique opportunity to test the model
20 sensitivity to different climatic conditions at once.

Beside its importance from a modeling perspective, the extension, geography and the presence of several under-developed or developing economies, makes the CORDEX Central Asia domain one of the most vulnerable regions on Earth to the effects of climate changes. Even small changes in climate conditions could dramatically affect ecosystems, agricultural crops, water resources, human health and livelihood of the region (Siegfried et al., 2012; Lioubimtseva et al., 2005; Lioubimtseva and
25 Henebry, 2009; Liu et al., 2013; Yong-Jian et al., 2013; Zhen-Feng et al., 2013; Wang et al., 2017; Chuluunkhuyag, 2008; Diniega, 2012; Macias-Fauria et al., 2012). In this context, reliable information on potential future changes with high spatial resolution acquire significant importance for the development of effective adaptation and mitigation strategies.

The recognized prerequisite that every climate model has to satisfy, in order to provide reliable future climate projections, is the ability of realistically simulating present-day climate (Kim et al., 2014; Nature-Editorial-Board, 2010; Kim and Lee, 2003).
30 Assessing the ability of a climate model to simulate the current climate is defined as model evaluation (Airey and Hulme, 1995). Model evaluation consists in an assessment of model quality and deficiencies originating from different modeling assumptions,

conducted through the comparison of model outputs and observations (Kim et al., 2014; Kim and Lee, 2003; Flato et al., 2013; Lenderink, 2010; Overpeck et al., 2011; Bellprat et al., 2012a, b). Evaluation experiments normally consist in a set of present-days simulations conducted in a perfect boundary setting, i.e., using reanalysis products as lateral boundary forcings. This "modus operandi" allows for the separation of possible model biases from biases due to erroneous large-scale forcings, thus highlighting specific model deficiencies (Kotlarski et al., 2014). These may be related to the model formulation and to choices in model configuration (Awan et al., 2011; Bellprat et al., 2012a, b; de Elía et al., 2008; Evans et al., 2012). In the second case, it should be possible to improve model performances by testing different model configuration setups and choosing the one that better agrees with observations. This approach might be conceived as an optimization step. Nevertheless, it is important to emphasize the fact that a specific model configuration could produce better results, by simply compensating for some deficiencies in the model formulation (Hourdin et al., 2017).

In climate models, the complexity and small spatial scales of the physical processes involved, requires the so-called parameterization of many of these processes: this basically consists in summarizing physical phenomena and their interaction across different spatial and temporal scales (Fernández et al., 2007; Rummukainen, 2010; McFarlane, 2011; Hourdin et al., 2017), which is associated with substantial uncertainties. The same processes may be described through different parameterizations, with a different degree of complexity and infinitive parameter values. Consequently, the outcomes of a climate model might largely differ, depending on the parameterizations used and the selected parameters inputs. Additionally, the use of different forcings datasets, for example for greenhouse gases, aerosols or land cover changes, might have a significant effect on the results. Further, other details that need to be considered when configuring a climate model simulation for a defined domain are the configuration and spatial resolution of the model grid (both horizontally and vertically) and the coupling with different models representative of other components of the climate system. For regional climate models, all these aspects are domain dependent (Jacob et al., 2007, 2012; Rockel et al., 2008). This means that a regional climate modeler should always evaluate different model configurations, isolating the one that leads to a better agreement with observations, for each investigated region and employed model. In doing so, several sources of uncertainties should be taken into consideration: the fact that performances of the RCM for a specific region might vary according to the boundary conditions, the model internal variability and observational datasets should be acknowledged when evaluating model performances.

RCMs evaluation and configuration have been the subject of a large number of studies, for different regions, such as in Kotlarski et al. (2014); Umakanth and Kesarkar (2018); Borge et al. (2008); García-Díez et al. (2013); Crétat et al. (2012); Rajeevan et al. (2010); Diro et al. (2012); Giorgi et al. (2012); Reboita et al. (2014); Li et al. (2018); Huang et al. (2015). For COSMO-CLM, Europe has received larger attention. Bellprat et al. (2012b) applied a quadratic metamodel on a subsample of model parameters in order to objectively tune the model for the region. Their method is considered the reference for COSMO-CLM for determining optimal parameters values and has been further developed and applied to the Mediterranean region by Avgoustoglou et al. (2017) and for higher resolution for the Alpine region by Voudouri et al. (2018). Bellprat et al. (2016) additionally used the same method for the European and the North American domain, finding quite similar values of optimal model parameters for the two regions. Using a more subjective approach, Montesarchio et al. (2012) conducted a set of sensitivity studies in order to determine the best model setup for the simulation of near surface temperature and precipitation

over Northern and Central Italy, at a spatial resolution of ~ 8 km. Despite several important findings, they were not able to determine an optimal model configuration with respect to these variables. The alpine region was the subject of a study with COSMO-CLM by Suklitsch et al. (2008), where they found that changes in model resolution has a larger impact on model simulation than modifying dynamical and numerical schemes. Bachner et al. (2008) conducted a similar work for Germany, focusing on model ~~performance~~ performances for summer precipitation, concluding that the model uncertainty due to the modified physical parameterizations is considerable and highlighting the need of conducting evaluation and sensitivity studies prior to the application of a model for climate change projections. Studies investigating COSMO-CLM sensitivity for regions out of Europe, are more rare. Lange et al. (2015) tested model performances to different convection and non-precipitating subgrid-scale clouds parameterizations for South America. Through this work they managed to reduce long-standing model biases in precipitation for the region, by using the IFS-Integrated Forecasting System (IFS, ?) of the European Centre for Medium-Range Weather Forecasts (ECMWF) convection scheme and statistical schemes for ~~convection and~~ subgrid-scale clouds. Buchhignani et al. (2016) investigated compared the performances of twenty-six different model configurations for the Middle East-North Africa (MENA) CORDEX domain, ~~comparing 26 different model configurations. The model seems to be.~~ They found that the model is particularly sensitive for the region to changes in physical and tuning parameters. In particular, they ~~found an optimal configuration with a~~ obtained best model performances with the representation of the albedo based on the Moderate Resolution Imaging Spectroradiometer (MODIS, ?) data, and a parameterization of aerosol based on the NASA-GISS Aerosol Optical Depth distributions ~~-(Tegen et al., 1997). Finally,~~ Buchhignani et al. (2012) evaluated several configurations for North-Western China at a spatial resolution of approximately ~ 8 km, even though they did not propose any optimal configuration for the region.

So far, neither an evaluation nor a sensitivity study on the impact of ~~the use of different physical parametrizations~~ different configurations of an RCM have been documented for the CORDEX Central Asia domain. Such analyses are required to guide further model development and applications for the region: if we want to produce future climate projections for the ~~Central Asia domain of the CORDEX experiment region,~~ we need to investigate model performances and deficiencies for the area and propose optimal model configurations.

In the light of the upcoming phase of the ~~Coordinated Regional climate Downscaling EXperiment (CORDEX) (Giorgi et al., 2009) CORDEX initiative,~~ denominated CORDEX - Coordinated Output for Regional Evaluations (CORE) ~~(Gutowski Jr et al., 2016), Gutowski Jr et al. (20~~ in this paper the results of a set of sensitivity experiments with the regional climate model COSMO-CLM version 5.0 (Rockel et al., 2008), for the Central Asia CORDEX domain, are presented. In this perspective, this work represents the first step for the production of climate projections for the Central Asia domain using COSMO-CLM, evaluating general model performances, isolating the effects of different uncertainty sources on model results and determining an optimal model configuration for a region for which almost no reference exists. Starting from a reference model setup, general model ~~performance is~~ performances are evaluated, testing the effects of a set of singular physical ~~parameterizations~~ options and their mutual interaction as well as two different forcing datasets on the simulation of monthly and seasonal values of three variables that are important for impact studies. These are near surface temperature (T2M), precipitation (PRE) and diurnal temperature range (DTR), the latter representing the daily excursion between maximum and minimum temperature, which is particularly important in terms of

human body adaptability and stress. The final goal of this study is two-fold: having a general overview of model ~~performance~~ performances and its uncertainties for the considered region and determining at the same time a "best" suitable model configuration.

In section 2 of this paper, the model, the different datasets and the methods employed in this study are ~~presented~~ described.

5 Then, in section 3, results are presented. Finally, conclusions are outlined, with a general discussion of model performances and the proposal of a final optimal model configuration for the area of study.

2 Methods

In this section the research methods are described, including details on the model and the different simulation setups, the observational datasets used for the evaluation of model results and the employed metrics.

10 2.1 Model and Experiments Description

The Consortium for Small-Scale Modeling in Climate Mode (COSMO-CLM(~~Roedel et al., 2008~~), Rockel et al. (2008)) is a non-hydrostatic regional climate model developed by the CLM-community, an open international network of scientists. The model version employed in this study is the COSMO-CLM 5.0_clm9. Many studies have been conducted in the recent years over different CORDEX regions, using the COSMO-CLM (Panitz et al., 2014; Dobler and Ahrens, 2010; Buccignani et al.,
15 2016; Smiatek et al., 2016; Jacob et al., 2014; Kotlarski et al., 2014; Zhou et al., 2016).

The simulations presented in this study are performed with a spatial resolution of 0.22° , as specified in the new CORDEX-CORE directives (Gutowski Jr et al., 2016), on a rotated geographical grid. The initial simulation domain extends from $\sim 3^{\circ}$ to $\sim 145^{\circ}$ over longitudes and from $\sim 16^{\circ}$ to $\sim 73^{\circ}$ ~~over latitudes~~ over latitudes. The domain includes a model relaxation zone of ~ 250 km on each domain side, used to "relax" the model variables towards the driving data (Køltzow, 2012; Davies, 1976).

20 Results of the simulation for this area are excluded from the analysis, with the final domain extent shown in Fig. 1. If not differently specified, all the simulations are run over a ~~15~~ fifteen year-long period from 1991 to 2005, with the first ~~5~~ five years excluded from the analysis and considered as spinup time.

In a set of sensitivity experiments labeled from **a** to **q** in the first section of Tab. 1, the effects on model ~~performance-of~~ ~~different physical parameterizations~~ performances of different changes in the model configuration are tested, first individually
25 and then combining them with each others. The setup of experiment **a** is the reference from which the other experiments are configured, by implementing the modifications specified in the table. The model configuration used for the reference simulation is the same used for the CORDEX East Asia domain for the COSMO-CLM model version 5.0. This was considered as a good reference for the purposes of this study, since the two regions share a large part of their domains. A general description of the setup of the reference simulation is provided in Tab. 2.

30 All the performed simulations are driven by the NCEP version 2 reanalysis data (Kanamitsu et al., 2002), provided as boundary and initial conditions. The boundaries have a temporal resolution of 6 hours and a spectral resolution of T62 (~~$\sim 1.89^{\circ}$~~ $\sim 1.89^{\circ}$). NCEP2 data have been selected as boundary data, instead of commonly employed ERAInterim reanalyses (Dee

et al., 2011), since their spatial resolution is closer to the one of the ~~3-three~~ Global Circulation Models (GCMs) that are used for CORDEX-CORE simulations in the CLM community: MPI-ESM (Giorgetta et al., 2013), HadGEM (The HadGEM2 Development Team: Martin et al., 2011) and NorESM (Bentsen et al., 2013; Iversen et al., 2013), with a spatial resolution of, respectively, ~~around 210km, 210x140km and 270x210~~ ~ 210 km, $\sim 210 \times 140$ km and $\sim 270 \times 210$ km. Thus, using NCEP2
5 as drivers allows to reproduce a resolution jump more similar to the one ~~of present when using~~ the considered GCMs.

Acknowledging the fact that ERAInterim ~~reanalysis data, which have a spectral resolution of T255 ($\sim 0.7^\circ$)~~, are normally employed for the evaluation of RCMs, two additional simulations are performed, driven by ERAInterim ~~reanalysis data~~ (second section of Tab. 1), ~~which have a spectral resolution of T255 ($\sim 0.7^\circ$ lon)~~. This allows to estimate the effects of the two different driving data on the simulations results and to support possible conclusions on an optimal setup, verifying how significantly the
10 results differ in the two cases.

In order to better discriminate different sources of uncertainties in the model simulations, a run covering the period 1991-2005 is also performed (third section of Tab. 1), using a ~~different timestep of 120s~~ timestep of 120 s, instead of the one of the reference simulation of ~~150s~~ 150 s.

Two 25-year long simulations, covering the period 1991-2015, are performed for testing different configurations that could
15 help in reducing model biases over areas characterized by the presence of permafrost in winter. The two simulations, labeled **SOIL** and **SNOW** in the ~~bottom part~~ fourth section of Tab. 1, are performed ~~, respectively, increasing~~ increasing in both the number of soil layers from 10 to 13, together with their total depth from approximately 15 m to more than 130 m, and, only for SNOW, additionally using the multi-layer snow model of COSMO-CLM (Machulskaya, 2015). These simulations cover a longer period than the others, since a longer spinup time is necessary in order to account for more and deeper soil layers. Their
20 results, excluded from the direct comparison with the other simulations, are discussed in the results and concluding sections of this paper.

Finally, a set of ~~4~~ four simulations are additionally performed for the investigation of the model internal variability (~~fourth last~~ fourth section of Tab. 1). These simulations have the same setup as the reference simulation **a**, but are initialized at four different dates, shifted by +/- 1 and 3 months with respect to the reference one.

25 All the proposed simulations are designed with the goal of better understanding main model limitations for the area and to which degree they can be reduced by properly configuring the model, isolating the effects of different sources of uncertainties.

2.2 Observations

Gridded observational datasets are used to compare model results against observational data on a similar scale. These gridded datasets are obtained through statistical extrapolations of surface observations. In addition to uncertainties related to the original
30 measurements, these datasets also contain important uncertainties due to the statistical extrapolation procedure (Flaounas et al., 2012; Gómez-Navarro et al., 2012). For climate model evaluation studies, these uncertainties are usually taken into account by using a range of different datasets (Collins et al., 2013; Gómez-Navarro et al., 2012; Bellprat et al., 2012a, b; Flaounas et al., 2012; Lange et al., 2015; Zhou et al., 2016; Solman et al., 2013).

In this study, the issue of observational uncertainties is addressed by considering three different datasets for each of the investigated variables. The datasets include both observations and reanalysis data. For all the three considered variables, information is retrieved from the CRU TS4.1 observational dataset (Harris and Jones, 2017). Information on T2M and PRE is also retrieved from the University of Delaware (UDel) gridded dataset (Willmott, 2000), provided by the NOAA/OAR/ESRL PSD, Boulder, Colorado, USA, from their Web site at <https://www.esrl.noaa.gov/psd/>. For T2M and DTR, in addition, the Modern-Era Retrospective analysis for Research and Applications, version 2 (MERRA2) (Gelaro et al., 2017) is employed. For precipitation, the third considered dataset is the Global Precipitation Climatology Centre dataset (GPCC) (Becker et al., 2011), while the ERAInterim reanalysis dataset (Dee et al., 2011) is used in addition to MERRA2 and to CRU for the evaluation of DTR.

All the datasets are retrieved on a grid with the same spatial resolution of 0.5° . The ERAInterim data, that originally have a horizontal resolution of approximately 80km, are interpolated to the same grid resolution. The output of the simulations is upscaled to the same 0.5° grid of the observations. For temperature and diurnal temperature range, a bilinear remapping method is used for the upscaling, while for precipitation a conservative remapping method is employed. ~~The Climate Data Operators (CDO) software package (available at <http://www.mpimet.mpg.de/cdo,version-1.9.5>) is used for the interpolation.~~

Fig. 2 shows the spread of the different observational datasets for each variable, for yearly, winter and summer climatological means over the period 1996-2005. As evident, large differences emerge among the different datasets, in particular for regions characterized by complex topography and lower observational stations density, such as the Tibetan Plateau and Siberia. The given spread could make it hard to quantify model biases over certain regions. In the case of T2M and DTR, the spread is certainly influenced by the fact that some of the datasets are reanalyses. Nevertheless, for T2M, differences exceeding 8° are present, in particular in winter, even between the CRU and the UDEL, over regions where the interpolation is highly affected by the low number of stations (Matsuura and Wilmott, 2012; Bucchignani et al., 2014). For PRE, the spread in the different observations (expressed in percentage with respect to the GPCC values) is remarkable in winter over the Tibetan Plateau and in summer over particularly dry areas. Despite the differences might likely be influenced by the employed interpolation methods in each case, the spatial coverage of observation is still considered their main driver (Dong and Sun, 2018; Matsuura and Wilmott, 2012; Sun et al., 2018; Naumann et al., 2014).

2.3 Analysis Details and Evaluation Metrics

In order to rank different model configurations according to their skills in simulating the three considered variables over the region, their performances are evaluated with respect to the ones of the reference simulation (a, Tab. 2).

Since in the context of CORDEX simulations the main interest is often on the comparison of the mean climate between two different periods in time, the primary focus of the proposed analyses is on climatological monthly means values of the considered variables: monthly values of daily means of T2M and DTR are considered, while for PRE integrated values are used. In addition, the results are supported by the investigation of the simulated monthly variability.

In the latter case, since the model is not expected to exactly match the observed temporal evolution of the investigated variables point by point (Gleckler et al., 2008; Wilks, 2006), regional mean anomalies are considered. For each grid point

in the domain, monthly anomalies are first calculated by subtracting the climatological mean from each monthly value. The variability is then analyzed based on these anomalies averaged over sub-regions characterized by similar climate conditions.

The decomposition of the domain into a set of sub-regions is obtained by means of a k-means clustering (Steinhaus, 1956; Ball and Hall Dj, 1965; MacQueen et al., 1967; Lloyd, 1982; Jain, 2010) of quantile-normalized (q-normalized) monthly climatologies of the investigated variables. K-means is a clustering technique using the concept of Euclidean distance from the centroids of a pre-determined group of clusters, for separating similar data into groups. For the purposes of this paper, following several tests and the results of other studies (Mannig et al., 2013), a total number of 11 clusters is selected. The k-means clustering algorithm is reiterated over 3000 times in order to achieve the presented results, using q-normalized values of monthly climatologies of ~~2-meter temperature and diurnal temperature range-T2M and DTR~~ T2M and DTR derived from the CRU dataset and ~~precipitation-PRE~~ PRE values derived from the GPCC as input. Fig. 2-3 shows the results of the k-means clustering. The mean climatologies of the considered regions for the three investigated variables are also reported in Tab. 3.

For both the analyses of mean climate and variability, metrics adapted from Gleckler et al. (2008) are used. In the following subsections, we give more details on the employed metrics.

2.3.1 Climatology

For the evaluation of the climatological means, we employ a Skill Score (SS) metrics expressed as:

$$SS = \left(1 - \frac{(MAE)_{exp}}{(MAE)_{ref}}\right) \times 100 \quad (1)$$

where the Mean Absolute Error (MAE) is given by:

$$MAE = \frac{1}{W} \sum_{i=1} \sum_{j=1} \sum_{m=1} w_{ijm} |sim_{ijm} - obs_{ijm}| \quad (2)$$

where *sim* and *obs* are the monthly climatological means of, respectively, the considered simulation and observational dataset. The indices *i*, *j* and *m* vary, respectively, over longitudes, latitudes and months of a year. *W* is the sum of the weights *w_{ijm}*, taking into account the different lengths of the months and the grid boxes effective area. The *SS* is calculated with respect to a reference simulation. Positive values indicate an improvement of the considered simulation *exp* with respect to the reference *ref*, while negative values indicate worse performances. The analyses of MAE for the mean seasonal cycle are conducted for the entire domain and single sub-regions. Additionally, the same metrics are applied for the analysis of single seasons for the entire area.

2.3.2 Variability

The analysis of the model performances in simulating the mean climate is complemented by the investigation of simulated variability.

There is no reason to expect models and observations to agree on the phasing of internal (unforced) variations. Hence metrics such as MAE are not appropriate for characterizing the model ~~performance of~~ performances for interannual variability (Gleckler et al., 2008). Here, for an overall evaluation of the simulated variance in the different cases, the ratio of simulated to observed variance is considered:

$$5 \quad \text{Variance ratio} = \frac{\sigma_{exp}^2}{\sigma_{obs}^2} \quad (3)$$

It is important to mention that correctly matching the observed variance does not guarantee a correct representation of the modes of variability associated with this variance.

For ~~tacking~~ taking into account observational uncertainties, all the proposed analyses are conducted separately for each observational dataset. Changes in model ~~performance due to different configurations will be~~ performances for a given configuration are considered relevant only when consistent among the ~~given~~ different observations.

3 Results

In this section the results of the conducted analyses are presented, starting from the consideration of climatological means and followed by the analyses of simulated-to-observed variability.

15 3.1 Mean Climate

In order to characterize the general performances of the model over the region, for the three considered variables, maps of the yearly, winter and summer mean biases of the reference model simulation **a** with respect to the different observational datasets, are first presented.

Fig. ~~3-4~~ 3-4 shows that for ~~temperature~~ T2M, the largest biases are evident in winter (central panels), with warmer simulated conditions over the northeastern part of the domain, where the bias in some case exceeds ~~15°C~~. ~~This °C~~. ~~These~~ exaggerated biases are mainly relative to the UDEL dataset and, in general, particularly large biases are limited to a few points characterized by complex topography and lower stations density, where the gridded datasets are less reliable. When the CRU dataset is considered, the values of the bias rarely exceed (are below) ~~10°C~~ (-10)°C, for really few points. Beside these points, still some remarkable biases are present but these are well within the ranges of other CORDEX simulations for the area (Wang et al., 2013; Bucchignani et al., 2014; Ozturk et al., 2012). In summer (Fig. ~~34~~ 34, right panels), a positive bias (ranging from ~~+5°C~~ to +10°C) is present over the central and south-western part of the domain, in arid and desertic areas such as the Arabian Peninsula and the Taklamakan desert. Conversely, a cold bias is present over Siberia in this case, with values rarely below ~~-5°C~~. Biases of annual mean values (Fig. ~~34~~ 34, left panels) are smaller than ~~in the seasonal cases~~ the seasonal ones, except for the Tibetan Plateau. Here a similar particularly pronounced cold bias is evident, for all seasons, with respect to all observational datasets, with values sometimes smaller than ~~-10°C~~. In this case the observations are likely less reliable. ~~For all~~

~~seasons~~In general, the simulation results are in better agreement with the MERRA2 dataset than with the CRU and the UDEL. Nevertheless, despite the evinced differences in the magnitude of the model biases against different observational datasets, their spatial patterns are very similar in all the cases.

Concerning ~~precipitation~~PRE (Fig.45), remarkable biases are present in the winter and summer as well as in the annual mean for all the observational datasets. The biases in this case are expressed as percentage with respect to the values of the corresponding observational estimates. In summer (Fig.45, right panels), a particularly pronounced negative bias, with values down to -100%, is visible over arid regions and the monsoon area. This is of the same order of the spread of the observational datasets for the area (Fig. 2). Over the Tibetan Plateau the bias in summer is positive, with values larger than 100%. In winter (Fig.45, central panels), this positive bias becomes even larger (but again in the order of the spread of observations), and extends further over adjacent regions. Over the central part of the domain, a different ~~behaviour~~behavior is evident between winter and summer.~~While:~~ while in winter the model simulates wetter conditions (+20% to +100%), summers are drier (~ -50 %) than in observations. In the annual mean (Fig.45, left panels), the simulated climate is wetter over a large part of the eastern domain (with values exceeding +100%) and drier over desert zones (with rare values smaller than -80%). ~~Over~~In this case, over the central part of the domain, winter and summer biases compensate each other.

In all the cases, the simulated DTRs are smaller than the observed ones over almost the entire domain (Fig.56). A positive bias in DTR, rarely exceeding +5^oC, is evident only over isolated parts of the southern domain, in particular over the southern borders of the Tibetan Plateau. The differences ~~compared with CRU observations~~arising from the comparison against CRU observations are more pronounced than ~~with the ones against~~ reanalysis data, with biases lower than -10^oC in some cases. The pattern of the bias is quite similar for all the three considered datasets, with some larger differences in summer. Over the northernmost part of the domain, characterized by particularly cold conditions (minimum temperature under -30°C in winter, see Tab. 3), a strong negative bias is evident only with respect to the CRU in all seasons. The smaller bias over this area arising from the comparison against reanalysis data is most likely due to the nature of these datasets, which combine model predictions and observations.

The additional simulations performed with the same reference setup but with a different timestep (TIMESTEP, Tab.1) and driven by ERAInterim instead of NCEP2 (a ERAInterim, Tab.1), lead to very similar biases, for all variables (see supplements). This suggests that evinced biases are likely inherent to the model formulation itself.

3.1.1 SS - Seasonal Cycle

In this section, the results of the Skill Score (SS) derived from the MAE calculated over the mean seasonal cycle and all the points of the domain are presented.

Fig.6-7 (upper row) shows that for ~~temperature~~T2M, among the experiments for which single changes are applied to the reference model configuration ~~are applied~~ (left side of the dotted vertical line), the ones with changes in the albedo treatment (**c+d**) lead to a noticeable improvement of the results (ranging between +4.5% and +7%). Nevertheless, in this case, the largest improvements (greater than 5% for all the observational datasets) are obtained for experiment **j**, in which the type of the hydraulic lower boundary accounts for ground water with drainage and diffusion. ~~In the combined configurations~~Combining

the configuration changes of different experiments (right side of Fig. 6-7) the results for temperature are considerably improved, whenever either one of the configuration-setup changes of experiments **d** or **j** are used, with values of SS larger than 4% in almost all the cases. Other "combined" experiments do not have an important effect on the results.

For precipitation-PRE (middle row in Fig. 67), only the results of one experiment, among the ones with single changes in the model configuration, are improved compared to the reference: experiment **d** (SS= \sim +4%), in which the albedo is modified considering the forest fraction. The positive effect of this change is slightly enhanced when used jointly with other configuration choices (experiments **m,n,o,p,q**), having indeed an important effect on precipitation.

As for precipitation-PRE, also for diurnal-temperature-range-DTR (Fig. 67, bottom row) only one experiment seems to sensibly improve over the results of the reference simulation: experiment **i** (SS ranging between +4% and +5%). In this experiment, the soil heat conductivity takes into account the ratio of soil moisture to soil ice. For DTR, two experiments, **d** and **j**, lead to particularly negative skills (SS between -4% and -5%), which also affect the combined experiments including these configurationstheir configuration changes. The unique exception is the combined experiment **q**: in this case, the negative effects on the simulation of DTR of the parameterizations employed in experiment **d**, seem to be compensated by the positive ones of experiment **i**, resulting in positive values of SS, varying between +1% and +2%.

In summary, the presented analyses show that the combined representation of surface albedo (taking into account forest fraction) and soil heat conductivity (accounting for the ratio between ice and moisture in the soil) (exp. as configured in experiment q), has the best positive effects on the representation of the mean seasonal cycle of all the three considered variables, among all the tested configurations.

Although some differences in the results of the SS calculated based on the different observational datasets are evident, experiment **q** shows the same positive sign of improvement in all the cases. Additionally, the ranges of improvement obtained with configuration This is also true when comparing the results obtained driving the same simulations q with respect to and a when using ERA-Interim as boundary conditions, reported in table 4, are similar as when using with NCEP2 as drivers. These results support and ERA-Interim reanalysis data (Tab. 4). This confirms the potential of experiment **q** in improving model performances for the area.

3.1.2 SS - Sub-domains

The same SS analysis-analyses for the mean seasonal cycle is-are conducted for sub-regions characterized by similar climate conditions. This allows to test the model sensitivity for regions where different physical processes might play a different role. The analyses presented in Fig. 8 are conducted, as in the case of the entire domain, separately for different observational datasets. Here, for visualization reasons, the magnitude of changes in the SS is only reported for a reference dataset for each variable, being the CRU for T2M and DTR and the GPCC for PRE. At the same time, for each experiment and subregion where the sign of changes in SS is the same among the different observations, a point is drawn.

Fig. 8 basically confirms the results of the SS calculated for the entire domain. For the experiments with single changes in the reference model configuration it is possible to see that for temperature-T2M (upper panel), the most relevant SS changes are obtained for experiment **d** and **j**, with improvements exceeding 30% over some region. For precipitation-PRE (middle panel),

improvements over all the clusters are obtained only for experiment **d**, and positive SS values are evident only for few other experiments for specific sub-domains. In this case, changes in SS are smaller than for ~~temperature~~T2M, rarely exceeding 10%. For ~~the diurnal temperature range~~DTR, experiment **i** allows to achieve improvement in model performances up to 25% with respect to the reference simulation, not visible in the other cases, for almost all the sub-domains.

5 Among the combined experiments (right side of each panel of Fig. 8), it is possible to affirm that experiments **m** and **q** present similar ~~performance~~performances for T2M and PRE. Conversely, only experiment **q** shows an important improvement in model ~~performance~~performances on more than one subdomain for DTR .

~~One important conclusion that can be drawn from~~ Fig. 8 ~~is~~ shows that it is almost impossible to achieve an improvement ~~of model performance~~in model performances for all regions and variables. Despite experiment **q** presents positive SS values
10 for a large majority of sub-domains, some negative values are also evident for specific sub-regions. This also happens when considering different variables. For example, for experiment **d**, improvements over the entire domain are evident for T2M and PRE, while the same setup leads to worse model performances in terms of DTR, for almost the entire domain. Therefore, even though important improvements are obtained in different cases, it is crucial to highlight the fact that these might be ~~a~~the product of some compensation effect over different variables and domain sub-regions.

15 3.1.3 SS - Single Seasons

The same SS analyses are additionally conducted for the monthly climatologies of each season, over the entire domain. Seasonal analyses could help in discriminating simulations presenting good and coherent performances over more periods of the year. The results, reported in the supplementary section of this paper, show that the largest changes in the seasonal values of SS are obtained for summer, for processes related to the representation of surface and soil properties. On the other hand, in
20 winter the changes in model performances among the different experiments are substantially smaller than in the other seasons. Overall, for single seasons, the most important and consistent improvements in the simulated climatological mean of the considered variables with respect to the reference simulation are obtained for experiment **q**, confirming the results obtained for the seasonal cycle.

3.1.4 Effects of Soil Depth and Snow Model on mean winter temperatures

25 The two simulations (**SOIL** and **SNOW**) specifically designed for testing the effects of changes in soil depth and the use of a multi-layer snow model on the COSMO-CLM simulation of ~~near surface temperature~~T2M over areas characterized by the presence of permafrost and snow in winter, do not present significantly different results than the reference simulation (Fig. 8). ~~Larger differences are evident for the experiment SNOW. Nevertheless, this configuration leads to even warmer conditions in winter with respect to 9). In particular, they do not allow to reduce the warm bias in T2M present for~~ the reference simulation .
30 ~~This further demarcates the model limits, highlighting the need to channel more efforts into the development of COSMO-CLM, trying to better represent snow and soil permafrost processes over cold areas. in winter over the Western Siberia part of the domain, with even warmer conditions simulated by experiment SNOW (Fig. 9, left).~~

3.2 Variability

In this section, the results of the analysis of simulated variance is presented, with the goal of complementing the analyses of the mean climate ~~in of~~ Sec. 3.1. First, a general overview of the model skill in simulating observational variability is described, followed by a discussion of the different uncertainties affecting this metrics.

5 Fig. 8-10 shows the ratio of variance of the different ~~ECLM-COSMO-CLM~~ experiments with respect to the one of the observations. The variances are calculated from monthly anomalies values of the three considered variables averaged over the subregions shown in Fig. 2-3 (see also Sec. 2.3). For ~~Visualization-visualization~~ reasons, a single observational dataset is used for each of the considered variables in this case: CRU for T2M and DTR, and GPCC for PRE. The results of the comparison against other observational datasets are considered when discussing different sources of uncertainties in Sec. 3.2.1.

10 In general, for DTR and T2M, there are no ~~big-large~~ differences in the variance ratios of all the experiments, except for a few sub-regions. For ~~precipitationPRE~~, conditions are more heterogeneous, with relatively large differences among all the simulations. Nevertheless, the most pronounced changes are still limited to a few clusters.

For T2M, the best results in terms of simulated variance are obtained: the model is able to reproduce the interannual variability of the observations particularly well. In particular, a good agreement between simulated data and observations is evident
15 for subregions ~~WSHWSC~~, ~~IMO~~ and ~~ARC~~. The largest underestimation of the observed variance of ~~temperature-T2M~~ is obtained for cluster ~~CSA~~. Therefore, the model is not only unable to simulate the mean temperatures ~~for areas characterized by particularly low climatological values of particularly cold areas~~, as demonstrated in Sec. 3.1, but it also shows a very low variability for the same ~~regions-variable, over these regions~~, when compared to observations. A ~~negative-particularly small~~ value of the variance ratio is also evident for ~~temperature-T2M~~ for the sub-domains ~~DSS~~, ~~SAR~~ and ~~STE~~ throughout almost all
20 the experiments. These regions are all ~~charaeheterized-characterized~~ by a large range between minimum and maximum monthly temperatures (see Tab. 3).

For ~~precipitationPRE~~, in general, the values of the ratio of simulated-to-observed variance are considerably larger than 1 for almost all the experiments and subdomains. Values are closer to 1 only for the domains ~~WSC~~ and ~~DHS~~ throughout all the experiments. In the domains ~~CSA~~, ~~DSS~~ and ~~TIB~~, variance ratios are particularly ~~large, reaching +remarkable, reaching a value~~
25 ~~of 3 in some cases for some experiment~~. Over these domains, characterized by ~~high-complex~~ topography, results from Sec. 3.1 have shown that the model simulates significantly wetter conditions. Hence, for ~~mountainous-mountainous~~ areas of the domain the model overestimates both mean values and variability of precipitation.

Values of variance ratios for DTR are smaller than 1 over almost all the subdomains and simulations. This indicates that the model, beside underestimating climatological values of the observed temperature diurnal cycle over the entire Central Asia
30 domain as demonstrated in Sec. 3.1, also undererestimates the amplitude of variations in the monthly means.

3.2.1 Uncertainties in the Investigation of Simulated Variability

In this section, the influence of uncertainties associated with the observational datasets, boundary data and internal variability on the evaluation of simulated variability are quantified. To investigate the effect of ~~the model~~ internal variability, four additional

simulations have been conducted using the setup of the reference simulation, but shifting the initial date by +/- 1 and +/-3 months.

Left columns of each panel of Fig. 9-11 show the absolute differences in the variance ratio of experiment **a** calculated, for each variable, with respect to different observational datasets. In addition, the right columns of the same figure show the absolute differences in the variance ratio between experiment **a** and the other experiments. The range of changes in the two cases is comparable for almost all clusters and variables. In many cases, the changes resulting from the use of different observations are larger than the differences between the experiments. In these cases, the observational uncertainty is thus too large to allow for a classification of the different experiments in terms of their skill in reproducing the observed variance. The influence of the observational datasets on the variance ratios is larger for PRE and DTR than for T2M.

Despite variations in the boundary data and in the simulated internal variability (as quantified in the additional experiments with shifted initial dates) do not have the same strong effect on the simulated variance ratio as the observational uncertainties, for some regions their values are still comparable to the differences between the simulations (not shown).

In ~~conclusion~~ conclusion, the fact that different uncertainties are in the same order of magnitude as the differences between the simulations does not allow for a classification of the different experiments with respect to their skill in representing the observed variability.

4 Discussion and Conclusions

The main goal of this work is to evaluate a set of different configuration setups of the regional climate model COSMO-CLM over the CORDEX Central Asia domain, and to isolate different sources of uncertainties, in order to quantify general model performances and to provide a basis for possible improvements of the model simulations for this region. The results of this study are of fundamental importance in the light of the next phase of the CORDEX ~~initiative~~ initiative, in particular considering the vulnerability of the region to the possible effects of climate change.

Concerning the simulation of the mean climate, the model shows remarkable deficiencies in simulating the three considered variables (~~2-meter~~ near surface temperature, precipitation and diurnal temperature range) over different areas of Central Asia and different seasons. Even though over specific areas of the domain these biases are hard to be quantitatively assessed, due to high uncertainties in the considered observational datasets, ~~the spatial pattern of the evinced biases~~ their spatial pattern is similar in all the cases.

For temperature, large positive model biases are present in winter over Siberia, with remarkable values exceeding +10°C in some cases. There are two likely reasons for these biases: an unsatisfactory representation of snow cover and soil permafrost. In fact, both these factors have a significant impact on heat transport within the soil and heat flux between soil and atmosphere, with important effects on near surface temperatures (Frauenfeld et al., 2004; Lachenbruch and Marshall, 1986; Saito et al., 2007; Klehmet, 2014). Siberian permafrost often exceeds a depth of 100 meters, reaching values of up to 1km (Yershov, 2004). Therefore, many studies (Alexeev et al., 2007; Dankers et al., 2011; Nicolsky et al., 2007; Lawrence et al., 2008; Saito et al., 2007; Klehmet, 2014) highlight the importance of an adequate depth of model soil layers for the proper representation of

processes related to permafrost. At the same time, other studies (Saito et al., 2007; Waliser et al., 2011; Klehmet, 2014) suggest that a better representation of the vertical stratification of the snow pack could have a significant effect on the simulated energy budget and, consequently, on near surface temperatures over the area. Following these hypotheses, two 25-year long additional simulations have been conducted during this study, with an increase of the total model soil depth and with the use of a multi-layer snow model. Results indicate that, for the part of Siberia included in the domain of study, no significant changes are evident in the two cases ~~and further tests are indeed necessary~~. This further demarcates model limitations, pointing to a structural problem in the model formulation and to the need of new parameterizations for the simulation of processes related to snow cover and permafrost in COSMO-CLM. Importantly, an additional cold bias, in some cases lower than -10°C , is present for every season over the Tibetan Plateau. Other regional climate models suffer from a similar bias (GUO et al., 2018; Meng et al., 2018). Acknowledging the fact that for this area the observational uncertainty is particularly high, the evinced biases could partly be related to a bad representation of the albedo for highly complex topographies. In fact, a study by Meng et al. (2018) showed that changes in the albedo over the region have led to an important improvement of the results of an RCM. Another possible explanation for this cold bias might be the parametrization of surface fluxes (Zhuo et al., 2016). Consequently, further analyses should focus on improving the mode representation of these processes.

For precipitation, particularly wet conditions are simulated by the COSMO-CLM over the Tibetan Plateau. This bias seems to be common to several RCMs for areas characterized by complex topography (GUO et al., 2018; Gao et al., 2015; Feng and Fu, 2006) and is likely related to an overestimation of orographic precipitation enhancement in the models (Gerber et al., 2018) and/or to an incorrect simulation of the planetary boundary layer (Xu et al., 2016). Additionally, in the COSMO-CLM simulations a significant dry bias occurs over arid and desertic regions, especially in summer. A similar COSMO-CLM bias has already been seen for other semi-arid and dry regions of the World, such as the Mediterranean region. In this case, it was connected with an incorrect simulation of soil-atmosphere interactions by the model (Fischer et al., 2007; Seneviratne et al., 2010; Russo and Cubasch, 2016), which is likely the case also for Central Asia. For both the Tibetan Plateau and arid summer areas, it is important to note that the biases are in the same order of the spread of the observations.

~~For DTR, the~~ The model underestimates the climatological mean of the diurnal cycle of temperatures, for all the seasons and sub-regions of the domain. This bias is relatively homogeneous over the entire domain of study. Several studies have shown that RCMs typically underestimate ~~DTR~~ diurnal temperature ranges over different parts of the World (Kyselý and Plavcová, 2012; Mearns et al., 1995; Laprise et al., 2003). The main factors responsible for these deficiencies seem to be errors in the simulation of the atmospheric circulation, cloud cover and heat and moisture fluxes between surface and atmosphere.

The evinced model limitations for the mean climate do not seem to differ significantly when considering ERAInterim as driving data and a different timestep.

In order to test whether it is possible to reduce the determined model biases, and to which degree, sensitivity experiments have been performed to study the effect of different ~~physical parameterizations~~ changes in the configuration of COSMO-CLM and their mutual interaction. After considering different sources of uncertainties, the combined change of the albedo taking into consideration the ratio of forest fractions and the soil conductivity taking into account the ratio of liquid water and ice in the soil, leads to the best results in simulated climatological means of the three considered variables (experiment q). Importantly,

the model seems to be particularly sensitive to those parameterizations that deal with soil and surface features, and that could positively affect the repartition of incoming radiation.

An analysis of model ~~performanee~~ performances in simulating climatological means per sub-regions characterized by similar physical processes shows that ~~the use of different~~ different model configurations may lead to improvements ~~of up to~~ 35 ~~exceeding 30% in some cases~~ over some region. The analysis for sub-regions is coherent with the SS analyses conducted over the entire domain, with experiment **q** presenting the best performances over the largest majority of regions, for all variables, in the two cases. Nevertheless, sub-regions analyses show that improvements in model ~~performanee~~ performances are not homogeneous among all the sub-regions and variables, but they are the result of some compensation effect in the different cases.

The investigation of ~~the model performanee for model performances for the simulation of~~ seasonal climatologies confirms the results obtained for the seasonal cycle, with experiment q leading to the best and most consistent results among all the seasons. For all the analyzed variables, winter is the season for which no substantial improvements in model results ~~could~~ can be achieved with the set of investigated configurations. This ~~points to an important role of other factors for the winter climatology, such as~~ suggests that other factors, playing a crucial role for the simulation of ~~snow cover, that are not affected by~~ the investigated parameters Central Asia winter climate, are not properly considered in COSMO-CLM.

The model improvements in the simulation of climatological means, with the same optimal configuration, are very similar when considering different observational datasets, and ERAInterim instead of NCEP2 as drivers.

Finally, the observed variability of temperature is relatively well represented in the model simulations for different sub-regions of the domain. For precipitation, the model overestimates the variability of observations. On the contrary, the model underestimates the variability in the diurnal cycle of temperatures over the entire region. Among the three investigated variables, only for precipitation there are significant changes in the simulated variance throughout all conducted experiments. However, due to the large uncertainties in the variability estimates from observations, the use of different boundaries and the model internal variability, it has not been possible to rank the different simulations according to their representation of the monthly variability.

Code and data availability. All the data upon which this research is based are available through personal communication with the authors. The code used for the postprocessing of model results is available at:

<https://doi.org/10.5281/zenodo.3469945>

Author contributions. The simulations of this research were performed by ER. All the authors equally contributed to the discussion of the results. The paper structure as well as most of the presented experiments were designed by ER and IK. All authors gave a substantial contribute to the revision of the text and to the formatting of the paper.

Competing interests. No competing interests are present in the paper.

Acknowledgements. This study was funded by the Federal Ministry of Education and Research of Germany (BMBF) as part of the CAME II project (Central Asia: Climatic Tipping Points & Their Consequences), project number 03G0863G.

The computational resources necessary for conducting the experiments presented in this research were made available by the German
5 Climate Computing Center (DKRZ).

The authors are also particularly grateful to the CLM community for all their efforts in developing the COSMO-CLM model and making its code available.

References

- Airey, M. and Hulme, M.: Evaluating climate model simulations of precipitation: methods, problems and performance, *Progress in Physical Geography*, 19, 427–448, 1995.
- Alexeev, V., Nicolsky, D., Romanovsky, V., and Lawrence, D.: An evaluation of deep soil configurations in the CLM3 for improved representation of permafrost, *Geophysical Research Letters*, 34, 2007.
- 5 Avgoustoglou, E., Voudouri, A., Khain, P., Grazzini, F., and Bettems, J.: Design and Evaluation of Sensitivity Tests of COSMO Model Over the Mediterranean Area, in: *Perspectives on Atmospheric Sciences*, pp. 49–54, Springer, 2017.
- Awan, N., Truhetz, H., and Gobiet, A.: Parameterization-induced error characteristics of MM5 and WRF operated in climate mode over the Alpine region: an ensemble-based analysis, *Journal of Climate*, 24, 3107–3123, 2011.
- 10 Bachner, S., Kapala, A., and Simmer, C.: Evaluation of daily precipitation characteristics in the CLM and their sensitivity to parameterizations, *Meteorologische Zeitschrift*, 17, 407–419, 2008.
- Ball, G. and Hall Dj, I.: A novel method of data analysis and pattern classification. *Isodata, A novel method of data analysis and pattern classification*. Tch. Report 5RI, Project 5533, 1965.
- Becker, A., Finger, P., Meyer-Christoffer, A., Rudolf, B., and Ziese, M.: GPCP full data reanalysis version 7.0 at 0.5: Monthly land-surface precipitation from rain-gauges built on GTS-based and historic data, 2011.
- 15 Bellprat, O., Kotlarski, S., Lüthi, D., and Schär, C.: Exploring perturbed physics ensembles in a regional climate model, *Journal of Climate*, 25, 4582–4599, 2012a.
- Bellprat, O., Kotlarski, S., Lüthi, D., and Schär, C.: Objective calibration of regional climate models, *Journal of Geophysical Research: Atmospheres*, 117, 2012b.
- 20 Bellprat, O., Kotlarski, S., Lüthi, D., De Elía, R., Frigon, A., Laprise, R., and Schär, C.: Objective calibration of regional climate models: application over Europe and North America, *Journal of Climate*, 29, 819–838, 2016.
- Bentsen, M., Bethke, I., Debernard, J., Iversen, T., Kirkevåg, A., Seland, O., Drange, H., Roelandt, C., Seierstad, I., Hoose, C., and Kristjánsson, J.: The Norwegian Earth System Model, NorESM1-M – Part 1: Description and basic evaluation of the physical climate, *Geoscientific Model Development*, 6, 687–720, <https://doi.org/10.5194/gmd-6-687-2013>, <https://www.geosci-model-dev.net/6/687/2013/>, 2013.
- 25 Borge, R., Alexandrov, V., Del Vas, J., Lumberras, J., and Rodriguez, E.: A comprehensive sensitivity analysis of the WRF model for air quality applications over the Iberian Peninsula, *Atmospheric Environment*, 42, 8560–8574, 2008.
- Bucchignani, E., Mercogliano, P., Montesarchio, M., Zollo, A., and Manzi, M.: Prearrangement of the COSMO-CLM Model on the Chinese region and sensitivity analysis, *CMCC Research Paper*, 2012.
- Bucchignani, E., Montesarchio, M., Cattaneo, L., Manzi, M. P., and Mercogliano, P.: Regional climate modeling over China with COSMO-CLM: Performance assessment and climate projections, *Journal of Geophysical Research: Atmospheres*, 119, 12–151, 2014.
- 30 Bucchignani, E., Cattaneo, L., Panitz, H., and Mercogliano, P.: Sensitivity analysis with the regional climate model COSMO-CLM over the CORDEX-MENA domain, *Meteorology and Atmospheric Physics*, 128, 73–95, 2016.
- Chuluunkhuyag, S.: The impact of climate change and human activity on Mongolian water resources, in: *International water conference paper*, 2008.
- 35 Collins, M., AchutaRao, K., Ashok, K., Bhandari, S., Mitra, A., Prakash, S., Srivastava, R., and Turner, A.: Observational challenges in evaluating climate models, *Nature Climate Change*, 3, 940, 2013.

- Crétat, J., Pohl, B., Richard, Y., and Drobinski, P.: Uncertainties in simulating regional climate of Southern Africa: sensitivity to physical parameterizations using WRF, *Climate dynamics*, 38, 613–634, 2012.
- Dankers, R., Burke, E., and Price, J.: Simulation of permafrost and seasonal thaw depth in the JULES land surface scheme, *The Cryosphere*, 5, 773–790, 2011.
- 5 Davies, H.: A lateral boundary formulation for multi-level prediction models, *Quarterly Journal of the Royal Meteorological Society*, 102, 405–418, 1976.
- de Elía, R., Caya, D., Côté, H., Frigon, A., Biner, S., Giguère, M., Paquin, D., Harvey, R., and Plummer, D.: Evaluation of uncertainties in the CRCM-simulated North American climate, *Climate Dynamics*, 30, 113–132, 2008.
- Dee, D., Uppala, S., Simmons, A., Berrisford, P., Poli, P., Kobayashi, S., Andrae, U., Balmaseda, M., Balsamo, G., Bauer, d., et al.: The
10 ERA-Interim reanalysis: Configuration and performance of the data assimilation system, *Quarterly Journal of the royal meteorological society*, 137, 553–597, 2011.
- Dentener, F., Kinne, S., Bond, T., Boucher, O., Cofala, J., Generoso, S., Ginoux, P., Gong, S., Hoelzemann, J., Ito, A., et al.: Emissions of primary aerosol and precursor gases in the years 2000 and 1750 prescribed data-sets for AeroCom, *Atmospheric Chemistry and Physics*, 6, 4321–4344, 2006.
- 15 Diniega, R.: *The Effect of Climate Change on Mongolian Herding Communities: Investigating the Current Prevalence of Ecomigration and Community Perceptions of and Responses to Migration in the Countryside*, 2012.
- Diro, G., Rauscher, S., Giorgi, F., and Tompkins, A.: Sensitivity of seasonal climate and diurnal precipitation over Central America to land and sea surface schemes in RegCM4, *Climate Research*, 52, 31–48, 2012.
- Dobler, A. and Ahrens, B.: Analysis of the Indian summer monsoon system in the regional climate model COSMO-CLM, *Journal of Geo-
20 physical Research: Atmospheres*, 115, 2010.
- Dong, S. and Sun, Y.: Comparisons of observational data sets for evaluating the CMIP5 precipitation extreme simulations over Asia, *Climate Research*, 76, 161–176, 2018.
- Evans, J., Ekström, M., and Ji, F.: Evaluating the performance of a WRF physics ensemble over South-East Australia, *Climate Dynamics*, 39, 1241–1258, 2012.
- 25 Feng, J. and Fu, C.: Inter-comparison of 10-year precipitation simulated by several RCMs for Asia, *Advances in atmospheric sciences*, 23, 531–542, 2006.
- Fernández, J., Montávez, J., Sáenz, J., González-Rouco, J., and Zorita, E.: Sensitivity of the MM5 mesoscale model to physical parameterizations for regional climate studies: Annual cycle, *Journal of Geophysical Research: Atmospheres*, 112, 2007.
- Fischer, E., Seneviratne, S., Lüthi, D., and Schär, C.: Contribution of land-atmosphere coupling to recent European summer heat waves,
30 *Geophysical Research Letters*, 34, 2007.
- Flaounas, E., Drobinski, P., Borga, M., Calvet, J., Delrieu, G., Morin, E., Tartari, G., and Toffolon, R.: Assessment of gridded observations used for climate model validation in the Mediterranean region: the HyMeX and MED-CORDEX framework, *Environmental Research Letters*, 7, 024017, 2012.
- Flato, G., Marotzke, J., Abiodun, B., Braconnot, P., Chou, S. C., Collins, W. J., Cox, P., Driouech, F., Emori, S., Eyring, V., et al.: Evaluation
35 of climate models. In: *climate change 2013: the physical science basis. Contribution of working group I to the fifth assessment report of the intergovernmental panel on climate change*, *Climate Change 2013*, 5, 741–866, 2013.
- Frauenfeld, O., Zhang, T., Barry, R., and Gilichinsky, D.: Interdecadal changes in seasonal freeze and thaw depths in Russia, *Journal of Geophysical Research: Atmospheres*, 109, 2004.

- Gao, Y., Xu, J., and Chen, D.: Evaluation of WRF mesoscale climate simulations over the Tibetan Plateau during 1979–2011, *Journal of Climate*, 28, 2823–2841, 2015.
- García-Díez, M., Fernández, J., Fita, L., and Yagüe, C.: Seasonal dependence of WRF model biases and sensitivity to PBL schemes over Europe, *Quarterly Journal of the Royal Meteorological Society*, 139, 501–514, 2013.
- 5 Gelaro, R., McCarty, W., Suárez, M., Todling, R., Molod, A., Takacs, L., Randles, C., Darmenov, A., Bosilovich, M., Reichle, R., et al.: The modern-era retrospective analysis for research and applications, version 2 (MERRA-2), *Journal of Climate*, 30, 5419–5454, 2017.
- Gerber, F., Besic, N., Sharma, V., Mott, R., Daniels, M., Gabella, M., Berne, A., Germann, U., and Lehning, M.: Spatial variability in snow precipitation and accumulation in COSMO–WRF simulations and radar estimations over complex terrain, *The Cryosphere*, 12, 3137–3160, 2018.
- 10 Giorgetta, M., Jungclaus, J., Reick, C., Legutke, S., Bader, J., Böttinger, M., Brovkin, V., Crueger, T., Esch, M., Fieg, K., et al.: Climate and carbon cycle changes from 1850 to 2100 in MPI-ESM simulations for the Coupled Model Intercomparison Project phase 5, *Journal of Advances in Modeling Earth Systems*, 5, 572–597, 2013.
- Giorgi, F., Jones, C., Asrar, G., et al.: Addressing climate information needs at the regional level: the CORDEX framework, *World Meteorological Organization (WMO) Bulletin*, 58, 175, 2009.
- 15 Giorgi, F., Coppola, E., Solmon, F., Mariotti, L., Sylla, M., Bi, X., Elguindi, N., Diro, G., Nair, V., Giuliani, G., et al.: RegCM4: model description and preliminary tests over multiple CORDEX domains, *Climate Research*, 52, 7–29, 2012.
- Gleckler, P. J., Taylor, K. E., and Doutriaux, C.: Performance metrics for climate models, *Journal of Geophysical Research: Atmospheres*, 113, 2008.
- Gómez-Navarro, J., Montávez, J., Jerez, S., Jiménez-Guerrero, P., and Zorita, E.: What is the role of the observational dataset in the evaluation and scoring of climate models?, *Geophysical Research Letters*, 39, 2012.
- 20 GUO, D., SUN, J., and YU, E.: Evaluation of CORDEX regional climate models in simulating temperature and precipitation over the Tibetan Plateau, *Atmospheric and Oceanic Science Letters*, pp. 1–9, 2018.
- Gutowski Jr, W. J., Giorgi, F., Timbal, B., Frigon, A., Jacob, D., Kang, H.-S., Raghavan, K., Lee, B., Lennard, C., Nikulin, G., et al.: WCRP coordinated regional downscaling experiment (CORDEX): a diagnostic MIP for CMIP6, *Geoscientific Model Development*, 9, 4087, 2016.
- 25 Harris, I. and Jones, P.: CRU TS4.01: Climatic Research Unit (CRU) Time-Series (TS) version 4.01 of high-resolution gridded data of month-by-month variation in climate (Jan. 1901- Dec. 2016), available from <http://catalogue.ceda.ac.uk/uuid/58a8802721c94c66ae45c3baa4d814d0>, 2017.
- Hourdin, F., Mauritsen, T., Gettelman, A., Golaz, J.-C., Balaji, V., Duan, Q., Folini, D., Ji, D., Klocke, D., Qian, Y., et al.: The art and science of climate model tuning, *Bulletin of the American Meteorological Society*, 98, 589–602, 2017.
- 30 Huang, B., Polanski, S., and Cubasch, U.: Assessment of precipitation climatology in an ensemble of CORDEX-East Asia regional climate simulations, *Climate Research*, 64, 141–158, 2015.
- Iversen, T., Bentsen, M., Bethke, I., Debernard, J., Kirkevåg, A., Seland, O., Drange, H., Kristjansson, J., Medhaug, I., Sand, M., and Seierstad, I.: The Norwegian Earth System Model, NorESM1-M – Part 2: Climate response and scenario projections, *Geoscientific Model Development*, 6, 389–415, <https://doi.org/10.5194/gmd-6-389-2013>, <https://www.geosci-model-dev.net/6/389/2013/>, 2013.
- 35 Jacob, D., Barring, L., Christensen, O., Christensen, J., De Castro, M., Deque, M., Giorgi, F., Hagemann, S., Hirschi, M., Jones, R., et al.: An inter-comparison of regional climate models for Europe: model performance in present-day climate, *Climatic change*, 81, 31–52, 2007.

- Jacob, D., Elizalde, A., Haensler, A., Hagemann, S., Kumar, P., Podzun, R., Rechid, D., Remedio, A., Saeed, F., Sieck, K., et al.: Assessing the transferability of the regional climate model REMO to different coordinated regional climate downscaling experiment (CORDEX) regions, *Atmosphere*, 3, 181–199, 2012.
- Jacob, D., Petersen, J., Eggert, B., Alias, A., Christensen, O., Bouwer, L., Braun, A., Colette, A., Déqué, M., Georgievski, G., et al.: EURO-CORDEX: new high-resolution climate change projections for European impact research, *Regional Environmental Change*, 14, 563–578, 2014.
- Jain, A. K.: Data clustering: 50 years beyond K-means, *Pattern recognition letters*, 31, 651–666, 2010.
- Kanamitsu, M., Ebisuzaki, W., Woollen, J., Yang, S., Hnilo, J., Fiorino, M., and Potter, G.: Ncep–doe amip-ii reanalysis (r-2), *Bulletin of the American Meteorological Society*, 83, 1631–1643, 2002.
- 10 Kim, J. and Lee, J.-E.: A multiyear regional climate hindcast for the Western United States using the mesoscale atmospheric simulation model, *Journal of Hydrometeorology*, 4, 878–890, 2003.
- Kim, J., Waliser, D. E., Mattmann, C. A., Goodale, C. E., Hart, A. F., Zimdars, P. A., Crichton, D. J., Jones, C., Nikulin, G., Hewitson, B., et al.: Evaluation of the CORDEX-Africa multi-RCM hindcast: systematic model errors, *Climate dynamics*, 42, 1189–1202, 2014.
- Klehmet, K.: A model-based reconstruction of recent Siberian climate-focusing on snow cover, Ph.D. thesis, Universität Hamburg Hamburg, 15 2014.
- Køltzow, M. A. Ø.: Abilities and limitations in the use of Regional Climate Models, 2012.
- Kotlarski, S., Keuler, K., Christensen, O., Colette, A., Déqué, M., Gobiet, A., Goergen, K., Jacob, D., Lüthi, D., Van Meijgaard, E., et al.: Regional climate modeling on European scales: a joint standard evaluation of the EURO-CORDEX RCM ensemble, *Geoscientific Model Development*, 7, 1297–1333, 2014.
- 20 Kyselý, J. and Plavcová, E.: Biases in the diurnal temperature range in Central Europe in an ensemble of regional climate models and their possible causes, *Climate dynamics*, 39, 1275–1286, 2012.
- Lachenbruch, A. and Marshall, B.: Changing climate: geothermal evidence from permafrost in the Alaskan Arctic, *Science*, 234, 689–696, 1986.
- Lange, S., Rockel, B., Volkholz, J., and Bookhagen, B.: Regional climate model sensitivities to parametrizations of convection and non-precipitating subgrid-scale clouds over South America, *Climate Dynamics*, 44, 2839–2857, 2015.
- 25 Laprise, R., Caya, D., Frigon, A., and Paquin, D.: Current and perturbed climate as simulated by the second-generation Canadian Regional Climate Model (CRCM-II) over northwestern North America, *Climate Dynamics*, 21, 405–421, 2003.
- Lawrence, D., Slater, A., Romanovsky, V., and Nicolsky, D.: Sensitivity of a model projection of near-surface permafrost degradation to soil column depth and representation of soil organic matter, *Journal of Geophysical Research: Earth Surface*, 113, 2008.
- 30 Lenderink, G.: Exploring metrics of extreme daily precipitation in a large ensemble of regional climate model simulations, *Climate Research*, 44, 151–166, 2010.
- Li, D., Yin, B., Feng, J., Dosio, A., Geyer, B., Qi, J., Shi, H., and Xu, Z.: Present Climate Evaluation and Added Value Analysis of Dynamically Downscaled Simulations of CORDEX—East Asia, *Journal of Applied Meteorology and Climatology*, 57, 2317–2341, 2018.
- Lioubimtseva, E. and Henebry, G.: Climate and environmental change in arid Central Asia: Impacts, vulnerability, and adaptations, *Journal of Arid Environments*, 73, 963–977, 2009.
- 35 Lioubimtseva, E., Cole, R., Adams, J., and Kapustin, G.: Impacts of climate and land-cover changes in arid lands of Central Asia, *Journal of Arid Environments*, 62, 285–308, 2005.

- Liu, H., W.A., P., Allen, C., Guo, D., Wu, X., Anenkhonov, O., Liang, E., Sandanov, D., Yin, Y., Qi, Z., et al.: Rapid warming accelerates tree growth decline in semi-arid forests of Inner Asia, *Global change biology*, 19, 2500–2510, 2013.
- Lloyd, S.: Least squares quantization in PCM, *IEEE transactions on information theory*, 28, 129–137, 1982.
- Machulskaya, E.: Description of the multi-layer snow parameterization scheme for ICON and COSMO. Technical Note, available from the author upon request, 2015.
- Macias-Fauria, M., Forbes, B., Zetterberg, P., and Kumpula, T.: Eurasian Arctic greening reveals teleconnections and the potential for structurally novel ecosystems, *Nature Climate Change*, 2, 613, 2012.
- MacQueen, J. et al.: Some methods for classification and analysis of multivariate observations, in: *Proceedings of the fifth Berkeley symposium on mathematical statistics and probability*, vol. 1, pp. 281–297, Oakland, CA, USA, 1967.
- 10 Mannig, B., Müller, M., Starke, E., Merckenschlager, C., Mao, W., Zhi, X., Podzun, R., Jacob, D., and Paeth, H.: Dynamical downscaling of climate change in Central Asia, *Global and planetary change*, 110, 26–39, 2013.
- Matsuura, K. and Wilmott, C.: *The Climate Data Guide: Global (land) precipitation and temperature*: Willmott & Matsuura, University of Delaware, The Climate Data Guide Available at: [climate.%5Cn%5Cgeog.udel.edu/~climate/html_pages/Global2011/5CnREADME.GlobalTsP2011.html](http://climate.geog.udel.edu/~climate/html_pages/Global2011/5CnREADME.GlobalTsP2011.html), 2012.
- 15 McFarlane, N.: *Parameterizations: representing key processes in climate models without resolving them*, *Wiley Interdisciplinary Reviews: Climate Change*, 2, 482–497, 2011.
- Mearns, L., Giorgi, F., McDaniel, L., and Shields, C.: Analysis of variability and diurnal range of daily temperature in a nested regional climate model: Comparison with observations and doubled CO₂ results, *Climate Dynamics*, 11, 193–209, 1995.
- Meng, X., Lyu, S., Zhang, T., Zhao, L., Li, Z., Han, B., Li, S., Ma, D., Chen, H., Ao, Y., et al.: Simulated cold bias being improved by using MODIS time-varying albedo in the Tibetan Plateau in WRF model, *Environmental Research Letters*, 13, 044028, 2018.
- 20 Montesarchio, M., Mercogliano, P., Manzi, M., and Bucchignani, E.: A sensitivity study with the RCM COSMO CLM over the north and center Italy, *CMCC Research Paper*, 2012.
- Nature-Editorial-Board: Validation Required, *Nature*, 2010.
- Naumann, G., Dutra, E., Barbosa, P., Pappenberger, F., Wetterhall, F., and Vogt, J.: Comparison of drought indicators derived from multiple data sets over Africa, *Hydrology and Earth System Sciences*, 18, 1625–1640, 2014.
- 25 Nicolsky, D., Romanovsky, V., Alexeev, V., and Lawrence, D.: Improved modeling of permafrost dynamics in a GCM land-surface scheme, *Geophysical Research Letters*, 34, 2007.
- Nikulin, G., Jones, C., Giorgi, F., Asrar, G., Büchner, M., Cerezo-Mota, R., Christensen, O., Déqué, M., Fernandez, J., Hänsler, A., et al.: Precipitation climatology in an ensemble of CORDEX-Africa regional climate simulations, *Journal of Climate*, 25, 6057–6078, 2012.
- 30 Overpeck, J. T., Meehl, G. A., Bony, S., and Easterling, D. R.: Climate data challenges in the 21st century, *science*, 331, 700–702, 2011.
- Ozturk, T., Altinsoy, H., Türkeş, M., and Kurnaz, M.: Simulation of temperature and precipitation climatology for the Central Asia CORDEX domain using RegCM 4.0, *Climate Research*, 52, 63–76, 2012.
- Ozturk, T., Turp, M., Türkeş, M., and Kurnaz, M.: Projected changes in temperature and precipitation climatology of Central Asia CORDEX Region 8 by using RegCM4. 3.5, *Atmospheric Research*, 183, 296–307, 2017.
- 35 Panitz, H., Dosio, A., Büchner, M., Lüthi, D., and Keuler, K.: COSMO-CLM (CCLM) climate simulations over CORDEX-Africa domain: analysis of the ERA-Interim driven simulations at 0.44 and 0.22 resolution, *Climate dynamics*, 42, 3015–3038, 2014.
- Rajeevan, M., Kesarkar, A., Thampi, S., Rao, T., Radhakrishna, B., and Rajasekhar, M.: Sensitivity of WRF cloud microphysics to simulations of a severe thunderstorm event over Southeast India, in: *Annales Geophysicae*, vol. 28, pp. 603–619, 2010.

- Reboita, M., Fernandez, J., Llopart, M., da Rocha, R., Pampuch, L., and Cruz, F.: Assessment of RegCM4. 3 over the CORDEX South America domain: sensitivity analysis for physical parameterization schemes, *Climate Research*, 60, 215–234, 2014.
- Rockel, B., Will, A., and Hense, A.: The regional climate model COSMO-CLM (CCLM), *Meteorologische Zeitschrift*, 17, 347–348, 2008.
- Rummukainen, M.: State-of-the-art with regional climate models, *Wiley Interdisciplinary Reviews: Climate Change*, 1, 82–96, 2010.
- 5 Russo, E. and Cubasch, U.: Mid-to-late Holocene temperature evolution and atmospheric dynamics over Europe in regional model simulations, *Climate of the Past*, 12, 1645–1662, 2016.
- Saito, K., Kimoto, M., Zhang, T., Takata, K., and Emori, S.: Evaluating a high-resolution climate model: Simulated hydrothermal regimes in frozen ground regions and their change under the global warming scenario, *Journal of Geophysical Research: Earth Surface*, 112, 2007.
- Seneviratne, S., Corti, T., Davin, E., Hirschi, M., Jaeger, E., Lehner, I., Orlowsky, B., and Teuling, A.: Investigating soil moisture–climate interactions in a changing climate: A review, *Earth-Science Reviews*, 99, 125–161, 2010.
- 10 Siegfried, T., Bernauer, T., Guiennet, R., Sellars, S., Robertson, A., Mankin, J., Bauer-Gottwein, P., and Yakovlev, A.: Will climate change exacerbate water stress in Central Asia?, *Climatic Change*, 112, 881–899, 2012.
- Smiatek, G., Helmert, J., and Gerstner, E.: Impact of land use and soil data specifications on COSMO-CLM simulations in the CORDEX-MED area, *Meteorologische Zeitschrift*, 25, 215–230, 2016.
- 15 Solman, S., Sanchez, E., Samuelsson, P., da Rocha, R., Li, L., Marengo, J., Pessacq, N., Remedio, A., Chou, S., Berbery, H., et al.: Evaluation of an ensemble of regional climate model simulations over South America driven by the ERA-Interim reanalysis: model performance and uncertainties, *Climate Dynamics*, 41, 1139–1157, 2013.
- Steinhaus, H.: Sur la division des corp materiels en parties, *Bull. Acad. Polon. Sci*, 1, 801, 1956.
- Suklitsch, M., Gobiet, A., Leuprecht, A., and Frei, C.: High resolution sensitivity studies with the regional climate model CCLM in the Alpine Region, *Meteorologische Zeitschrift*, 17, 467–476, 2008.
- 20 Sun, Q., Miao, C., Duan, Q., Ashouri, H., Sorooshian, S., and Hsu, K.: A review of global precipitation data sets: Data sources, estimation, and intercomparisons, *Reviews of Geophysics*, 56, 79–107, 2018.
- Tegen, I., Hollrig, P., Chin, M., Fung, I., Jacob, D., and Penner, J.: Contribution of different aerosol species to the global aerosol extinction optical thickness: Estimates from model results, *Journal of Geophysical Research: Atmospheres*, 102, 23 895–23 915, 1997.
- 25 The HadGEM2 Development Team: Martin, G., Bellouin, N., Collins, W., Culverwell, I., Halloran, P., Hardiman, S., Hinton, T., Jones, C., McDonald, R., McLaren, A., O’Connor, F., Roberts, M., Rodriguez, J., Woodward, S., Best, M., Brooks, M., Brown, A., Butchart, N., Dearden, C., Derbyshire, S., Dharssi, I., Doutriaux-Boucher, M., Edwards, J., Falloon, P., Gedney, N., Gray, L., Hewitt, H., Hobson, M., Huddleston, M. R., Hughes, J., Ineson, S., Ingram, W., James, P., Johns, T., Johnson, C., Jones, A., Jones, C., Joshi, M., Keen, A., Liddicoat, S., Lock, A., Maidens, A., Manners, J., Milton, S., Rae, J., Ridley, J., Sellar, A., Senior, C., Totterdell, I., Verhoef, A., Vidale, P., and Wiltshire, A.: The HadGEM2 family of Met Office Unified Model climate configurations, *Geoscientific Model Development*, 4, 723–757, <https://doi.org/10.5194/gmd-4-723-2011>, <https://www.geosci-model-dev.net/4/723/2011/>, 2011.
- 30 Umakanth, U. and Kesarkar, A.: Performance evaluation of regional climate model to simulate sub-seasonal variability of Indian Summer Monsoon, *Climate dynamics*, 50, 3595–3612, 2018.
- Voudouri, A., Khain, P., Carmona, I., Avgoustoglou, E., Kaufmann, P., Grazzini, F., and Bettems, J.: Optimization of high resolution COSMO model performance over Switzerland and Northern Italy, *Atmospheric research*, 213, 70–85, 2018.
- Waliser, D., Kim, J., Xue, Y., Chao, Y., Eldering, A., Fovell, R., Hall, A., Li, Q., Liou, K., McWilliams, J., et al.: Simulating cold season snowpack: Impacts of snow albedo and multi-layer snow physics, *Climatic Change*, 109, 95–117, 2011.

- Wang, D., Menz, C., Simon, T., Simmer, C., and Ohlwein, C.: Regional dynamical downscaling with CCLM over East Asia, *Meteorology and Atmospheric Physics*, 121, 39–53, 2013.
- Wang, L., Zeng, Y., and Zhong, L.: Impact of climate change on tourism on the qinghai-tibetan plateau: Research based on a literature review, *Sustainability*, 9, 1539, 2017.
- 5 Wilks, D.: *Statistical Methods in the Atmospheric Sciences* (International Geophysics Series; V. 91), Academic Press, 2006.
- Willmott, C. J.: Terrestrial air temperature and precipitation: Monthly and annual time series (1950-1996), WWW url: http://climate.geog.udel.edu/~climate/html_pages/README_ghcn_ts.html, 2000.
- Xu, G., Xie, Y., Cui, C., Zhou, Z., Li, W., and Xu, J.: Sensitivity of the summer precipitation simulated with WRF model to planetary boundary layer parameterization over the Tibetan Plateau and its downstream areas, *Journal of Geology and Geophysics*, 5, 249, 2016.
- 10 Yershov, E. D.: *General geocryology*, Cambridge university press, 2004.
- Yong-Jian, R., Jiang-Xue, C., Su-Qin, W., Min, L., Zheng-Hong, C., Yu-Fang, L., and Ji-Jun, W.: Climate change impacts on central China and adaptation measures, *Advances in Climate Change Research*, 4, 215–222, 2013.
- Zhen-Feng, M., Jia, L., Shun-Qian, Z., Wen-Xiu, C., and Shu-Qun, Y.: Observed climate changes in southwest China during 1961–2010, *Advances in Climate Change Research*, 4, 30–40, 2013.
- 15 Zhou, W., Tang, J., Wang, X., Wang, S., Niu, X., and Wang, Y.: Evaluation of regional climate simulations over the CORDEX-EA-II domain using the COSMO-CLM model, *Asia-Pacific Journal of Atmospheric Sciences*, 52, 107–127, 2016.
- Zhuo, H., Liu, Y., and Jin, J.: Improvement of land surface temperature simulation over the Tibetan Plateau and the associated impact on circulation in East Asia, *Atmospheric Science Letters*, 17, 162–168, 2016.




Figure 1. Orography map of the Central Asia simulation domain ~~in rotated coordinates,~~ at a spatial resolution of 0.22° lon.




Figure 2. Maps of the spread calculated among different observational datasets, for each considered variable, for the annual (*leftleft*), winter (*middlemiddle*) and summer means (*rightright*). From top to bottom, the values for near surface temperature (T2M, °C), *relative* precipitation (PRE, %) and diurnal temperature range (DTR, °C, bottom panel) are respectively represented.




Figure 3. Map of the 11 subdomains obtained through k-means clustering of the q-normalized monthly climatologies of the three considered variables over the period 1996-2005.




Figure 4. Mean bias of annual mean (*left*), winter mean (*middle*) and summer mean (*right*) near surface temperature (T2M, °C), of the reference COSMO-CLM simulation (**a**) with respect to three observational datasets (from top to bottom: CRU, UDEL and MERRA2), for the period 1995-2005.




Figure 5. Mean bias of annual (*left*), winter (*middle*) and summer mean (*right*) relative precipitation (PRE, %), of the reference COSMO-CLM simulation (**a**) with respect to three observational datasets (from top to bottom: CRU, UDEL and GPCC), for the period 1995-2005.




Figure 6. Mean bias of annual (*left*), winter (*middle*) and summer mean (*right*) diurnal temperature range (DTR, °C), of the reference COSMO-CLM simulation (**a**) with respect to three observational datasets (from top to bottom: CRU, MERRA2 and ERAInterim), for the period 1995-2005.

SS Seasonal Cycle




Figure 7. Skill Score (SS) derived from the MAE calculated over the monthly climatological values of the seasonal cycle of different COSMO-CLM simulations and observational datasets. From top to bottom, the SS for each variable near surface temperature (T2M), precipitation (PRE) and diurnal temperature range (DTR) is respectively displayed. The dotted vertical black line divides the simulations with the same configuration of the reference simulation plus a single change in the model setup (on the left left) and the ones obtained through the combinations of the previous ones (on the right right). Positive (negative) values indicate better (worse) performance performances of the considered simulations compared to the reference one.

Mean bias of near surface temperature (T2M, °C) winter values of the reference simulation **a** and the simulation **SNOW** (*left*) and **SOIL** (*right*), all driven by NCEP2, calculated over the period 2006-2015.

SS - Subdomains




Figure 8. Skill Score (SS) derived from the MAE calculated for each domain sub-region over the monthly climatological values of the seasonal cycle of different COSMO-CLM simulations and observational datasets. From top to bottom, each panel represents the results

BIAS T2M DJF

SNOW-REF

SOIL-REF




Figure 9. [Near surface temperature \(T2M, °C\) winter mean bias calculated with respect to the reference simulation over the period 2006-2015, for the simulations SNOW \(left\) and SOIL \(right\).](#)

Variance Ratio




Figure 10. Fraction of [Variance-variance](#) calculated between the monthly anomalies over the period 1996-2005 derived from the different COSMO-CLM simulations and a single observational dataset, for (top to bottom) [2-meter-for near surface temperature \(T2M\) using the CRU](#), for precipitation ([PRE](#)) using the [GPCC](#) and for diurnal temperature range ([DTR](#)) using the [CRU as observational datasets](#), for each of the 11 sub-regions obtained by k-means clustering. The dotted vertical black line divides the simulations with the same configuration of the reference simulation plus a single change in the model setup ([on-the-leftleft](#)) and the ones obtained through the combinations of the previous ones ([on-the-rightright](#)). Values larger (smaller) than one indicate better (worse) performances of the considered simulations with respect to the reference one, in the representation of observed variability.

Amplitude Variance Ratio Changes OBS vs SIM




Figure 11. Absolute differences in variance ratio. The left column of each panel shows the absolute differences in the variance ratio of the same experiment **a** when considering different observational datasets. The right column of each panel shows the range of absolute differences between the variance ratio of experiment **a** and the [variance ratios](#) of the other experiments, from **b** to **q**, when using a single observational dataset for each variable. Each of the three panels, from left to right, presents, respectively, the results of the comparison for [near surface temperature](#) (T2M), [precipitation](#) (PRE) and [diurnal temperature range](#) (DTR). The different rows show the results [obtained](#) for each of the clusters.

Table 1. List of ~~conducted~~performed experiments and their corresponding configuration.

Experiment	Changes in Model Configuration
a	Reference Simulation - CORDEX South -East Asia setup
b	a+ AeroCom Aerosol Dataset (Dentener et al., 2006) <u>AEROCOM Aerosol Dataset (?)</u>
c	a+ Surface albedo determined as a weighted mean of two external fields for dry and saturated soil
d	a+ Vegetation albedo modified considering forest fraction.
e	a+ Type surface-atmosphere transfer based on prognostic TKE in the surface layer
f	a+ Cloud representation taking into account subgrid-scale condensation; cloud cover and water content calculated according to a statistical closure.
g	a+ Equal to f but cloud cover and water content calculated according to a relative-humidity criterion
h	a+ Exponential root distribution
i	a+ Soil heat conductivity taking into account soil moisture/soil ice
j	a+ Hydraulic lower boundary considering ground water with drainage and diffusion
k	a+e+f+g
l	a+h+i+j
m	a+b+d
n	a+d+h+i+j
o	a+b+d+e+f+g+i
p	a+b+d+e+f+g+h+i+j
q	a+d+i
<u>a</u> - ERAInterim	a driven by ERAInterim
<u>q</u> - ERAInterim	q driven by ERAInterim
<u>TIMESTEP</u>	<u>a+120s Timestep</u>
SOIL	<u>a+</u> increased soil layers number and depth (25-year long)
SNOW	<u>a+</u> increased soil layers number and depth + use of multi-layer snow model (25-year long)
TIMESTEP+120s -Timestep-a2	a with <u>+</u> initial date shifted by +1 month
a3	a with <u>+</u> initial date shifted by +3 month
a4	a with <u>+</u> initial date shifted by -1 month
a5	a with <u>+</u> initial date shifted by -3 month

Table 2. General description of model setup of the reference simulation [Aa](#).

Spatial Resolution	~ 0.22° <u>25 km</u>
Timestep	150s
<u>Domain Extent</u>	<u>326×220 points</u>
Convection	Tiedke
Time Integration	Runge-Kutta,
Lateral Relaxation Layer	250km
Soil Model	TERRA-ML SVAT
Aerosol	TEGEN (?) <u>Tegen (Tegen et al., 1997)</u>
Albedo	function <u>Function</u> of soil type
Rayleigh Damping Layer (rdheight)	≥ 18km
Active Soil Layers	9
Active Soil Depth	5.74m
Atmospheric Vertical Layers	45

Table 3. Sub-regions resulting from the k-means clustering based on climatological monthly means of near surface temperature (T2M, CRU), precipitation (PRE, GPCC) and diurnal temperature range (DTR, CRU) for CORDEX Central Asia. Acronyms are assigned to the different regions corresponding to their main climatic characteristics. Together with the names, mean climatic ~~informations are~~ information is provided for each area. The regions illustrate the wide range of climate zones of the Central Asia domain.

Region	max T2M	min T2M	mean T2M	max PRE	min PRE	mean PRE	max DTR	min DTR	mean DTR
SDT	22.7	0.5	11.8	49.1	10.7	29.5	13.9	8.5	11.4
ARC	12.5	-22.6	-5.5	61.0	22.6	36.0	8.9	4.5	7.0
DSS	18.4	-21.3	-0.3	76.2	4.7	26.4	14.5	11.1	13.0
STE	22.5	-10.1	6.7	31.1	15.2	22.0	13.8	8.5	11.4
CSA	16.8	-33.1	-8.0	55.0	10.1	28.0	15.4	8.2	11.3
WSC	19.3	-5.2	6.7	65.7	30.7	44.4	10.8	5.3	8.3
IMO	22.3	3.3	13.8	152.0	9.8	62.3	11.7	9.0	10.5
SAR	17.8	-17.6	0.0	71.9	26.3	45.3	11.3	6.3	9.1
DCW	21.5	-11.5	6.1	32.9	2.5	12.4	14.5	12.3	13.7
TIB	9.4	-12.5	-1.2	94.4	3.0	35.3	16.4	11.8	14.1
DHS	29.4	9.0	19.9	27.5	3.4	12.7	14.9	11.1	13.3

Table 4. Changes of the SS calculated for the experiment **q** with respect to reference simulation **a**, when both simulations are driven by ERA-Interim (*left*) and NCEP2 (*right*) reanalysis data.

Obs. Dataset	T2M		PRE		DTR	
	ERA-Interim	NCEP2	ERA-Interim	NCEP2	ERA-Interim	NCEP2
CRU	+7.5	+4.9	+3.5	+3.4	+1.8	+1.1
UDEL	+7.3	+5.7	+3.8	+3.5	x	x
GPCC	x	x	+4.1	+3.6	x	x
MERRA2	+11.1	+7.4	x	x	+3.1	+2.4
ERA-Interim	x	x	x	x	+1.5	+1.4